User Manual

Data entry

This manual provides an overview of the various data entry modes and on the data entry from dedicated management window.

Version: 5.3.SP36

Wolters Kluwer

CCH® Tagetik

wolterskluwer.com

Table of contents

Data Entry 1

Data Entry and its rules 2

Data entry modes 2
Data entry rules 3
Amount & Intercompany rules page 3
Journal rules and settings page 7
Default Settings window 9
Categories for draft journals page 10

Amounts 11

Amounts 11
Gross Amounts page 12
IC Amounts (Show IC declarations) page 15
Balancing page 16
IC amounts page 17
Delete IC error signs algorithm 21

Journals 22

Journals 22
Entity journals 23
Consolidation journals 24
Draft journals 24
Headers (Entity Journals) page 29
Rows (Entity Journals) page 34
Headers (Consolidation journals) page 37
Rows (Consolidation journals) page 46
Actions from journal headers 51
Documents page 54
Consolidation scenario page 55
Periodic Management page 56
Overridden FX rates page 57
Submit from workflow page 58
Journal log 59

Copy window 60
Edit category window 61
Actions from the journal rows 62
Original and consolidated rows page 64
Control group balancing 68
Control Group Balancing page 68
Drill down on control groups page 70

Overrides on amounts and journals 74

Override journals and amounts 74
Override on the consolidation scenario - Proportional page 75
Override on the consolidation scenario - Converted and Consolidable page 76
Override journals on the original scenario - Carry forward page 78
Override amounts on the consolidation scenario - Proportional page 79
Override amounts on the consolidation scenario - Converted and consolidable page 79
Override gross amounts on the original scenario - Carry forward on Original scenarios page 80
Override IC amounts on the original scenario - Carry forward on Original scenarios page 80

Reconciliation accounts and Notes 81

Reconciliation accounts 81
Reconciliation accounts page 81
Data entry notes 86
The Edit Notes page 87

Introduction to Reporting 90

The reporting system 91

Reporting: user roles 92
Specific dimensions for reporting 93

Form Design 95

Design: basic concepts 96

Structure of the data in the forms and filters 96
Designing forms 97
Design toolbar 98
Creating forms 99

New form window 102
Batch import window (Import Wizard) 102
Batch export window (Export Wizard) 103
Managing forms 103
Cell fields 105
Cell Fields Wizard 105
Configuring cell fields 106
Validations 106
Configuring validations 107
Validations window 108
Examples of validation 110
Dictionaries 112
Working on dictionary items 113
Form - Import Dictionary window 114
Dictionary Items window 114
Example: importing dictionaries 114

Design: style sheets 118

Tagetik styles 118
Applying style sheets 120
Tagetik style window 121
Styles window 122
Styles window - Defined Styles tab 123
Styles window - Styles to use tab 123
Style settings window (Styles) 125
Defining Tagetik styles 125
Example of the definition of style sheets 126

Design: form structure 132

Structure of a form 132
Multi-template forms 133
Form options window 133
Parameters 136
Types of parameter 138
Working with custom parameters 139

Automatic parameter definition ... 141
Examples of custom parameters ... 141
Parameters Definition window ... 146
Parameters Configuration window ... 149
Advanced selection: scenario and period parameters ... 151
Examples of using dynamic parameters ... 152
Cell editability ... 156
Conditional editability expression window ... 157
Forms grouping ... 158
Working with grouping nodes (Excel add-in) ... 158
Working with grouping nodes (web interface) ... 159
Forms grouping page ... 159
Form groupings page (Structure view) ... 160
Element/node relationships page ... 161
Financial statement templates ... 161
FSTs & KPIs page ... 163
Formulas in financial statement templates ... 165
Standard formula syntax ... 166
How to create a financial statement template ... 167
Setting up a financial statement template ... 168
Particular features of multidimensional formulas ... 170
FST items page ... 171
Relationships page ... 172
Copy From window ... 173
Dashboard reports ... 173
Working with dashboard reports ... 174
Define Dashboard window ... 175
Slicer ... 176
Working with slicers ... 176
New Slicer window ... 176

Design: matrices ... 178

Form matrices ... 178
The Origin dimension ... 180
Sign class ... 180

Headers 181
Setting headers 182
Headers tab 183
Overrides 185
The Override content on cells function 186
Overriding cell content 186
Setting overrides 187
Overrides tab 187
Matrix Wizard - Window structure 187
Dimensions tree in the Matrix Wizard 188
Working in the properties table 190
Table of row/column filter properties 190
Matrix filter properties table 197
Details of FX rate properties 199
Details of Reference FX rate properties 200
Details of Periodic value calculation properties 201
Tagetik style property details 201
Specific features of scenario and period parameter properties 202
Search window 206
Choose the dataset window 206
Matrix options tab 206
Transactional form editor tab 209
Preview window 210
Structure and definition of an advanced selection script 210
Dynamic matrices 211
Creating matrices 213
Managing matrices 214

Design: filters 216

Form filters 216
Form filters window 217
Form filter properties 218
Setting form filters 218
Tab filters 219
Setting tab filters 219

Tab filters window 220
Tab filter properties 222
Tab filter properties table 223
Matrix filters 226
Setting matrix filters 226
Matrix filter properties 227
Matrix Filters tab 227
Row/column filters 229
Set row/column filters 230
Row/column filter properties 231
Row/column filters tab 234
Examples of row/column filter settings 236
Formula filters 237
Managing formulas 240
Predefined filters 240
Working with predefined filters 241
Examples of predefined filter settings 242
Custom filters 243
Custom filters tab 244
The Print Filters function 245
Print Filters Wizard 245
Print Filters examples 246
Generate a filters printout 248
List of filters used window 249

Design: functions 250

Dimensional functions 250
Description of dimensional functions 251
Dimensional attributes 252
Description of the attributes shared by all dimensions 252
Description of attributes for the Entity dimension 256
Description of attributes for the Account dimension 262
Description of attributes for the Scenario dimension 265
Description of attributes for the Period dimension 270
Description of attributes for other dimensions 272

Non-dimensional functions 273
Description of non-dimensional functions 273
Non-dimensional attributes 279
Location functions 283
Description of location functions 283
Aggregation structure navigation functions 286
Description of aggregation structure navigation functions 286
Excel functions 294
Functions on sets 296
Hyperlinks 298
Managing hyperlinks 301
Action List Wizard window 303
The Open form window (Action List Wizard) 304
Properties Window: Filters cycle 306

Data Entry: introduction 308

Data entry forms 308
Data entry in cells 310
Data entry 311
Particular features of forms 312
Spreading 313
Spreading methods in data entry mode 313
Data entry tracking log 315

Data Entry from Excel 316

Data entry in the Excel add-in 316
Data entry toolbar 316
Working with data entry forms in Excel 318
Data Entry panel 319
Setup and Administration Panel - Data Processing 321
Workflow panel 321
Cell edit - Amounts window 323
Cell edit - comments window 325
Working with Cell edit - Comments 327
Cell edit - intercompany window 327

Intercompany report window 329
Edit intercompany: use case 330
Working with spreading 332
Data entry in work off-line mode 333
Work off-line toolbar 333
Working in Work off-line mode 333
Locked data entry forms page 335

Data Entry from Web 336

Forms page 336
The web forms page (data entry) 339
Working with comments and attachments 341
Edit comments page 342
Edit IC page 344
Run data entry in web forms 345
Data processing via hyperlinks in web forms 346
The grouping function 346
Rich Text Editor 349
Working with spreading in web forms 350
Journals Hub 350
Dashboard View 352
Management view 353
Bulkloader view 355

Data Entry

Introduction

Data entry, or the entry of financial statement data in CCH Tagetik, concerns the following types of data:

- original data, i.e. gross amounts and intercompany entries.
- journal data, i.e. entity journals and consolidation journals

To enter these data correctly, the following aspects of the system must be configured:

- data entry rules
- if useful, custom dimension management

Data Entry and its rules

Contents

This section covers the following topics:

Data entry modes 2
Data entry rules 3
Amount & Intercompany rules page 3
Journal rules and settings page 7
Default Settings window 9
Categories for draft journals page 10

Data entry modes

Introduction

The ways in which financial statement data can be loaded to CCH Tagetik are listed below. The various methods can be used in combination. By default, data entry is enabled on all processes.

Data entry from Excel forms

This method allows you to enter data in a guided manner and directly into the CCH Tagetik database using specially prepared Excel spreadsheets.

Procedure

1. Open the form in Data Entry mode (Open a form in data entry mode in the Reporting section).
2. Enter data in editable cells.

   ***Note**: editable cells are highlighted in a specific colour: yellow for cells that can contain gross amounts and green for cells that can contain both gross amounts and intercompany declarations.*

Data entry from web forms

This method allows you to enter data in a guided manner and directly into the CCH Tagetik database using specially prepared web forms.

Procedure

1. Open the data entry form (Open data entry form from cockpit or Open data entry form from Forms tile in the Reporting section).
2. Enter data in editable cells.

   ***Note**: editable cells are highlighted in yellow or a dedicated colour.*

Data entry from data entry windows

This method allows you to enter data completely manually.
It is not recommended for entering an entire financial statement, but is recommended for inserting edits or new journals on financial statement data that have already been loaded.

Procedure

1. Open the data entry form from the cockpit of the desired process (Open data entry form from cockpit in the Reporting section).
2. Select the desired entity or node.

3. From **Actions** > **Edit windows**, select the desired action.
4. Enter data by adding a row and completing the required elements.

Data entry via ETL

You can extract data from external sources, process them and then load them to CCH Tagetik via an ETL (Extraction, Transformation and Loading) routine. This procedure is recommended when the accounting data have been inserted previously, e.g. in Excel files or other formats. For details on the data loading procedure, see Run ETL in the ETL section.

Data entry using copy functions

Data on gross amounts, intercompany entries and entity and consolidation adjustment journals can also be loaded using the copy functions present in the various pages of CCH Tagetik. These functions allow you to copy the data of a specific entity onto another scenario/period, or onto another entity on the same scenario/period or a different scenario/period.

Data entry using utilities

This method allows you to load data using algebraic operations. In particular, you can load data on the same scenario or among different scenarios. See Algebraic operations in the Operations section.

Data entry rules

Amount & IC rules

The amount and IC rules define the criteria that CCH Tagetik applies to the entry of data related to amounts and intercompany entries. You can define general rules and overrides, or deviations from the general rule to be applied to specific processes.

For example, you may need to enable data entry from forms at the node level, or to activate the break back function (The Break Back function in the Reporting section), for a certain process but not for another.

By default, data entry is enabled for every process.

Journal rules and settings

The journal rules and settings define the criteria that CCH Tagetik apply to the entry of data related to journals. For these rules you can also define general rules and overrides, or deviations from the general rule to be applied to specific processes.

For example, for a given process, you may need to insert journals with details on the custom dimensions on the journals even if their management is enabled.

Amount & Intercompany rules page

Admin

Database applicativo > tile Data Entry e Regole certificazione > Regole Saldi e IC

Purpose of the page

This page allows you to set the default rules for data entry on gross amounts and intercompany entries.

Page sections

Section	Description
Dimensions	Defines the custom dimensions enabled on amounts, intercompany entries and reconciliation accounts.
Intercompany	Defines additional fields for the intercompany declaration and specific behaviour for the intercompany declaration methods.
Transaction currency	Defines the management mode for the currency in which the transaction was carried out, regardless of the entity that executed it.
Editability	Defines the editability options for data originating from specific sources.
Break back	Defines, for the managed dimensions, the requirements for entering data from forms at the level of hierarchy nodes.
IC Cockpit Advanced rules	Defines advanced requirements for inserting reconciliation accounts from the IC cockpit.
Spreading	Defines the way in which the spreading functionality is used.
Countervalue calculation	Defines the FX rate used in the countervalue calculation data processing, and the data on which it is run.

Fields in the Dimensions section

Element	Description
<Custom Dimension n>	Enables the use of custom dimension <n>.

Fields in the Intercompany section

Element	Description
Enable additional fields on IC	If not set to **No**, this allows you to manage the following additional fields during data entry: • **Only information for document**: to manage the following information: **Field** / **Description** **Invoice number** — Identifier of the original document. Used by the automatic relationship procedure to relate documents that have the same number to each other. **Invoice date** — Document date. Used by the automatic relationship procedure to relate documents that have the same date to each other. **Accounting date** — Date on which the document was booked. **Document Type** — Type of document (document, invoice or accrual) **Sent/Received** — Indicates whether the document has been sent or received. **Invoice matching number** — Number updated by the automatic invoices relationship procedure. This can be edited manually for manual matching. • **Information for document and amount type**
Copy intercompany to gross data	Enables the automatic calculation of the gross data based on the saving of intercompany data from forms. By enabling this option, the plausibility diagnostic will diagnose the intercompany data and the minorities share together.

Element	Description
Allow intercompany declarations towards same Declaring entity	If selected, allows you to enter intercompany declarations towards the same declaring entity. The declaring entity is therefore the same as the counterparty entity. If NOT selected, in the intercompany data entry step an editability check is enabled which locks records where the declaring entity is the same as the counterparty entity. *For example, it is useful to perform intercompany declarations in the context of the same entity to eliminate dividends received from group companies towards profits carried forward.*
Define CTP <Custom dimension 2> with default Entity element	When entering intercompany data, the CTP custom dimension 2 is automatically defined as the default element of the custom dimension 2 associated with the entity.

Fields in the Transaction currency section

Element	Description
Managed on gross amount	Allows you to manage the transaction currency and the transaction currency amount on gross amounts.
Managed on IC amount	Allows you to manage the transaction currency and the amount in foreign currency of the transaction on intercompany amounts.
Keep transaction currency on consolidated gross amount	Keeps details of the transaction currency on consolidated amounts.
Use detail window to input gross & IC data on transaction currency	Where the transaction currency is being managed, the entry of data (gross and intercompany amounts) within the form must obligatorily be done from the relative management window and not directly from the cell.

Fields in the Editability section

Element	Description
Edit data with ETL origin	Enables the data collected by the ETL procedure to be edited manually.
Save data in form incrementally	Enables changes to data in forms to be tracked. When saving the form, the system creates a database row for every change made to the individual amount. If disabled, the system sums up all the values entered, and only shows the total. *For example, if enabled, if the value 100 is initially present in a cell and the user overwrites that value with 110 first, and then with 150, the system inserts the initial amount record of 100, an amount record of 10 and another amount record of 40, all with INPUT_DEFORM as their origin. Otherwise, there will only be one record with 150 as its amount and INPUT_DEFORM as its origin.* ***IMPORTANT**: enabling this option allows you to have full data traceability but generates a high number of rows.* ***IMPORTANT**: if the data edited from the form is an intercompany entry and the counterparty entity definition is already present on the form's columns/rows, or it is not necessary to use the dedicated edit function, the system will always perform incremental saving, regardless of this setting.*

Fields in the Break back section

***IMPORTANT**: with break back active, data entry forms are also editable if certain dimensions are filtered at the node level.*

Element	Description
Dimensions	Allows you to select the dimensions on which to run the break back. • **None** • **Custom dimensions** • **Custom dimensions - Entity - Accounts**
Editability check	With break back active, it allows you to select the mode in which the editability check is performed. • **Automatic**: if the data is saved on a reference element, the system performs the check on the reference lowest element. If no reference element is specified, the editability check is not performed. • **On reference lowest element**: the system always performs the editability check on the reference element. If no reference element is specified, the data will not be editable.
Always write on reference element	With break back active and enabled, for data entry from forms it automatically attributes the changes made on the node to the same node's reference entity. When disabled, changes made on a node are distributed among the lowest level elements related to the same node in proportion to the values already present.

Fields in the IC Cockpit Advanced rules section.

Element	Description
Attribute only the reconciliation account category to the cockpit step	If active, the system behaves as follows: For account/category pairs present in an intercompany matching cockpit in which the category is the one used on the IC cockpit for reconciliation accounts, this defines the intercompany step as the step in which the cockpit is currently found. For account/category pairs present in an intercompany matching cockpit in which the category is **not** the one used on the IC cockpit for reconciliation accounts, it behaves as if the option were not active. If not active, the system behaves as follows: • for account/category pairs belonging to the intercompany matching cockpit, the intercompany step is the same as the cockpit step • for account/category pairs not belonging to any cockpit, where there are overrides, the system considers the intercompany step to be the overridden step. If there are no overrides, it uses the highest step out of the gross data step and the lowest step on which a cockpit is present.
Simplified calculation of the ic step	Defines the gross step, or any overridden step, as the intercompany step for accounts/categories not associated with the cockpit.
Allow the insertion of reconciliation accounts with IC data entry in progress	Allows you to insert reconciliation accounts even if one of the two entities has not yet finished inserting intercompany entries. Reconciliation accounts can therefore always be added, regardless of the status of the entities of the relationship on the IC matching cockpit.
Mandatory notes when inserting reconciliation accounts	Makes it mandatory to insert notes when loading reconciliation accounts.

Fields in the Spreading section

Element	Description
Intercompany Spreading display method	Tells the system how to display data related to intercompany entries in the data entry step when the intercompany spreading functionality is in use. • **All data**: the system displays the original declarations and write-off and reallocation entries. • **Original data**: the system only displays the original declarations. • **Only Reallocations**: the system only displays data related to reallocations on the counterparty custom dimension 2.
Granularity: <Custom dimension 2>	Defines the level of detail for the intercompany spreading functionality. • **By element** • **By node**

Element	Description
Reference Hierarchy <Custom dimension 2>	Only with **<Custom dimension 2> Granularity** = **By node**. Defines the custom dimension 2 hierarchy to be used.
Reference level for the <Custom dimension 2> hierarchy	Only with **<Custom dimension 2> Granularity** = **By node**. Selects the level of the custom dimension 2 hierarchy to be used to select the available nodes.
Display override type CTP <Custom dimension 2>	Enables **CTP custom dimension 2 override** information in data entry management windows for intercompany entries and entity journals.
Preferential allocation to <Custom dimension 1>	Enables the management of intercompany declarations belonging to the entity/counterparty/custom dimension 1 relationships that are balanced as a stand-alone set of declarations.
Balancing threshold on <Custom dimension 1>	Defines the threshold below which an entity/counterparty/custom dimension 1 is considered to be balanced.
Delete error signs	Enables an intercompany declaration reallocation algorithm on the counterparty custom dimension 2, to eliminate the effects of IC declarations with anomalous signs. For details of the algorithm, seeDelete error signs algorithm in the Processes section

Fields in the Countervalue calculation section

Element	Description
Conversion	Defines the type of FX rate to be used in countervalue calculation data processing to convert the following accounts with conversion type set to P&L FX rate. The following FX rates are available: • **Average FX rate** • **Period average FX rate** • **Final FX rate** • **Override Period average FX rate on P&L or on Variations accounts**: the system converts all P&L accounts, Other Variations accounts and Variations accounts (regardless of their Nature), ignoring the account's conversion type. Conversion takes place at the period's average FX rate and the period length is the one indicated on the scenario being processed. For more details on FX rates, see Currencies: basic concepts in the Data Model section.
Run also on Balance Sheet, Other Stock & Guard. and Comm. accounts	Includes balance sheet accounts and normal and detailed other stock accounts in the countervalue calculation data processing.

Journal rules and settings page

Admin

Database applicativo > tile Data Entry e Regole certificazione > Regole ed impostazioni Scritture

Purpose of the page

This page allows you to set the default rules for entity journals and consolidation journals.

Page sections

Element	Description
Dimensions	Defines the custom dimensions enabled on the journals.
Transaction currency	Defines the management mode for the currency in which the transaction was carried out, regardless of the entity that executed it.
Others	Defines specific behaviour for relationships, editability, journal compilation and elimination logics.
Draft journals	Defines the type of control to be run when a draft journal is published.

Fields in the Dimensions section

Element	Description
<Custom Dimension n>	Enables the use of custom dimension <n>.

Fields in the Transaction currency section

Element	Description
Entity journals	Allows you to manage the transaction currency and the transaction currency amount on the rows of an entity journal.
Consolidation journals	Allows you to manage the transaction currency and the transaction currency amount on the rows of a consolidation journal.

Fields in the Other section

Element	Description
Relationship type	Defines the declaring entity/counterparty relationships. • **Entity**: declaring entity/counterparty relationships are entity-entity. • **Entity - custom dimension 2**. Declaring entity/counterparty relationships are entity-custom dimension 2. The system generates the automatic intercompany elimination journals based on the relationship between the entity and the custom dimension 2. • **Entity - synthetic custom dimension 2**: The headers are generated on the basis of the relationships between entities and their COD_DEST1 and COD_DEST2 fields are empty. When the entity or relationship (CTP eliminations, minorities, NER, etc.) are used to generate the journal number, custom dimension 2 is not inserted. The journal rows are generated on the basis of the entity/custom dimension 2 relationship and their COD_DEST2_CTP_SEGMENT field is defined. The system considers the Entity - custom dimension 2 relationship type both during the row creation step and during the reading/processing of the data of the same rows.
Enable financial investments editability on journals	Overrides the editability of financial investment accounts on journals.
Manages CTP entity and CTP Products regardless of the header relationship	In the consolidation journal compilation step, this allows you to set counterparty entities and/or custom dimension 2s, if managed, other than those defined in the journal header, as counterparty entities and/or counterparty custom dimension 2s on the rows (regardless of the value in the **Many to many relationship** field).
Exclude intercompany capacity check on the single row of the journal	Only if the row account manages intercompany declarations and the **IC capacity check** in the process validation rules is **Check =**. When saving a journal entry row, makes the counterparty entity valuation optional. Useful when the IC capacity check is configured by category node.
Eliminate once the accounts present in more than one elimination logics	When the account is associated with several elimination logics, it deletes the account with the highest code in the elimination logic.

Fields in the Draft journals section

Element	Description
Check	Checks to be run before publication of the journal. • **No check**: does not run checks. • **Diagnostic result**: when the journal is published, it runs the diagnostic and prevents publication if there are blocking errors. • **Journal balancing**: checks the balancing on publication of the journal. If the journal is unbalanced, this prevents publication.

Buttons and/or links on the page

Element	Description
Default Settings	Opens a page to define the default settings for journal data entry, see Default Settings window.
Categories for draft journals	Opens a page to define categories for draft journals, see Categories for draft journals page.

Default Settings window

Admin

Data Entry & Submission rules tile > Journal rules and settings > Default Settings

Navigation panel > Processes and Workflow > Journal Rules > Default Settings

Purpose of window

This window allows you to define the default settings for journal data entry. You cannot set overrides at the process level in these settings.

Page fields

Element	Description
Journal # separator	Defines the symbol to be used as the separator between the journal prefix and suffix.
Journal prefix	Defines the way in which the a journal number's prefix is generated. • **Entity code**: the entity journal prefix will be the code of the declaring entity. • **User's personal prefix**: the prefix will be the value of the **Journal prefix number** defined in the users table for the user inserting the journal. • **User's personal prefix & Entity code**: the prefix will be the concatenation of the **Journal prefix number**, **Journal number separator** and, only in Declaring entity journals, the **Declaring entity code.**
Amounts	Defines how the system writes amounts in the database. • **Write amounts in one column with accounting signs**. • **Write amounts in Debit & Credit columns in absolute value**. If selected, two columns for the amount will be shown in the journal: **Debit amount** and **Credit amount**.
Show only main accounts	In the data entry step for the rows of a journal, only the rows for the main accounts are shown. The filter can be edited from the data entry window.
Exclude Result accounts and their variations	In the data entry step for the rows of a journal, neither the rows for the result accounts nor their variations are shown. The filter can be edited from the data entry window.
Journals data entry: account type	Defines the type of account on which to filter the rows of a journal to be shown. • **Details** • **Variation** • **Normal** • **Any**
Journal Book: View amounts in Debit & Credit Columns	Defines how the debit/credit is shown, either in separate columns or in a single column with a sign, on the journals book in Excel.

Categories for draft journals page

Admin

Database applicativo > tile Data Entry e Regole certificazione > Regole ed impostazioni Scritture > Categorie per scritture in lavorazione

Purpose of the page

This page allows you to define the categories that are valid for draft journals.

Page fields

Element	Description
Category	Selects a category.

Amounts

Contents

This section covers the following topics:

Amounts 11
Gross Amounts page 12
IC Amounts (Show IC declarations) page 15
Balancing page 16
IC amounts page 17
Delete IC error signs algorithm 21

Amounts

Gross amounts

Original financial statement amounts are defined as gross amounts since the values to be inserted are "gross" of IC declarations, i.e. the inserted amounts also include the intercompany portion.

They are typically inserted manually by the Contributor user from the relative cockpit with data entry via Excel or online, but they could also be the result of ETL loading. They can be subdivided into two groups:

- static amounts, i.e. Balance Sheet and Profit & Loss amounts.
- dynamic amounts, i.e. variations, used to relate balance sheet accounts, memorandum accounts or other stock accounts to the relative entries.

***Note**: statistical values (quantity, headcount, m², etc.), which are typically used as drivers in allocation processes, in the creation of indices (e.g. revenue per passenger on a ship) and in management reporting, are managed as amounts.*

Once the amounts have been inserted, CCH Tagetik checks that they are balanced, or represent the sum of all the amounts inserted on the various accounts with "Balance Sheet" nature and "Normal" type and indicates the total amount in the **Balancing**" field.

***Note**: the calculation is performed taking account of any filters that have been applied, with the exception of filters on the account (code, description, nature or type) and on amounts.*

IC amounts

IC amounts are intercompany amounts, i.e. all the amounts (costs, revenues and assets) related to transactions between entities belonging to the same group.

***Note**: only accounts which have the "IC Management" option active can accept intercompany values (see Accounts table in the Data Model section).*

To facilitate the selection of the counterparty entity during the IC amounts data entry step, CCH Tagetik allows you to define the list of most common counterparty entities for each entity. These counterparties are defined in the Counterparties tab in the list of entities and are shown in the CTP entity selection window. See Entities list in the Data Model section.

Additional fields

Additional fields are only shown if "Enable additional fields on IC" is selected in the process's gross and IC amount rules.

These fields are used by the automatic document relationship procedure, and relate an entity's IC declarations to a counterparty's declarations based on information related to the invoice.

Restrictions and conditions

Gross and IC amounts are managed by process and potentially by scenario/period, if the process is not a single submission process. Moreover, it is only possible on scenarios/periods that are not stored offline and

are visible to the user.

Only contributor amounts can be managed from the Contributor cockpit, whereas from the Consolidator cockpit it is also possible to manage consolidator amounts.

Counterparty dynamic groups

In the declaration of an IC amount, it could be useful to indicate only one subset of entities included in the list as counterparty entities.

For example, for the "Investments at equity" account it may be practical to use only entities consolidated using the net equity method as counterparty entities, or you may only want to use counterparties that are banks for the "Receivables from banks" account.

To restrict the set of entities that can be selected as the counterparty entity for a given account or custom dimension, it is possible to create a Counterparty dynamic group (see Create a counterparty dynamic group in the Data Model section)

The counterparty dynamic group can therefore be associated, using the **CTP restriction** field, with every account (see Account list in the Data Model section) or with every element of the custom dimensions that manage the counterparty dynamic groups and, in that case, if the counterparty entity is defined. The system behaves as follows:

If...	Then...
the selected account has a CTP restriction	the CTP entity must be one of the counterparties allowed by the account.
the selected custom dimensions have a CTP restriction	the CTP entity must be one of the counterparties allowed by the custom dimension element.

Gross Amounts page

User

Processes tile > select process > Contributor > Detail summary tab > (Actions) Edit windows > Edit Amounts

Processes tile > select process > Consolidator > Overview tab > (Actions) Edit windows > Edit Amounts

Processes tile > select process > Step tab > from a workflow task > select a Gross Amounts task > Run

Navigation panel > Processes > select process > Contributor > Detail summary tab > (Actions) Edit windows > Edit Amounts

Navigation panel > Processes > select process > Consolidator > Overview tab > (Actions) Edit windows > Edit Amounts

Navigation panel > Processes > select process > Step tab > from a workflow task > select a Gross Amounts task > Run

Purpose of the page

This page shows a list of the inserted gross amounts and allows you to insert others. In particular, it shows a view dedicated to the amounts of the selected entities. If nodes of entities are selected, the amounts of entities belonging to the selected nodes will be shown, going down recursively to the last level.

The overall value of the balancing is reported at the bottom of the page.

The filters applied to the page can always be edited from the filters panel ( ) and saved for future access.

Click to view columns with additional information on the page: e.g. account nature, account type, origin, etc.

Amounts inserted manually have "INPUT_WEB" indicated as their **Origin**.

***Note**: You can configure CCH Tagetik so that amounts with different origins are different colours. See **Colours by origin** option in the Settings window in the General Introduction section.*

Icons on this page

Element	Description
	The amounts cannot be edited. Shows the reason for the lock.
	The amount data are no longer consistent, e.g. on accounts or entities not belonging to the process. Shows the reason for the inconsistency. The row and the amount can be deleted using the  button.

Actions on this page

Element	Description
	Spreadsheet view: shows the data in a spreadsheet.
	List view: shows the data in a table. Default view.
	**Show IC declarations**: Only for accounts that allow for the management of intercompany entries. Opens a page to insert intercompany declarations for the selected entity/account. See IC Amounts page. **Diagnostic**: Only if diagnostic is enabled on the process. Runs the diagnostic on the entities to which the selected amounts belong if the category type is “contributor amount”; runs it on the consolidator nodes if the category type is “consolidator amount”. See Diagnostic data processing in the Diagnostic section. **Balancing**: opens a window to check the balancing in detail, by category. See Balancing page.

Page attributes

Field	Description
Scenario	Scenario to which the amount belongs. You can choose an active original scenario, which you can edit and for which there exists at least one unblocked period belonging to the selected process.
Period	Period to which the selected amount belongs. You can choose a different period, provided that it is not locked and is linked to the selected scenario.
Entity	Entity to which the selected amount belongs. You can choose another entity, provided it meets the following requirements: • Editable by the user. • Belong to the selected process. • Belong to the selected scenario/period and, on that scenario/period, cannot be an “Only CTP” entity. • Start date and end date, if defined, must be between the start date and end date of the selected scenario/period.
Category	Amount category The chosen categories must meet the following requirements: • Editable by the user. • Belong to the selected process. • If the page is opened from the Contributor cockpit, the category type must be “contributor amount”. • If the page is opened from the Consolidator cockpit, the category type must be “consolidator amount”.

Field	Description
Account	Account on which the amount was inserted. The chosen account must meet the following requirements: • Editable for the user. • Linked to the data model process associated with the selected entity. • Start date and end date, if present, must be between the start date and end date of the scenario/period to which the amount belongs.
Custom dimension	For every managed custom dimension, if enabled in the process's gross and IC amount rules, you can select an element of the custom dimension which meets the following requirements: • Editable for the user. • Visible from the selected entity. • Visible from the selected account. If no value is selected, CCH Tagetik will choose the custom dimension to be the entity's default custom dimension or the custom dimension with the lowest code from among those which meet the above requirements.
Entity currency	Currency assigned to the entity in the process. Defined automatically and non-editable.
Entity currency amount	Amount expressed in the entity currency. Regardless of the number of decimals inserted, amounts are shown with a number of decimals that is consistent with those assigned to the currency in which they are expressed, with the exception of "Other stocks" and "Other variations" accounts where the **Manage maximum number of decimals** option is active (see Accounts list in the Data Model section). For these accounts, it is possible to insert up to 9 decimals.
Transaction currency	Only shown if the transaction currency is managed on gross amounts (general or overridden on the individual process) in the process's gross and gross amount rules. If not entered, it will be defined as the entity currency.
Transaction currency amount	Only shown if the transaction currency is managed on gross amounts (general or overridden on the individual process) in the process's gross and gross amount rules. Defined as the entity currency if the **Transaction currency** field is empty or the same as the entity currency. Defined automatically as the entity currency amount, applying the conversion rate set on the account, if the **transaction currency** has been entered and is different from the entity currency, and if the entity currency amount is defined and the transaction currency amount is not. The same is true for the entity currency amount, if it is not defined but the transaction currency amount is defined.
Notes	Any explanatory notes. For example: • On rows originating from the merger data processing, to store information on the incorporating entity. • On rows originating from the base calculation logics, to store information on which calculation logic generated the row.

IC Amounts (Show IC declarations) page

User

Processes tile > select process > Contributor > Detail summary tab > (Actions) Edit windows > Edit Amounts > select amount > ⋮ > Show IC declarations

Processes tile > select process > Consolidator > Overview tab > (Actions) Edit windows > Edit Amounts > select amount > ⋮ > Show IC declarations

Processes tile > select process > Step tab > from a workflow task > select a Gross Amounts task > Run > select amount > ⋮ > Show IC declarations

Navigation panel > Processes > select process > Contributor > Detail summary tab > (Actions) Edit windows > Edit Amounts > select amount > ⋮ > Show IC declarations

Navigation panel > Processes > select process > Consolidator > Overview tab > (Actions) Edit windows > Edit Amounts > select amount > ⋮ > Show IC declarations

Navigation panel > Processes > select process > Step tab > from a workflow task > select a Gross amounts task Gross Amounts > Run > select amount > ⋮ > Show IC declarations

Purpose of the page

This page allows you to insert intercompany declarations for the selected entity/account. It is useful for managing intercompany entries in the same insert gross amounts step. Only available for accounts which allow the management of intercompany amounts.

On saving, for accounts which have a capacity check, any inconsistencies between the value present on the gross amounts and the value present on the IC declaration are checked according to the following criteria:

If the IC Capacity Check attribute is	Then...
Check <=	it indicates whether the sum of the IC amounts exceeds the gross amount.
Check =	It indicates whether the sum of the IC amounts is different from the gross amount.

For the setup of the **IC Capacity check** attribute, see Accounts list in the Data Model section.

Balancing page

User

Processes tile > select process > Contributor > Detail summary tab > (Actions) Edit windows > Edit Amounts > select amount > ⋮ > Balancing

Processes tile > select process > Consolidator > Overview tab > (Actions) Edit windows > Edit Amounts > select amount > ⋮ > Balancing

Processes tile > select process > Step tab > from a workflow task > select a Gross Amounts task > Run > select amount > ⋮ > Balancing

Navigation panel > Processes > select process > Contributor > Detail summary tab > (Actions) Edit windows > Edit Amounts > select amount > ⋮ > Balancing

Navigation panel > Processes > select process > Consolidator > Overview tab > (Actions) Edit windows > Edit Amounts > select amount > ⋮ > Balancing

Navigation panel > Processes > select process > Step tab > from a workflow task > select a Gross Amounts task > Run > select amount > ⋮ > Balancing

Purpose of the page

This page shows the balancing data for the selected amount.

Page fields

Field	Description
Scenario	Scenario to which the amount belongs. You can choose an active original scenario, which is visible to the user and for which there is at least one unblocked period belonging to the selected process.
Period	Period to which the selected amount belongs. You can choose a different period, provided that it is not locked and is linked to the selected scenario.
Entity	Entity to which the selected amount belongs. You can choose another entity, provided it meets the following requirements: • Editable by the user. • Belong to the selected process. • Belong to the selected scenario/period and, on that scenario/period, cannot be an “Only CTP” entity. • Start date and end date, if defined, must be between the start date and end date of the selected scenario/period.
Category	Amount categories. You can choose categories which exist in the environment and meet the following requirements: • Editable by the user. • Belong to the selected process. • If the page is opened from the Contributor cockpit, the category type must be “contributor amount”. • If the page is opened from the Consolidator cockpit, the category type must be “consolidator amount”.
Entity currency	Currency of the entity to which the selected amount belongs, but you can choose a different one.

Field	Description
Balancing P&L	Total, with its sign changed, of the amounts inserted on the accounts with “Profit & Loss” nature and “Normal” type. ***Note**: this total does not include the amounts of the P&L result account. The code of the Profit & Loss result account can be recovered from the set of result accounts defined in the process’s calculation logics.*
Balancing balance sheet	Total, with its sign changed, of the amounts inserted on the accounts with a “Balance Sheet” nature and “Normal” type. ***Note**: this total does not include the amounts of the Balance Sheet result account. The code of the Balance Sheet result account can be recovered from the set of result accounts defined in the process’s calculation logics.*
Balancing	Result of the sum of the Profit & Loss account balancing and the Balance Sheet account balancing.

IC amounts page

User

Processes tile > select process > Contributor > Detail summary tab > (Actions) Edit windows > Edit IC

Processes tile > select process > Consolidator > Overview tab > (Actions) Edit windows > Edit IC

Processes tile > select process > Step tab > from a workflow task > select an IC amounts task > Run

Navigation panel > Processes > select process > Contributor > Detail summary tab > (Actions) Edit windows > Edit IC

Navigation panel > Processes > select process > Consolidator > Overview tab > (Actions) Edit windows > Edit IC

Navigation panel > Processes > select process > Step tab > from a workflow task > select an IC amounts task > Run

Purpose of the page

This page shows a list of the inserted IC amounts and allows you to insert others. Shows a view dedicated to managing the amounts of the selected entities. If nodes are selected, the amounts of entities belonging to the selected nodes will be shown, going down recursively to the last level.

The filters applied to the page can always be edited from the filters panel ( ) and saved for future access.

Click to view columns with additional information on the page: account nature, account type and origin.

IC amounts inserted manually have “INPUT_WEB” indicated as their **Origin**.

***Note**: You can configure CCH Tagetik so that IC amounts with different origins are different colours. See **Colours by origin** option in the Settings window in the General Introduction section.*

Icons on this page

Element	Description
	The amounts cannot be edited. Shows the reason for the lock.
	The amount data are no longer consistent, e.g. on accounts or entities not belonging to the process. Shows the reason for the inconsistency. The row and the amount can be deleted using the button.

Actions on this page

Element	Description
	Spreadsheet view: shows the data in a spreadsheet.
	List view: shows the data in a table. Default view.
	**Relationship check**: shows the result of a diagnostic balancing check which considers, based on the selected relationship, all the IC amounts declared by the declaring entity towards the counterparty entity (and vice versa) for all the accounts present in the IC matching and elimination logic in the process and in which the selected account is found. **Check all**: shows the result of a diagnostic balancing check which considers, based on the selected relationship, all the IC amounts inserted by the declaring entity towards the counterparty entity (and vice versa) and all the IC amounts in which the entity is present as the declaring or counterparty entity for all the accounts present in the IC matching and elimination logic processed in the process and which includes the selected account. **Diagnostic**: Only if diagnostic is enabled on the process. Runs the diagnostic on the entities to which the selected amounts belong if the category type is “contributor amount”; runs it on the consolidator nodes if the category type is “consolidator amount”. See Diagnostic data processing in the Diagnostic section.

Page attributes

The **Additional fields** tab is only shown if the **Enable additional fields on IC** option is not set to “No” in the process’s gross and IC amount rules.

> ***Note**: these fields contain information that is necessary for the automatic document relationship procedure, which relates an entity’s IC declarations to a counterparty’s declarations based on information related to the invoice.*

Field	Description
General	
Scenario	Scenario to which the amount belongs. You can choose an active original scenario, which you can edit and for which there exists at least one unblocked period belonging to the selected process.
Period	Period to which the selected amount belongs. You can choose a different period, provided that it is not locked and is linked to the selected scenario.
Entity	Entity to which the selected amount belongs. You can choose another entity, provided it meets the following requirements: • Editable by the user. • Belong to the selected process. • Belong to the selected scenario/period and, on that scenario/period, cannot be an “Only CTP” entity. • Start date and end date, if defined, must be between the start date and end date of the selected scenario/period.
Category	Amount category The chosen categories must meet the following requirements: • Editable by the user. • Belong to the selected process. • If the page is opened from the Contributor cockpit, the category type must be “contributor amount”. • If the page is opened from the Consolidator cockpit, the category type must be “consolidator amount”.

Field	Description
Account	Account on which the amount was inserted. The chosen account must meet the following requirements: • Enabled for IC management. • Editable for the user. • Linked to the data model process associated with the selected entity. • Start date and end date, if present, must be between the start date and end date of the scenario/period to which the amount belongs.
Custom dimension	For every managed custom dimension, if enabled in the process's gross and IC amount rules, you can select an element of the custom dimension which meets the following requirements: • Editable for the user. • Visible from the selected entity. • Visible from the selected account. If no value is selected, CCH Tagetik will choose the custom dimension to be the entity's default custom dimension or the custom dimension with the lowest code from among those which meet the above requirements. The custom dimension 2 is managed even if it is not enabled in the process's gross and IC amount rules, but the process's relationship type is "entity - custom dimension 2" or "entity - synthetic custom dimension 2".
CTP entity	An entity can be chosen, provided it meets the following requirements: • Belong to the selected process. • Must belong to the selected scenario/period. • Start date and end date, if present, must be between the start date and end date of the selected scenario/period. You can define a list of most frequently used counterparty entities, see Entities list in the Data Model section. To use only a subset of entities as counterparties, it may be useful to create a group of counterparties (Dynamic counterparty groups). You can also declare IC data in the context of the same entity (and therefore use the same code for both the entity and the counterparty). This is only possible if the **Allow intercompany declarations towards same Declaring entity** option is active (Amount & Intercompany rules page). *For example, this is useful for eliminating dividends received from group companies towards profits carried forward, or for eliminating self-invoicing results.*
CTP custom dimension 2 override type	Only present under the following conditions: • Custom dimension 2 is managed. • The process' relationship type is "entity - custom dimension 2" or "entity - synthetic custom dimension 2". • The **Spreading - Show CTP custom dimension 2 override type** option is active in the process's gross and IC amount rules. • The user's role contains function 0002274. It can be set as follows: • To allocate • None • Override

Field	Description
CTP Custom dimension 2	Only present under the following conditions: • Custom dimension 2 is managed. • The process' relationship type is "entity - custom dimension 2" or "entity - synthetic custom dimension 2". It is only mandatory under the following conditions: • A CTP entity has been specified. The field is only editable if the **Spreading - Display CTP custom dimension 2 override type** option is active in the process's gross and IC amount rules, or if that option is active and: • The user's role contains function 0002274. • **CTP custom dimension 2 override type** is not "To allocate" If the field is editable, it is defined as the CTP entity's default custom dimension 2 or, if the **Spreading - Show CTP custom dimension 2 override type** and **Show CTP custom dimension 2 with entity's default element** options are not active in the process's gross and IC amount rules, the field is defined as the default custom dimension 2 element specified in the custom dimension 2 settings.
Entity currency	Currency assigned to the entity in the process. Defined automatically and non-editable.
Entity currency amount	Amount expressed in the entity currency. Regardless of the number of decimals inserted, amounts are shown with a number of decimals that is consistent with those assigned to the currency in which they are expressed, with the exception of "Other stocks" and "Other variations" accounts where the **Manage maximum number of decimals** option is active (see Accounts list in the Data Model section). For these accounts, it is possible to insert up to 9 decimals.
Transaction currency	Only present if the transaction currency is managed on IC amounts in the process's gross amounts and IC rules. If not entered, it will be defined as the entity currency.
Transaction currency amount	Only present if the transaction currency is managed on IC amounts in the process's gross amounts and IC rules. Defined as the entity currency amount even if the **Transaction currency** field is empty. Defined automatically as the entity currency amount, applying the conversion rate set on the account, if the **transaction currency** has been entered and is different from the entity currency, and if the entity currency amount is defined and the transaction currency amount is not. The same is true for the entity currency amount, if it is not defined but the transaction currency amount is defined.
Notes	Any explanatory notes. For example: • On rows originating from the merger data processing, to store information on the incorporating entity. • On rows originating from the base calculation logics, to store information on which calculation logic generated the row.
Additional fields	
Relationship	Any information on the relationship between an entity's IC declarations and the counterparty declarations.
Invoice number	Document identifier. Used by the automatic document relationship procedure if it has been requested to relate documents which have the same document number.
Invoice date	Document date. Used by the automatic document relationship procedure if it has been requested to relate documents which have the same document date.

Field	Description
Document Type	Document type: • Document • Bill • Accrual
Accounting date	Date on which the document was booked.
Sent/Received	Indicates whether the document has been sent or received.
Invoice matching number	Identifier of the relationship created between an entity's IC declarations and a counterparty's declarations. It is generated by the automatic invoices relationship procedure. In some cases, it is not possible to automatically create relationships between IC declarations, for example, if an entity has entered the booking date instead of the invoice date. However, you can relate the IC declaration manually by setting the **Invoice matching number** field with the same number used in the counterparty entity's IC declaration. You can also edit an automatic relationship number that has been generated by the system. ***Note**: for the manual relationship, do not use a code that starts with $, as this symbol is used by the system to automatic relationships.*

Delete IC error signs algorithm

Introduction

The following algorithm allows you to reallocate intercompany declarations on counterparty custom dimension 2, in IC Spreading data processing.

Algorithm properties

- On each side of a relationship between entities, the system separates the custom dimensions 2 according to whether they have a positive total, a negative total or a total of nil (typically resulting from amounts off written directly on input)
- Custom dimensions 2 with a sign are reallocated to those of the counterparty with the opposite sign following a specific allocation sequence.
- Amounts related to custom dimensions 2 with a total of nil are allocated to the default.

With regard to how the system functions when the aforementioned option is NOT active, there are the following differences:

- The step that associates custom dimensions 2 that are the same on both sides only takes place if the totals are of opposite signs on each side. Otherwise, those mini-relationships will remain empty.
- If, after that step, one of the two sides remains without custom dimensions 2 or the desired sign, the counterparty's remainder is allocated to the default custom dimension 2, ignoring the custom dimensions 2 on which the original declarations had been made.
- The step that reallocates on a proportional basis never reallocates groups of custom dimensions 2 with different signs together, and always works in conditions that prevent any risk of incorrect signs or amounts.

Allocation sequence

Custom dimensions 2 with a sign are allocated according to the following steps:

- If there are shared custom dimensions 2 on each side, the system allocates the lower module portion (comparing the declarations of the two entities) entirely to the same custom dimension 2. The remaining portion on the side of the higher module, where applicable, is dealt with in the next steps.
- If there are no custom dimensions 2 of the opposite sign on the counterparty side, or all the custom dimensions 2 to be reallocated have been entirely reallocated in the previous step, then any remaining amounts are allocated to the default custom dimension 2.
- Otherwise, the custom dimensions 2 intersect with remaining amounts in every way possible, using the counterparty declarations as weightings.

Journals

Contents

This section covers the following topics:

Journals ... 22
Entity journals ... 23
Consolidation journals ... 24
Draft journals ... 24
Headers (Entity Journals) page ... 29
Rows (Entity Journals) page ... 34
Headers (Consolidation journals) page ... 37
Rows (Consolidation journals) page ... 46
Actions from journal headers ... 51
Documents page ... 54
Consolidation scenario page ... 55
Periodic Management page ... 56
Overridden FX rates page ... 57
Submit from workflow page ... 58
Journal log ... 59
Copy window ... 60
Edit category window ... 61
Actions from the journal rows ... 62
Original and consolidated rows page ... 64
Control group balancing ... 68
Control Group Balancing page ... 68
Drill down on control groups page ... 70

Journals

Journal structure

Both entity journals and consolidation journals are logically composed of two parts:

- a **header**, i.e. the container of the journal's general attributes (code, description, etc.). This part defines how the journal must be managed, whether it must be carried forward, the consolidation scenarios on which it must be processed, etc..
- **rows**, i.e. the records of the saved entries for that journal.

When entries are inserted, CCH Tagetik checks whether the journal satisfies the double entry logic, i.e. whether it is balanced. The double entry logic requires every operation to be recorded twice, on two accounts, simultaneously and with opposite signs. To do this, CCH Tagetik adds together all the amounts entered on the various accounts with "Balance Sheet" nature and "Normal" type used in the journal, and reports the total amount in the "Balancing" field present under the table of rows.

> ***Note**: when saving each row edit, all the calculated base type accounts which belong to the process and have one of the accounts edited in the journal as their input are run.*

Journal management

Journals can be managed in different ways depending on the project type and the client's requirements.

Management type	Description
Sentence case	Journals are managed by individual period and the data entered are cumulative. This is the complete method and recommended for statutory consolidations.
Periodic	The journals are managed from the requested period until the end of the process. Recommended for consolidation in the management setting. ***Note**: on single submission processes, you can manage rows in periodic mode for periodic journals.*

Periodic management for single submission processes

If the process on which you are working is a single submission process, periodic management can be performed in two different ways:

- directly from the management of a journal's rows. In this case, in the save step, it is saved not only on the period in question but also on all subsequent periods that belong to the same process.
- using the **Periodic management** function (Periodic Management page). In this case, the user can enter the journal data for all periods until the end of the process.

If the process on which you are working is a submission by scenario/period process, its valuation tells the carry forward data processing to copy the data from the previous period. In more detail, during this data processing the amounts of the journal of a period are made cumulative by automatically copying the periodic data from previous periods of the same journal.

Journals numbering

CCH Tagetik allows you to choose the Journals numbering method (see Default Settings window).

By default, the Journals numbering method is manual; therefore, when creating a new journal, the user specifies a prefix and suffix which are concatenated to generate the journal number.

If the journal numbering method is automatic, however, the user does not have to specify a prefix and suffix, as the journals are generated with an automatically assigned journal number:

- *EJ_<scenario>_<period>_<counter>*, for Entity journals
- *CJ_<scenario>_<period>_<counter>,* for consolidation journals

In order to avoid any anomalies in the journal numbering, the original scenario recoding utility will not allow a scenario for which journals have already been generated with automatic numbering to be chosen as the source or target scenario.

Moreover, the journal recoding utility will not allow journals prefixed with EJ_ or CJ_ to be recoded, nor will it allow an identifier beginning with EJ_ or CJ_ to be chosen as the new journal number.


Despite these precautions, it will still be possible to encounter gaps in the journal numbering. For example, if some journals are deleted, or if categories, entities, currencies are deleted, or the data table cleaning utility is used. The copy utilities may also discard some journals, but in this case it will also be noted that the scenario/period contained in the journal number does not correspond to the scenario/period to which the journal was copied.

Entity journals

Introduction

Entity journals are data related to a single entity that are used to "correct" original financial statement amounts. They are generally used to standardise the financial statements of entities in accordance with the accounting standards adopted by the group's holding company and to standardise the financial statements to be aggregated.

Entity journals are created to record the following variations:

- variation in depreciation percentage
- variation in certain cost allocation criteria
- variation in the inventory valuation

Entity journals do not change the original data as they are created on the "Entity journals" category.

Entity journals can be inserted on original scenarios/periods by both the Contributor user and the Consolidator user.

Editor user	Description
Contributor	Entity journals are inserted on categories whose type is “Entity journals” by users authorised to enter amounts for the entity. The journals are subject to diagnostics and submitted together with the financial statements data.
Consolidator	Entity journals are inserted on categories whose type is “Consolidator entity journals” by users who are authorised to insert the consolidation journals of the first node to be submitted above the entity. The journals are submitted together with the consolidation journals of that node. ***Note**: as consolidated financial statements can have several levels of consolidation, there can be several consolidators who operate on different levels of the group hierarchy.*

Consolidation journals

Introduction

Consolidation journals allow the consolidator user to perform the following actions:

- supplement journals generated by CCH Tagetik
- enter manual adjustment entries for the consolidation (e.g. eliminations of intercompany profits, depreciation of goodwill, dividend write offs, etc.)

Consolidation journals are processed as entity journals, however they have the following particular features:

- they are allocated to the “consolidation journals” category
- they generally involve two entities

Consolidation journal types

Consolidation journals are classified depending on the type of consolidation operation that they represent:

- elimination of dividends
- revaluations/write-downs of financial investments
- elimination of financial investments
- valuation at net equity
- net equity reclassification (NER)
- intercompany eliminations
- currency conversion
- minorities calculation
- valuation of entities at equity
- mergers
- deconsolidation
- other consolidation journals

Draft journals

Introduction

You can give journals “Draft” status to be able to process them without impacting the result of data processing or data reporting.

This function is applied by category (Categories for draft journals page), where it is possible to enable the function for the following categories:

- Entity journals
- Consolidator entity journals
- Consolidation journals.

For this function, it is also possible to define general rules and overrides, or deviations from the general rule to be applied to specific processes.

A journal is automatically created in 'Draft' status when its category is one of those for Draft journals.

When a journal has “Draft” status, it is indicated by an icon ( ). The rows inserted up to that point are not edited ( ), and are locked due to “Row already posted”, but remain visible in any case. Any new rows are inserted in a provisional area and are not visible to data processing or reports. These new rows remain in a provisional state until publication on the journal.

Once the journal is posted , all rows will become non-editable Only the insertion of new rows will be permitted, which will automatically return the journal to the 'Draft' status.

To edit already posted rows, you must first undo their publication.

All operations related to publishing, unpublishing, and converting the journal into the Draft mode are tracked and can be consulted by means of the 'Show journal Log' function.

***IMPORTANT**: if the journal has draft status, when saving each row edit, all the calculated base type accounts which belong to the process and have one of the accounts edited in the journal as their input are run, except for calculated accounts with MD type.*

Journal publication

This data processing transforms draft journals into journals that influence the financial statement results (profit & loss result and balance sheet result).

The data processing can be run from the processes cockpit, in several ways:

Cockpit	Path
Contributor	Edit Windows > Edit Entity journals > select Draft Journal > > Submission and Porting > Post the selected draft journals Edit Windows > Edit Entity journals > > Post all the draft Journals Entity journal cockpit > select draft journal > Submission and porting > Post
Consolidator	Edit Windows > Edit Entity journals > select Draft Journal > > Submission and Porting > Post the selected draft journals Edit Windows > Edit Entity journals > > Post all the draft Journals Edit Windows > Edit consolidation journals > select Draft Journal > > Submission and Porting > Post the selected draft journals Edit Windows > Edit consolidation journals > > Post all the draft Journals Entity journal cockpit > select draft journal > Submission and porting > Post Consolidation journal cockpit > select draft journal > Submission and porting > Post

Before posting a journal, CCH Tagetik checks that the following requirements are met:

- The user must be responsible for entering the data of the entity to which the journal belongs. For this reason, they must fulfil at least one of these conditions:

- Be the editor of the entity to which the entity journal belongs.
- Be the editor of the consolidation node of the entity to which the consolidator entity journal belongs.
- Be the editor of the consolidation node of the relationship between the entities to which the consolidation journal belongs.

- The editability checks are satisfied, including the one that verifies that, if journal submission is enabled, the journal is submitted.
- The journal category must be one of those selected in the journal rules as categories for which to manage “Draft” journal status.
- Any check selected in the journal rules (Journal rules and settings page) with the **Draft journals - Check** option, must be passed. In particular, the following checks can be requested:
  - Diagnostic result: the journal’s publication is only allowed if no blocking errors are detected.
  - Journal balancing: the journal’s publication is only allowed if the journal is balanced.

Journals unposting

This data processing cancels the posting of journals, moving them back to the 'Draft' status so that they can be edited without affecting the data processing result and data reporting.

IMPORTANT: If, in the process submission rules, the data lock for journals with manual/calculated origin has been enabled during journal submission (Submission Rules page), then when unposting, rows with origin SUB_% will not be restored and will remain in the public journal section.

The data processing can be run from the processes cockpit, in several ways:

Cockpit	Path
Contributor	*Edit Windows > Edit Entity journals > select Draft Journal > ⋮ > Submission and Porting > Journals unposting*
	Entity journal cockpit > select draft journal > Submission and porting > Unposting
Consolidator	*Edit Windows > Edit Entity journals > select Draft Journal > ⋮ > Submission and Porting > Journals unposting*
	Edit Windows > Edit consolidation journals > select Draft Journal > ⋮ > Submission and Porting > Journals unposting
	Entity journal cockpit > select draft journal > Submission and porting > Unposting
	Consolidation journal cockpit > select draft journal > Submission and porting > Unposting

Before unposting a journal, CCH Tagetik checks that the following requirements are met:

- The user has the rights to unpost contents, i.e., according to what is indicated as 'User enabled for Journals rejection' in the process submission rules:
  - is responsible for the entity to which the journal belongs (owner entity of the entity journal or consolidation node to which the owner entity of the consolidator's entity journal belongs or consolidation node to which the relationship between the owner entities of the consolidation journals belongs)
  - is responsible for the parent node of the entity to which the journal belongs. The parent entity of a given entity is the first node to be submitted or approved in the data collection process, obtained by moving up the tree of the entity hierarchy associated with the process from the given (excluded) element. If such a node is not found, the first node to be consolidated is taken in the consolidation process, always obtained by moving up the tree starting from the given (excluded) element. The parent node of a consolidator node is the first node to be

consolidated in the consolidation process, obtained by moving up the tree of the Entity hierarchy associated with the process from the given element (excluded)

- The editability checks are satisfied, including the one that verifies that, if journal submission is enabled, the journal is not submitted.
- The journal category must be one of those selected in the journal rules as categories for which to manage “Draft” journal status.

Diagnostic on draft journals

When the function is active, or has been activated on at least one category, the diagnostic also runs the “draft journals” check. This check lists the draft journals linked to the diagnosed scenario/period/entity. The severity of these results is always blocking because it is not possible to submit an entity’s data if there are draft journals. The step attributed to these results is linked to the accounts (accounts/category) used in the draft journals and corresponds to the lesser step.

***IMPORTANT**: this check cannot be selected from the run window because it is always performed.*

The diagnostic result linked to draft journals, or to aggregated categories which also contain just one draft journal, are indicated with the “Draft” status icon ( ). This makes it possible to quickly identify, in the diagnostic result, reports that are still in progress because they are linked to draft data.

Draft journal submission

When the functionality is active and the submission uses the diagnostic result to validate data, the submission of an entity on a certain step is blocked by the presence of draft journals on that step. In any case, you can override submission as an exception or by authorising blocking errors. However, in this case the draft data are simply ignored and will not be posted. To submit them, it is first necessary to reject, remove the 'Draft' status and then to re-submit all the entity data.

Journal submission, on the other hand, is also permitted on draft journals. Not only is it allowed, but it is compulsory to submit the journals in order to post them.

For convenience, when the journal submission is active, the 'Submit and Post' function is available for journals in 'Draft' status. In this case, the user submitting the journal may also post it.

Similarly, once the journal has been posted, the rejecting user can use the 'Reject and Unpost' function.

Particular features of utilities run on draft journals

The following data processing is accessible to the Administrator user in the various pages of CCH Tagetik.

Data Processing	Description
Open/Close Custom Dimension	Also updates data present in draft journals.
Recoding	Also updates data present in draft journals, whether the recoding concerns a dimension code or a journal number.
Deletion	Also deletes data present in draft journals.
Store data offline	Does not run the store data offline operation and shows the message “It's not possible to archive scenarios/periods with draft Journals.”
Data tables clean-up **Clean up data that is inconsistent with the process** **Journals clean-up**	The functions that remove dimensions that are no longer used or are no longer present in the selected process from the data tables also remove data present in draft journals. The function that removes the headers of journals with no content checks that no data are present in the draft journals.

Data Processing	Description
Clone Process	Also clones data present in draft journals. In particular, if the category is one of those used for draft journals, the journals with “public” status in the source scenario will be copied to the target scenario with “draft” status. It is advisable to perform data processing on consolidation scenarios in the cloned process, in order to clean up the effects of journals that were copied with a 'draft' status.
Create/Restore Snapshot	Also copies or restores data present in draft journals.
Copy Amounts and Journals	Also copies data present in draft journals. Specifically: • if the category in the target process is one of those designated for draft journals, the journals will be copied with 'draft' status, even if they are posted in the source process • if the category in the target process is not one of those designated for draft journals, journals in 'draft' status will not be copied
Copy Consolidation	Also copies data present in draft journals. Specifically: • if the category in the target process is one of those used for draft journals, journals with a 'public' status in the source scenario will be copied to the target scenario with a 'draft' status • if the category in the target process is not one of those designated for draft journals, journals in 'draft' status will not be copied At the end of the copying process, it is advisable to perform the data processing on the consolidation scenarios in the target process, in order to clean up the effects of journals that were copied with a 'draft' status.
Data Rounding	Also rounds data present in draft journals.
Change Entity Currency	Also changes the currency of data present in draft journals.
Segment - Custom dimension replacement	Also replaces the custom dimension in data present in draft journals.
Create BS Ctp (Entity journals)	It does not create BS CTPs and shows the message 'Unable to proceed. Some of the selected Journals are draft Journals'.
Create Depreciation plan	Depreciation plans are generated per journal. Depreciation plan generation is not allowed for draft journals

Data Processing	Description
Copy Journal	Copying is performed per individual journal, even if the journal is in 'Draft' status. Specifically: • if the category in the target process is one of those designated for draft journals, the journal will be copied with 'Draft' status, even if it is posted in the source process • if the category in the target process is not one of those used for draft journals, the journal with a 'draft' status will not be copied
Next period headers wizard	It carries forward headers to subsequent periods for draft journals as well.
Edit category	Also changes the category for draft journals.
Delete journals	Also deletes draft journals
Consolidate (consolidation journals)	It does not perform consolidation for draft journals, and reports them in the audit.

Headers (Entity Journals) page

User

Processes tile > select process > Consolidator > Overview tab or Step tab > (Actions) Edit windows > Edit Entity Journals

Processes tile > select process > Contributor > Detail summary tab or Step tab > (Actions) Edit windows > Edit Entity Journals

Processes tile > select process > Step tab > from a workflow task > select an Entity journals task > Run

Navigation panel > Processes > select process > Consolidator > Overview tab or Step tab > (Actions) Edit windows > Edit Entity Journals

Navigation panel > Processes > select process > Contributor > Detail summary tab or Step tab > (Actions) Edit windows > Edit Entity Journals

Navigation panel > Processes > select process > Step tab > from a workflow task > select an Entity journals task > Run

Purpose of the page

This page allows you to define the composition of entity journal headers. It also shows certain calculated, non-editable information for every header.

Icons on this page

Element	Description
	Journal being created and not yet saved
	Journal being deleted and not yet saved

Element	Description
	Journal not balanced
	Draft Journal
	Journal containing attached documents/journal with amortisation/depreciation plan
	The headers cannot be edited. Shows the reason for the lock.

Actions on this page

Element	Description
	Spreadsheet view: shows the data in a spreadsheet.
	List view: shows the data in a table. Default view.
	**Submit all automatic journals**: Only if journal submission on at least one entity is active on the process. Opens a window to select the scenario/period and the step for which to submit all automatic journals, or those for which rows with manual origin are not present (INPUT_WEB, INPUT_DEFORM, BREAK_BACK, QDL or MAP_%). See Submission data processing in the Data Processing section. **Post all the draft Journals**: Only if categories for which to manage “Draft journal” status are defined on the process. Opens a window to select the scenario/period for which to post all the draft journals, thus making them visible to data processing and reports. See Draft Journals.
	Allows you to access specific actions for the headers, see Actions from the journal headers.

Attributes on the page

The following information is shown in addition to the attributes that can be defined from the configuration tabs:

 *Not all attributes may be visible by default. Click*  *to select other columns to be shown.*

Field	Description
In progress	Indicates whether the journal includes “Draft” rows (). These do not influence the result of the data processing or the reports until they are published. Only present if the relative function is activated by creating categories for draft journals (Journal rules and settings page).
Balancing	Indicates whether or not the journal is balanced. If it is not, the journal will be reported (✖). ***Note**: balancing is calculated by adding the amounts of all accounts of “Balance Sheet” nature and “Normal” type that are present in the journal rows.*
Documents	Indicates whether there are any documents attached to the journal.
Depreciation	Indicates whether the journal manages depreciation.
Manual rows	Indicates whether the journal contains rows with manual origin.
Journal number	Identifier of the journal within the scenario/period. During data entry, it is calculated according to the journal numbering method defined in the default settings (seeDefault Settings window): • if the journal numbering method is manual, it is calculated by concatenating the journal prefix and suffix • if the numbering method is automatic, it is generated by the system by concatenating EJ_<scenario>_<period>_<counter> (for entity journals) or CJ_<scenario>_<period>_<counter> (for consolidation journals)

Field	Description
Generator type	For automatically generated journals, this indicates the data processing that generated them. • Ctp elimination logic • Reclassification accounts logic • NER logic • Closing version rule • Mapping • Look Through Vehicle entity • IFRS5 event • Look Through operational entity • IFRS5 IC eliminations write off • Rules Engine Designer
Generator	For automatically generated journals, it indicates the code of the generator. *For example, if the generator type is equal to "CTP elimination logic", it will contain the code of the elimination logic.*
Original generator	For automatically generated journals, it indicates the code of the generator of the original journal from which the journal was generated.
Original category	For automatically generated journals, it indicates the category code of the original journal from which the journal was generated.
Original entity 1	For automatically generated journals, it indicates the entity code of the original journal from which the journal was generated.

Attributes in the General tab

Field	Description
Scenarios	Scenario to which the journal belongs. You can choose an active original scenario, which you can edit and for which there exists at least one unblocked period belonging to the selected process. ***IMPORTANT**: once saved, this data can no longer be edited.*
Period	Period to which the journal belongs. The chosen period must not be locked and must be linked to the selected scenario. ***IMPORTANT**: once saved, this data can no longer be edited.*
Entity	Entity to which the journal belongs. The chosen entity must meet the following requirements: • Editable for the user. For contributor entity journals, the user must be the entity's editor. For consolidator entity journals, the user must be the editor of the consolidation node to which the entity belongs. • Belong to the selected process. • Belong to the selected scenario/period and, on that scenario/period, cannot be an "Only CTP" entity. • Start date and end date, if present, must be between the start date and end date of the selected scenario/period. ***IMPORTANT**: once saved, this data can no longer be edited.*

Field	Description
Journal prefix	Only if the journal numbering method defined in the default settings is manual. Prefix to be used when inserting a new journal to form its number. By default, the prefix defined as the **Journal prefix** is used (see Default Settings window). ***IMPORTANT**: do not enter any prefixe used by data processes generating automatic journals ("MIN_", "EQ_", "GPN_", "ELICTP_", "RECL_", "EQNFI_", "MRECL_", "IFRS5_", "EPUA_", "EPUT_", "LTO_", "LTV_", "ESM_", "ESR_", "EJ_", "CJ_").*
Journal suffix	Only if the journal numbering method defined in the default settings is manual. Suffix to be used when inserting a new journal to form its number.
Unit	Currency assigned to the entity in the process. Defined automatically and non-editable.
Category	Journal category. The chosen categories must meet the following requirements: • Editable by the user. • Belong to the selected process. • If the page is opened from the Contributor cockpit, the category type must be “contributor entity journals”. • If the page is opened from the Consolidator cockpit, the category type must be “contributor entity journals” or “consolidator entity journals”. Based on the category assigned to the journal, certain information is entered automatically according to what is defined in the categories list in the **Default for manual journals** section. See Categories list in the Data Model section. ***Note**: journals attributed to the same category are generally processed and treated in the same way.*
Note	Any explanatory notes
Advanced settings	
Periodic journal	Enables periodic management for the journal. See Journal management.
Consolidation scenarios filter	With the **Consolidation scenario** function (Consolidation scenario page), it allows you to filter the consolidation scenarios in which a journal is considered. ***Note**: in general, the system decides whether journal is included in a consolidation scenario according to the entity and the category.*
Journal is complete	Indicates that the journal’s insertion is complete. *This can be used, for example, to indicate journals that are ready to be valued to change category.*
Grouping for Journals book	Label that allows you to group the journals within the journal book, if this is run with the **Journals grouping** option = “Journals grouping” (Headers (Consolidation journals) page).

Attributes in the Data Processing tab

Field	Description
Overridden data processing parameters	If enabled, this allows you to override the setup of the **Tax calculation method**, **Reverse journal type** and **Enable carry forward** options so they are no longer the defaults set in the category list. See Categories list in the Data Model section.
Tax calculation method	Indicates the calculation method for deferred taxes. If **Override journal parameters** is selected, it can be set as follows: • None • Entity 1 • Entity 1 -Invert credits/debits • Permanent OCI • Permanent P&L Otherwise, it is set according to the categories list.
Reverse journal type	Only if **Override journal parameters** is selected. Indicates whether and how the journal must be automatically reversed in the restore step. It can be set as follows: • None • Set BS accounts to 0 (cut off) • Set BS accounts to 0 and Write off P&L impact (IC) • Set BS accounts and Variations to 0 and Write off P&L impact (IC) Otherwise, it is set according to the categories list.
Enable carry forward	Only if **Override journal parameters** is selected. Indicates whether or not the journal must be carried forward into the subsequent scenario. If **Override journal parameters** is not selected, it is set as per the categories list.

Attributes of the Submission status tab

Field	Description
<Selected step> - Status	If journal submission is active, this indicates the submission status of the journal in the step. It can be set as follows: • Not Started • Started • Rejected • In Submission • Submitted • Not relevant. This is the case if the journal submission is not enabled for the step or the entity/node to which the journal belongs.
<Selected step> - User	If journal submission is active, this tells the user who performed the journal's most recent submission activity in the step.
<Selected step> - Date	If journal submission is active, this indicates the date on which the journal's most recent submission activity in the step was performed.

Rows (Entity Journals) page

User

Processes tile > select process > Contributor > Detail summary tab or Step tab > (Actions) Edit windows > Edit Entity Journals > select header > ⋮ > Rows

Processes tile > select process > Consolidator > Overview tab or Step tab > (Actions) Edit windows > Edit Entity Journals > select header > ⋮ > Rows

Processes tile > select process > Step tab > from a workflow task > select task whose type is entity journals > Run > select header > ⋮ > Rows

Navigation panel > Processes > select process > Contributor > Detail summary tab or Step tab > (Actions) Edit windows > Edit Entity Journals > select header > ⋮ > Rows

Navigation panel > Processes > select process > Consolidator > Overview tab or Step tab > (Actions) Edit windows > Edit Entity Journals > select header > ⋮ > Rows

Navigation panel > Processes > select process > Step tab > from a workflow task > select an entity journals task > Run > select header > ⋮ > Rows

Purpose of the page

This page allows you to insert the entries that comprise the individual journal. The origin is also shown for every entry.

Entries inserted manually have “INPUT_WEB” indicated as their **Origin**.

> ***Note**: you can configure CCH Tagetik so that entries with different origins are different colours. See **Colours by origin** option in the Settings window in the General Introduction section.*

The page may show a subset of journal rows depending on the filters set by default in the journal rules (Journal rules and settings page) or set specifically for the page (▼).

Filters on the page

The most significant filters for the page and the results that they give you are described below.

Element	Description
Show only main accounts	Allows you to view only accounts that are defined in the process data model as “main accounts on journals” (Process Data Model Definition page in the Processes section). This hides the accounts that are less significant for the journal.
Exclude Result accounts and their variations	This allows you to exclude accounts belonging to the set of result accounts specified from among the requirements of the process’s calculation logics (Calculation logic requirements page in the Processes section). In particular, the Profit & Loss result account, the Balance Sheet result account and their variations, determined taking account only of control groups belonging to the process, are excluded.
Account type	Allows you to view only accounts of the type indicated by the **Journals data entry: account type** option, unless “Any” is selected (Default settings window).
Account nature	Allows you to view only accounts of the selected nature.
CTP Custom dimension 2 allocations	Only present if custom dimension 2 is managed, the process’s relationship type is “entity - custom dimension 2” or “entity - synthetic custom dimension 2”, and the **Spreading - Show CTP custom dimension 2 override type** option is active in the process’s gross and IC amount rules. • **Original data**: excludes rows whose origin is “PROC_IC_SPREADING” or “PROC_IC_SPREADING_CB”. • **Only reallocation**: shows only rows whose origin is “PROC_IC_SPREADING”.

Icons on this page

Element	Description
	Row just added but not yet saved
	Row being deleted but not yet saved
	The rows cannot be edited. The reason for the lock is reported, e.g. “Row already posted” if the user has tried to assign the journal draft status.
	Draft Journal.

Actions on this page

Element	Description
	Spreadsheet view: shows the data in a spreadsheet.
	List view: shows the data in a table. Default view.
	Allows you to access specific actions for the rows, see Actions from the journal rows.

Attributes on the page

Not all attributes are editable.

Field	Description
Scenario	Scenario set in the header. Not editable.
Period	Period set in the header. Not editable.
Journal number	Journal number in the header. Not editable.
Entity	Entity set in the header. Not editable.
Account	Account on which a value is entered. The chosen account must meet the following requirements: • Editable for the user. • Linked to the data model process associated with the entity to which the journal belongs. • Start date and end date, if set, must be between the start date and end date of the scenario/period to which the journal belongs. If the **CTP entity** field is defined, it must allow intercompany data management.
Category	Category set in the header. Not editable.
Custom dimension	For every custom dimension that is managed and enabled in the process’s journal rules, you can select an element of the custom dimension which meets the following requirements: • Editable for the user. • Visible from the entity to which the journal row belongs. • Visible from the selected account. If no value is selected, the custom dimension will be shown as the entity’s default custom dimension or the custom dimension with the lowest code from among those which meet the above requirements. ***IMPORTANT**: the custom dimension 2 is managed even if it is not enabled in the process’s journal rules, but the process’s relationship type is “entity - custom dimension 2” or “entity - synthetic custom dimension 2”.*

Field	Description
CTP entity	Counterparty entity in the journal. An entity can be chosen, provided it meets the following requirements: • Belong to the selected process. • Must belong to the selected scenario/period. • Start date and end date, if present, must be between the start date and end date of the selected scenario/period. You can define a list of most frequently used counterparty entities, see Entities list in the Data Model section. To use only a subset of entities as counterparties, it may be useful to create a group of counterparties (Dynamic counterparty groups). You can also declare IC data in the context of the same entity (and therefore use the same code for both the entity and the counterparty). This is only possible if the **Allow intercompany declarations towards same Declaring entity** option is active (Amount & Intercompany rules page). *For example, this is useful for eliminating dividends received from group companies towards profits carried forward, or for eliminating self-invoicing results.*
CTP custom dimension 2 override type	Only present under the following conditions: • Custom dimension 2 is managed. • The process' relationship type is "entity - custom dimension 2" or "entity - synthetic custom dimension 2". • The **Spreading - Show CTP custom dimension 2 override type** option is active in the process's gross and IC amount rules. • The user's role contains function 0002274. It can be set as follows: • To allocate • None • Override
Counterparty custom dimension 2	Only present under the following conditions: • Custom dimension 2 is managed. • The process' relationship type is "entity - custom dimension 2" or "entity - synthetic custom dimension 2". It is only mandatory under the following conditions: • A CTP entity has been specified. The field is only editable if the **Spreading - Display CTP custom dimension 2 override type** option is active in the process's gross and IC amount rules, or if that option is active and: • The user's role contains function 0002274. • **CTP custom dimension 2 override type** is not "To allocate" If the field is editable, it is defined as the CTP entity's default custom dimension 2 or, if the **Spreading - Show CTP custom dimension 2 override type** and **Show CTP custom dimension 2 with entity's default element** options are not active in the process's gross and IC amount rules, the field is defined as the default custom dimension 2 element specified in the custom dimension 2 settings.
Company currency	Currency set in the header, not editable.

Field	Description
Entity currency amount	Amount expressed in the entity currency. Regardless of the number of decimals inserted, amounts are shown with a number of decimals that is consistent with those assigned to the currency in which they are expressed, with the exception of “Other stocks” and “Other variations” accounts where the **Manage maximum number of decimals** option is active (see Accounts list in the Data Model section). For these accounts, it is possible to insert up to 9 decimals. The amount may be shown in two different columns: **Entity currency amount - debit** and **Entity currency amount - credit**. This happens if the Amounts option is set to **Write amounts in Debit & Credit columns in absolute value** in the journal rules definition (Default Settings window).
Override FX rate	Only present if the transaction currency is managed on entity journals in the process’s journal rules. If selected, you can edit all the amounts in the current row, thereby indirectly overriding the field applied to change from the entity currency amount to the transaction currency amount. Otherwise, only the transaction currency will be editable, but the transaction currency amount will not be. On saving, it automatically defines the amount in the transaction currency based on the account’s conversion type.
Transaction currency	Only present if the transaction currency is managed on entity journals in the process’s journal rules. If not entered, it will be defined as the entity currency.
Transaction currency amount	Only present if the transaction currency is managed on entity journals in the process’s journal rules. If the transaction currency has not been entered or is the same as the entity currency, the field is defined as the entity currency amount. Otherwise, if the **Override FX rate** option is not selected, the entity currency will be defined automatically based on the account’s conversion type. For the rest, the considerations made for the **Entity currency** amount will be valid.
Notes	Any explanatory notes
Additional notes	Any additional notes

Headers (Consolidation journals) page

User

Processes tile > select process > Consolidator > Overview tab or Step tab > (Actions) Edit windows > Edit Consolidation journals

Processes tile > select process > Step tab > from a workflow task > select a Consolidation journals task > Run

Navigation panel > Processes > select process > Consolidator > Overview tab or Step tab > (Actions) Edit windows > Edit Consolidation journals

Navigation panel > Processes > select process > Step tab > from a workflow task > select a Consolidation journals task > Run

Purpose of the page

This page allows you to define the composition of consolidation journal headers. It also shows certain calculated, non-editable information for every header.

Icons on this page

Element	Description
	Journal being created and not yet saved
	Journal being deleted and not yet saved
	Journal not balanced
	Draft journal
	Journal containing attached documents/journal with amortisation/depreciation plan
	The headers cannot be edited. Shows the reason for the lock.

Actions on this page

Element	Description
	Spreadsheet view: shows the data in a spreadsheet.
	List view: shows the data in a table. Default view.
	**Submit all automatic journals**: Only if journal submission on at least one entity is active on the process. Opens a window to select the scenario/period and the step for which to submit all automatic journals, or those for which rows with manual origin are not present (INPUT_WEB, INPUT_DEFORM, BREAK_BACK, QDL or MAP_%). See Submission data processing in the Data Processing section. **Post all the draft Journals**: Only if categories for which to manage "Draft journal" status are defined on the process. Opens a window to select the scenario/period for which to post all the draft journals, thus making them visible to data processing and reports. See Draft Journals.
	Allows you to access specific actions for the headers, see Actions from the journal headers.

Attributes on the page

The following information is shown in addition to the attributes that can be defined from the configuration tabs:

Not all attributes may be visible by default. Click to select other columns to be shown.

Field	Description
In progress	Indicates whether the journal includes "Draft" rows ( ). These do not influence the result of the data processing or the reports until they are published. Only present if the relative function is activated by creating categories for draft journals (Journal rules and settings page).
Balancing	Indicates whether or not the journal is balanced. If it is not, the journal will be reported ( ). ***Note**: balancing is calculated by adding the amounts of all accounts of "Balance Sheet" nature and "Normal" type that are present in the journal rows.*
Documents	Indicates whether there are any documents attached to the journal.
Depreciation	Indicates whether the journal manages depreciation.
Manual rows	Indicates whether the journal contains rows with manual origin.

Field	Description
Journal number	Identifier of the journal within the scenario/period. During data entry, it is calculated according to the journal numbering method defined in the default settings (seeDefault Settings window): • if the journal numbering method is manual, it is calculated by concatenating the journal prefix and suffix • if the numbering method is automatic, it is generated by the system by concatenating EJ_<scenario>_<period>_<counter> (for entity journals) or CJ_<scenario>_<period>_<counter> (for consolidation journals)
Generator type	For automatically generated journals, this indicates the data processing that generated them. • Ctp elimination logic • Reclassification accounts logic • NER logic • Closing version rule • Mapping • Look Through Vehicle entity • IFRS5 event • Look Through operational entity • IFRS5 IC eliminations write off • Rules Engine Designer
Generator	For automatically generated journals, it indicates the code of the generator. *For example, if the generator type is equal to "CTP elimination logic", it will contain the code of the elimination logic.*
Original generator	For automatically generated journals, it indicates the code of the generator of the original journal from which the journal was generated.
Original category	For automatically generated journals, it indicates the category code of the original journal from which the journal was generated.
Original entity 1	For automatically generated journals, it indicates the entity 1 code of the original journal from which the journal was generated.
Original entity 2	In case of automatically generated journal, it indicates the code of Entity 2 of the original journal from which the journal was generated.

Attributes in the General tab

Field	Description
Scenarios	Scenario to which the journal belongs. You can choose an active original scenario, which you can edit and for which there exists at least one unblocked period belonging to the selected process. ***IMPORTANT**: once saved, this data can no longer be edited.*
Period	Period to which the journal belongs. The chosen period must not be locked and must be linked to the selected scenario. ***IMPORTANT**: once saved, this data can no longer be edited.*

Field	Description
Entity 1	One of the two entities in the relationship to which the journal belongs. The chosen entity must meet the following requirements: • Must be visible for the user. • Belong to the selected process. • Belong to the selected scenario/period and, on that scenario/period, cannot be an "Only CTP" entity. • Start date and end date, if present, must be between the start date and end date of the selected scenario/period. ***IMPORTANT**: once saved, this data can no longer be edited.*
Custom dimension 2 1	Only if custom dimension 2 is managed and the process's relationship type is "entity - custom dimension 2". You can only select an element of the custom dimension 2 that is visible to entity 1. ***IMPORTANT**: once saved, this data can no longer be edited.*
Entity 2	One of the two entities in the relationship to which the journal belongs. The chosen entity must meet the following requirements: • Must be visible for the user. • Belong to the selected process. • Belong to the selected scenario/period and, on that scenario/period, cannot be an "Only CTP" entity. • Start date and end date must be between the start date and end date of the selected scenario/period. ***IMPORTANT**: once saved, this data can no longer be edited.*
Custom dimension 2 2	Only if custom dimension 2 is managed and the process's relationship type is "entity - custom dimension 2". You can only select an element of the custom dimension 2 that is visible to entity 2. ***IMPORTANT**: once saved, this data can no longer be edited.*
Journal prefix	Only if the journal numbering method defined in the default settings is manual. Prefix to be used when inserting a new journal to form its number. By default, the prefix defined as the **Journal prefix** is used (see Default Settings window). ***IMPORTANT**: do not enter any prefixe used by data processes generating automatic journals ("MIN_", "EQ_", "GPN_", "ELICTP_", "RECL_", "EQNFI_", "MRECL_", "IFRS5_", "EPUA_", "EPUT_", "LTO_", "LTV_", "ESM_", "ESR_", "EJ_", "CJ_").*
Journal suffix	Only if the journal numbering method defined in the default settings is manual. Suffix to be used when inserting a new journal to form its number.
Unit	Journal currency. ***IMPORTANT**: once saved, this data can no longer be edited.*

Field	Description
Category	Journal category. The chosen categories must meet the following requirements: • Editable by the user. • Belong to the selected process. • The category type must be “consolidation journal”. Based on the category assigned to the journal, certain information is entered automatically according to what is defined in the categories list in the **Default for manual journals** section. See Categories list in the Data Model section. ***Note**: journals attributed to the same category are generally processed and treated in the same way.*
Note	Any explanatory notes Field not editable if the journal is generated by counterparty eliminations. ***Note**: all journals whose number starts with “ELICTP_” are considered to be journals generated by the counterparty eliminations.*
Advanced settings	
Periodic journal	Enables periodic management for the journal. See Journal management.
Many to many relationship	Indicates whether the journal rows can be attributed to any entity (and custom dimension, if the process’s relationship type is “entity - custom dimension 2”), regardless of what is declared in the header. Field not editable if the journal is generated by counterparty eliminations ***Note**: all journals whose number starts with “ELICTP_” are considered to be journals generated by the counterparty eliminations.*
Consolidation scenarios filter	With the **Consolidation scenario** function (Consolidation scenario page), it allows you to filter the consolidation scenarios in which a journal is considered. ***Note**: in general, the system decides whether journal is included in a consolidation scenario according to the entity and the category.*
Journal is complete	Indicates that the journal’s insertion is complete. *This can be used, for example, to indicate journals that are ready to be valued to change category.* Field not editable if the journal is generated by counterparty eliminations. ***Note**: all journals whose number starts with “ELICTP_” are considered to be journals generated by the counterparty eliminations.*
Grouping for Journals book	Label that allows you to group the journals within the journal book, if this is run with the **Journals grouping** option = “Journals grouping” (Headers (Consolidation journals) page). Field not editable if the journal is generated by counterparty eliminations ***Note**: all journals whose number starts with “ELICTP_” are considered to be journals generated by the counterparty eliminations.*

Attributes in the Data Processing tab

Field	Description
Overridden data processing parameters	If enabled, it allows you to override the setup of the **Proportional calculation method**, **Minorities calculation method**, **Minorities calculation on entity 1**, **Minorities calculation on entity 2**, **Equity evaluation method**, **Tax calculation method**, **Reverse journal type**, **Enable carry forward**, and **Exclude Reclassifications and NER** options so they are no longer the default set in the categories list or elimination logic. See Categories list in the Data Model section and Intercompany matching and elimination logics in the Consolidation section.
Proportional calculation method	Only if **Override journal parameters** is selected. This indicates how to determine the proportional calculation percentage: • None • Lesser % • Greater % • Entity 1 % • Entity 1 % * Entity 2 % (only for processes that use the “In memory” consolidation engine). If **Override journal parameters** is not selected and the generator type is “CTP elimination logic”, then it is defined using what is present on the elimination logic indicated in **Generator**. For other types of generator, it is defined using the relative value present in the categories list.
Minorities calculation method	Only if **Override journal parameters** is selected. This defines how to calculate the minorities: • Sentence case • Based on Entity 1 % • Advanced (selectable only if the journal type is not "Many to many relationship") • None If **Override journal parameters** is not selected and the generator type is “CTP elimination logic”, then it is defined using what is present on the elimination logic indicated in **Generator**. For other types of generator, it is defined using the relative value present in the categories list.

<table>
<tr><th>Field</th><th>Description</th></tr>
<tr><td>Minorities calculation on entity 1</td><td>Indicates how to calculate the minorities on entity 1.
If these requirements are met:
Override journal parameters is selected
The process manages In memory consolidation, i.e. in general configuration the consolidation engine is set to “In memory” or “Defined by process” and on the process, among the consolidation requirements, the in memory consolidation engine is selected.
The minorities calculation method is Advanced.
It can take the following values:
Based on entity 1 %
Based on Entity 2 %
None
If one of the requirements is not met, then:
if Override journal parameters is selected:<table><tr><th>If the minorities calculation method is...</th><th>Then it is defined as...</th></tr><tr><td>Normal or Based on entity 1 %</td><td>Based on entity 1 %</td></tr><tr><td>None</td><td>None</td></tr><tr><td>Advanced (but the process does not manage in memory consolidation)</td><td>Based on entity 2 %</td></tr></table>If Override journal parameters is not selected:<table><tr><th>If the generator type is...</th><th>Then it is defined as...</th></tr><tr><td>Ctp elimination logic</td><td>what is present on the elimination logic indicated in Generator.</td></tr><tr><td>another type</td><td>the relative value present in the categories list.</td></tr></table></td></tr>
</table>

<table>
<tr><th>Field</th><th>Description</th></tr>
<tr><td>Minorities calculation on entity 2</td><td>Indicates how to calculate the minorities on entity 2
If these requirements are met:
Override journal parameters is selected
The process manages In memory consolidation, i.e. in general configuration the consolidation engine is set to “In memory” or “Defined by process” and on the process, among the consolidation requirements, the in memory consolidation engine is selected.
The minorities calculation method is Advanced.
It can take the following values:
Based on entity 1 %
Based on Entity 2 %
None
If one of the requirements is not met, then:
if Override journal parameters is selected:<table><tr><th>If the minorities calculation method is...</th><th>Then it is defined as...</th></tr><tr><td>Sentence case</td><td>Based on entity 2 %</td></tr><tr><td>Based on entity 1 %</td><td>Based on entity 1 %</td></tr><tr><td>None</td><td>None</td></tr><tr><td>Advanced (but the process does not manage in memory consolidation)</td><td>Based on entity 2 %</td></tr></table>If Override journal parameters is not selected:<table><tr><th>If the generator type is...</th><th>Then it is defined as...</th></tr><tr><td>Ctp elimination logic</td><td>what is present on the elimination logic indicated in Generator.</td></tr><tr><td>all other types of generator</td><td>the relative value present in the categories list.</td></tr></table></td></tr>
<tr><td>Equity evaluation method</td><td>Only if Override journal parameters is selected. This indicates what the system should do during the equity evaluation step where there is an entity at equity:
None
Delete
Evaluate with equity method: single Entity journals
Evaluate with equity method: if entity 2 is at equity (only if entity 1 and entity 2 are different)
If Override journal parameters is not selected and the generator type is “CTP elimination logic”, then it is defined using what is present on the elimination logic indicated in Generator. For other types of generator, it is defined using the relative value present in the categories list.</td></tr>
</table>

Field	Description
Tax calculation method	Only if **Override journal parameters** is selected. Indicates the calculation method for deferred taxes: • None • Entity 1 • Entity 2 • Entity 1 -Invert credits/debits • Entity 2 -Invert credits/debits • Permanent OCI • Permanent P&L If **Override journal parameters** is not selected and the generator type is "CTP elimination logic", then it is defined using what is present on the elimination logic indicated in **Generator**. For other types of generator, it is defined using the relative value present in the categories list.
Reverse journal type	Only if **Override journal parameters** is selected. Indicates whether and how the journal must be automatically reversed in the restore step. It can be set as follows: • None • Set BS accounts to 0 (cut off) • Set BS accounts to 0 and Write off P&L impact (IC) • Set BS accounts and Variations to 0 and Write off P&L impact (IC) If **Override journal parameters** is not selected and the generator type is "CTP elimination logic", then it is defined using what is present on the elimination logic indicated in **Generator**. For other types of generator, it is defined using the relative value present in the categories list. For details on reversals, see Journal reversal data processing in the Consolidation section.
Enable carry forward	Only if **Override journal parameters** is selected. Indicates whether or not the journal must be carried forward into the subsequent scenario. If **Override journal parameters** is not selected and the generator type is "CTP elimination logic", then it is defined using what is present on the elimination logic indicated in **Generator**. For other types of generator, it is defined using the relative value present in the categories list.
Exclude Reclassifications and NER	Only if **Override journal parameters** is selected. This indicates whether equity reclassification and account reclassification must be carried out for the journal. If **Override journal parameters** is not selected and the generator type is "CTP elimination logic", then it is defined using what is present on the elimination logic indicated in **Generator**. For other types of generator, it is defined using the relative value present in the categories list.

Attributes of the Submission status tab

Field	Description
<Selected step> - Status	If journal submission is active, this indicates the submission status of the journal in the step. It can be set as follows: • Not Started • Started • Rejected • In Submission • Submitted • Not relevant. This is the case if the journal submission is not enabled for the step or the entity/node to which the journal belongs.
<Selected step> - User	If journal submission is active, this tells the user who performed the journal's most recent submission activity in the step.
<Selected step> - Date	If journal submission is active, this indicates the date on which the journal's most recent submission activity in the step was performed.

Rows (Consolidation journals) page

User

Processes tile > select process > Consolidator > Overview tab or Step tab > (Actions) Edit windows > Edit Consolidation journals > select header > ⋮ > Rows

Processes tile > select process > Step tab > from a workflow task > select a consolidation journals task > Run > select header > ⋮ > Rows

Navigation panel > Processes > select process > Consolidator > Overview tab or Step tab > (Actions) Edit windows > Edit Consolidation journals > select header > ⋮ > Rows

Navigation panel > Processes > select process > Step tab > from a workflow task > select a consolidation journals task > Run > select header > ⋮ > Rows

Purpose of the page

This page allows you to insert the entries that comprise the individual journal. It also shows the origin for every entry.

Entries inserted manually have "INPUT_WEB" indicated as their **Origin**.

> ***Note**: you can configure CCH Tagetik so that entries with different origins are different colours. See **Colours by origin** option in the Settings window in the General Introduction section.*

The page may show a subset of journal rows depending on the filters set by default in the journal rules (Journal rules and settings page) or set specifically for the page (▼).

Filters on the page

The most significant filters for the page and the results that they give you are described below.

Element	Description
Show only main accounts	Allows you to view only accounts that are defined in the process data model as “main accounts on journals” (Process Data Model Definition page in the Processes section). This hides the accounts that are less significant for the journal.
Exclude Result accounts and their variations	This allows you to exclude accounts belonging to the set of result accounts specified from among the requirements of the process’s calculation logics (Calculation logic requirements page in the Processes section). In particular, the Profit & Loss result account, the Balance Sheet result account and their variations, determined taking account only of control groups belonging to the process, are excluded.
Account type	Allows you to view only accounts of the type indicated by the **Journals data entry: account type** option, unless “Any” is selected (Default settings window).
Account nature	Allows you to view only accounts of the selected nature.

Icons on this page

Element	Description
	Row just added but not yet saved
	Row being deleted but not yet saved
	The rows cannot be edited. The reason for the lock is reported, e.g. “Row already posted” if the user has tried to assign the journal draft status.
	Draft Journal.

Actions on this page

Element	Description
	Spreadsheet view: shows the data in a spreadsheet.
	List view: shows the data in a table. Default view.
	Allows you to access specific actions for the rows, see Actions from the journal rows.

Attributes on the page

Not all attributes are editable.

Field	Description
Scenario	Scenario set in the header. Not editable.
Period	Period set in the header. Not editable.
Journal number	Journal number in the header. Not editable.
Entity	If the journal type is not “many to many relationship”, you can choose one of the two header entities. The other is automatically set as “Segment CTP Entity”. If the journal type is “many to many relationship”, the chosen entity must meet the following requirements: • Editable by the user. • Belong to the selected process. • Belong to the selected scenario/period and, on that scenario/period, cannot be an “Only CTP” entity. • Start date and end date, if present, must be between the start date and end date of the selected scenario/period. • Must belong to aùconsolidation node that is editable for the user.

<table>
<tr><th>Field</th><th>Description</th></tr>
<tr><td>Category</td><td>Category set in the header. Not editable.</td></tr>
<tr><td>Account</td><td>Account on which a value is entered.
The chosen account must meet the following requirements:
Editable for the user.
Linked to the data model process associated with the entity to which the journal belongs.
Start date and end date, if set, must be between the start date and end date of the scenario/period to which the journal belongs.</td></tr>
<tr><td>Custom dimension</td><td>For every custom dimension that is managed and enabled in the process's journal rules, you can select an element of the custom dimension which meets the following requirements:
Editable for the user.
Visible from the selected entity.
Visible from the selected account.
If no value is selected, the custom dimension will be shown as the entity's default custom dimension or the custom dimension with the lowest code from among those which meet the above requirements.

IMPORTANT: the custom dimension 2 is managed even if it is not enabled in the process's journal rules, but the process's relationship type is "entity - custom dimension 2" or "entity - synthetic custom dimension 2".

If the relationship type is "entity - custom dimension 2" and the journal type is "many to many relationship", the system will behave as follows:<table><tr><th>If...</th><th>Then...</th></tr><tr><td>the selected entity is the same as the header's entity 1</td><td>the custom dimension 2 is defined as the header's custom dimension 2 1.</td></tr><tr><td>the selected entity is the same as the header's entity 2</td><td>the custom dimension 2 is defined as the header's custom dimension 2 2.</td></tr><tr><td>the header's entity 1 and entity 2 are the same</td><td>You can decide which of the header's custom dimension 2s to assign to the custom dimension 2. The other will be assigned to the segment CTP custom dimension 2.</td></tr></table></td></tr>
<tr><td>CTP entity</td><td>Typically inserted if the journal is used to eliminate an entry that had been declared with a counterparty in the financial statements of the individual entity.
If the journal type is not "many to many relationship" and the Manage CTP entity and CTP custom dimension 2 independently of the header relationship option is not enabled in the process's journal rules, if defined it must be the same as the segment CTP entity.
If the journal type is "many to many relationship" or the Manage CTP entity and CTP custom dimension 2 independently of the header relationship option is enabled in the process's journal rules, the chosen entity must meet the following requirements:
Belong to the selected process.
Must belong to the selected scenario/period.
Start date and end date, if present, must be between the start date and end date of the selected scenario/period.
You can define a list of most frequently used counterparty entities, see Entities list in the Data Model section.
To use a subset of entities as counterparties, it may be useful to create a group of counterparties (Dynamic counterparty groups).</td></tr>
</table>

<table>
<tr><th>Field</th><th>Description</th></tr>
<tr><td>Counterparty custom dimension 2</td><td>Only present under the following conditions:
Custom dimension 2 is managed.
The process' relationship type is “entity - custom dimension 2” or “entity - synthetic custom dimension 2”.
It is only mandatory if a CTP entity has been specified.

If the process relationship type is “entity - custom dimension 2”, the journal type is not “many to many relationship” and the Manage CTP entity and CTP custom dimension 2 independently of the header relationship option is not enabled in the process's journal rules, if defined it must be the same as the segment CTP custom dimension 2.

In other cases, you can select an element of the custom dimension 2 and, if no value is selected but the field is mandatory, the counterparty custom dimension 2 is automatically set as the CTP entity's default custom dimension.</td></tr>
<tr><td>Segment CTP Entity</td><td>If the journal type is not “many to many relationship”, it is possible to choose one of the two header entities (the one not selected as “Entity”). If the journal type is “many to many relationship”, the chosen entity must meet the following requirements:
Editable for the user.
Belong to the selected process.
Belong to the selected scenario/period and, on that scenario/period, cannot be an “Only CTP” entity.
Start date and end date, if present, must be between the start date and end date of the selected scenario/period.
Must belong to aùconsolidation node that is editable for the user.</td></tr>
<tr><td>Segment CTP custom dimension 2</td><td>Only shown if custom dimension 2 is managed and the process's relationship type is “entity - custom dimension 2” or “entity - synthetic custom dimension 2”.

If the relationship type is “entity - custom dimension 2” and the journal type is “many to many relationship”, the system will behave as follows:<table><tr><th>If...</th><th>Then...</th></tr><tr><td>the selected segment CTP entity is the same as the header's entity 1</td><td>the segment CTP custom dimension 2 is defined as the header's custom dimension 2 1.</td></tr><tr><td>the selected segment CTP entity is the same as the header's entity 2</td><td>the segment CTP custom dimension 2 is defined as the header's custom dimension 2 2.</td></tr><tr><td>the header's entity 1 and entity 2 are the same</td><td>You can decide which of the header's custom dimension 2s to assign to the segment CTP custom dimension 2. The other will be assigned to the custom dimension 2.</td></tr></table>In other cases, you can select a visible element of the custom dimension 2 of the selected segment CTP entity and, if no value is selected, the segment CTP custom dimension 2 is automatically set as the segment CTP entity's default custom dimension.</td></tr>
<tr><td>Journal currency</td><td>Header currency. Not editable.</td></tr>
</table>

Field	Description
Journal currency amount	Amounts are indicated with the sign defined in the account list settings. Alternatively, you can show the debit and credit in two different columns: **Journal currency amount - Debit** and **Journal currency amount - Credit**. This happens if the **Amounts** option is set to **Write amounts in Debit & Credit columns in absolute value** in the journal rules definition (Default Settings window). Regardless of the number of decimals inserted, amounts are shown with a number that is consistent with those assigned to the currency they are expressed in, with the exception of "Other stocks" and "Other variations" accounts where the **Manage maximum number of decimals** option is active (see Accounts list in the Data Model section). For these accounts, it is possible to insert up to 9 decimals.
Override FX rate	If selected, it is possible to edit all the amounts in the current row, thereby indirectly overriding the field applied to change from the journal currency amount to the entity currency amount or transaction currency amount. Otherwise, only the entity currency and transaction currency will be editable, but the amount will not be. On saving, it automatically defines the row amount in the entity currency and the transaction currency based on the account's conversion type.
Company currency	If not entered, it will be defined as the selected entity's currency.
Entity currency amount	If the entity currency is not entered, or is the same as the journal currency, it will be defined as the journal currency amount. Otherwise, if the **Override FX rate** option is not selected, the entity currency will be defined automatically based on the account's conversion type. For the rest, the considerations made for the **Journal currency** amount will be valid.
Transaction currency	Only present if the transaction currency is managed on consolidation journals in the process's journal rules. If not entered, it will be defined as the journal currency.
Transaction currency amount	Only present if the transaction currency is managed on consolidation journals in the process's journal rules. If the transaction currency is not entered, or is the same as the journal currency, it will be defined as the journal currency amount. Otherwise, if the **Override FX rate** option is not selected, the entity currency will be defined automatically based on the account's conversion type. For the rest, the considerations made for the **Journal currency** amount will be valid.
Notes	Any explanatory notes
Additional notes	Any additional notes
Financial investments event	Number of the financial investment event existing between the various pairs of entities in the group. Defined automatically by the financial investment elimination data processing. Information used in conversion step: if this field is defined, CCH Tagetik applies the FX rates of the structure linked to the event.

Actions from journal headers

User

Processes tile > select process > Contributor > Detail summary tab or Step tab > (Actions) Edit windows > Edit Entity Journals >

Processes tile > select process > Consolidator > Overview tab or Step tab > (Actions) Edit windows > Edit Entity Journals >

Processes tile > select process > Consolidator > Overview tab or Step tab > (Actions) Edit windows > Edit Consolidation journals >

Navigation panel > Processes > select process > Contributor > Detail summary tab or Step tab > (Actions) Edit windows > Edit Entity Journals >

Navigation panel > Processes > select process > Consolidator > Overview tab or Step tab > (Actions) Edit windows > Edit Entity Journals >

Navigation panel > Processes > select process > Consolidator > Overview tab or Step tab > (Actions) Edit windows > Edit Consolidation journals >

Actions on this page

Depending on the selected header, some of the following actions are available.

Action	Description
Rows	Only for individual headers. Opens a window to record the entries of the selected journal: Rows (Entity Journals) page and Rows (Consolidation journals) page.
Documents	Only for individual headers. Opens a page to manage the documents attached to the journal (Documents page).
Consolidation scenarios	Only for individual headers and on journals with the **Filter consolidation scenarios** option active. Opens a page to define the consolidation scenarios to be used to process the journal (Consolidation Scenario page).
Periodic management	Only for individual headers, on single submission processes and on journals which have the **Periodic journal** option active and do not have “Draft” status. Opens a window to manage the journal rows in periodic mode (Periodic Management page).
Override > Overridden FX rates	Only for individual headers, on journals that do not have “Draft” status and on processes that DO NOT manage In memory consolidation, see Settings windowSettings window in the General configuration section. Opens a page to set the overridden FX rates to be used when consolidating the journal (Overridden FX rates page).
Override > Overridden rows - Proportional	Only for individual headers and on journals that do not have “Draft” status. Opens a page to define the rows overridden on the proportional amount type by consolidation scenario (Override on the consolidation scenario - Proportional page). The rows are used when consolidating the journal.

Action	Description
Override > Overridden rows - Converted and Consolidable	Only for individual headers and on journals that do not have “Draft” status. Opens a page to define the rows overridden on the converted and consolidable amount type by consolidation scenario (Override on the consolidation scenario - Proportional page). The rows are used when consolidating the journal.
Override > Overridden rows - Carry forward on Original scenarios	Only for individual headers and on journals that do not have “Draft” status. Opens a page to define the rows overridden for the original scenario and to be used when carrying forward the journal onto a new scenario/period (Override journals on the original scenario - Carry forward page).
Diagnostic > Diagnose selected journals	Balance sheet (civil code) Runs the diagnostic data processing on the selected journals. See Diagnostic data processing Diagnostic data processing in the Diagnostic section.
Diagnostic > Diagnose and update log for selected journals	Only if diagnostic is enabled on the process, if the scenario/period is not locked and management of the diagnostic log has been activated on the process. Runs the diagnostic data processing on the selected journals and updates the log of diagnostic reports. See Diagnostic data processing Diagnostic data processing in the Diagnostic section.
Submission and posting > Submit the selected journals	Only if rows belonging to the same scenarios/period are selected, if the scenario/period is not locked and if the journal submission has been activated for at least one of the entities to which the selected journals belong. Opens a window to select the step for which to submit the selected journals. See Submission data processing Submission data processing in the Data Processing section.
Submission and posting > Submit the selected journals via workflow	Only for individual headers, if the scenario/period is not locked and if journal submission has been activated for the entity to which the journal belongs. Opens a page to view the journal submission steps. Selecting the desired step will display the workflow for performing the journal submission (Workflow submission page). See Submission data processing Submission data processing in the Data Processing section.
Submission and posting > Reject the selected journals	Only if rows belonging to the same scenarios/period are selected, if the scenario/period is not locked and if the journal submission has been activated for at least one of the entities to which the selected journals belong. Opens a window to select the step for which to reject the selected journals. See Submission data processing Submission data processing in the Data Processing section.
Submission and posting > Show journal log	Only per header and if the journal submission has been activated for the entity to which the selected journal belongs or the journal category is one of those for which the status 'Draft Journal' is managed. Opens the submission and publication activity log page for the selected journal (Journal Log).
Submission and posting > Post the selected draft Journal/s	Only if rows belonging to the same scenarios/period are selected, if the scenario/period is not locked and if at least one of the selected journals has “Draft” status. The selected draft journals will be published and thus become visible to the data processing and reports. See Draft journals.

Action	Description
Submission and posting > Unpost the selected journals	Only if rows belonging to the same scenarios/periods are selected, if the scenario/period is not locked, if at least one of the selected journals is on category for draft journals but is not in 'draft' status. The posting of selected journals is cancelled, so they will no longer affect processing results or data reporting. See Draft journals.
Submission and posting > Submit and post the selected journals	Only if rows belonging to the same scenarios/periods are selected, if the scenario/period is not locked, if the journal submission has been enabled for at least one of the Entities to which the selected journals belong and it is in 'Draft' status. Opens the window to select the step for which to submit the selected journals, and posts the journals once submission is complete. See Submission data processing Submission data processing in the Data processing section and Draft Journals
Submission and posting > Reject and unpost the selected journals	Only if rows belonging to the same scenarios/periods are selected, if the scenario/period is not locked, and if the journal submission has been enabled for at least one of the entities to which the selected journals belong, it is on category for draft journals but is not in 'Draft' status. Opens the window to select the step for which to reject the selected journals and, when submission is complete, cancels the posting of the journals. See Submission data processing Submission data processing in the Data processing section and Draft Journals
Copy	Only for individual headers. Opens a window to copy journals (Copy window).
Edit category	Opens a window to edit, if possible, the category of the selected journals (Edit category window).
Delete journals	Deletes the selected journals, if they are not locked. Before deleting the journals, the due controls are carried out, e.g. whether the journal has been locked or submitted.
Open Journal headers in the following periods	Only if rows belonging to the same scenarios/periods are selected and if the scenario/period is not locked. Allows you to copy the headers of the selected journals onto subsequent periods.

Action	Description
Generate balance sheet amount	Only for entity journals and if at least one of the selected journals does not have “Draft” status. Generates balance sheet contra-entries for the profit & loss rows of the selected journals. This can only take place if the accrual account has been defined for the profit & loss accounts. See Accounts ListAccounts List in the Data Model section.
Consolidate journal	Only for consolidation journals and if rows belonging to the same scenarios/period are selected, if the scenario/period is not locked and if at least one journal does not have “Draft” status. Opens a window to select consolidation scenarios. This function allows you to consolidate one or several journals without having to run the entire consolidation data processing. This is useful, for example, in cases where it is necessary to consolidate on “non-processable” scenarios, i.e. scenarios which include data on the proportional, converted and consolidable amount types that cannot be regenerated. By consolidating the journals directly, you can edit the consolidable amount type without changing the data that is already present. You can select one or several consolidation scenarios from among those that are associated with the original scenario of the journals that are editable by the user. Consolidation only takes place if the following conditions are fulfilled for every selected journal: • The proportional calculation method is “none”. • The minorities calculation method is “none”. • The equity evaluation method is “none”. • The journal has not been converted. If one or more conditions are not fulfilled, an error message showing the relative details will be shown.

Documents page

User

Processes tile > select process > Contributor > Detail summary tab or Step tab > (Actions) Edit windows > Edit Entity Journals > select row > ⋮ > Documents

Processes tile > select process > Consolidator > Overview tab or Step tab > (Actions) Edit windows > Edit Entity Journals > select row > ⋮ > Documents

Processes tile > select process > Consolidator > Overview tab or Step tab > (Actions) Edit windows > Edit Consolidation journals > select row > ⋮ > Documents

Navigation panel > Processes > select process > Contributor > Detail summary tab or Step tab > (Actions) Edit windows > Edit Entity Journals > select row > ⋮ > Documents

Navigation panel > Processes > select process > Consolidator > Overview tab or Step tab > (Actions) Edit windows > Edit Entity Journals > select row > ⋮ > Documents

Navigation panel > Processes > select process > Consolidator > Overview tab or Step tab > (Actions) Edit windows > Edit Consolidation journals > select row > ⋮ > Documents

Purpose of the page

This page shows the attachments to the header of a journal and allows you to add or remove them.

You can store document of any type (PDF, Word, Excel, etc.) or size, but the administrator can also set restrictions on the permitted file extensions, see Settings window in the General configuration section.

Actions on this page

Action	Description
⋮	• **Upload attachment**: allows you to insert an attachment or replace the current document with another one, while keeping the description or notes field unchanged. • **Download attachment**: downloads the document locally. • **Remove attachment**: removes the attached document.

Consolidation scenario page

User

Processes tile > select process > Contributor > Detail summary tab or Step tab > (Actions) Edit windows > Edit Entity Journals > select row > ⋮ > Consolidation scenario

Processes tile > select process > Consolidator > Overview tab or Step tab > (Actions) Edit windows > Edit Entity Journals > select row > ⋮ > Consolidation scenario

Processes tile > select process > Consolidator > Overview tab or Step tab > (Actions) Edit windows > Edit Consolidation journals > select row > ⋮ > Consolidation scenario

Navigation panel > Processes > select process > Contributor > Detail summary tab or Step tab > (Actions) Edit windows > Edit Entity Journals > select row > ⋮ > Consolidation scenario

Navigation panel > Processes > select process > Consolidator > Overview tab or Step tab > (Actions) Edit windows > Edit Entity Journals > select row > ⋮ > Consolidation scenario

Navigation panel > Processes > select process > Consolidator > Overview tab or Step tab > (Actions) Edit windows > Edit Consolidation journals > select row > ⋮ > Consolidation scenario

Purpose of the page

This page is only available for journals with the **Filter consolidation scenarios** option active and allows you to define the consolidation scenarios in which to process the journal.

Page fields

Action	Description
Consolidation scenario	Allows you to select a consolidation scenario, which must meet the following requirements: • Linked to the original scenario of the journal header. • The existing periods must also include the same period as the journal header period. • Editable for the user. • Not have a category filter or in any case include the journal header category. • Include, in its own consolidation area, the journal header entity or both header entities in the case of consolidation journals.
Exclude next scenario	The journal will not be processed as a restoration in the scenario following the selected scenario.

Periodic Management page

User

Processes tile > select process > Contributor > Detail summary tab or Step tab > (Actions) Edit windows > Edit Entity Journals > select row > ⋮ > Periodic Management

Processes tile > select process > Consolidator > Overview tab or Step tab Consolidation journals > (Actions) Edit windows > Edit Entity Journals > select row > ⋮ > Periodic Management

Processes tile > select process > Consolidator > Overview tab or Step tab Consolidation journals > (Actions) Edit windows > Edit Consolidation journals > select row > ⋮ > Periodic Management

Navigation panel > Processes > select process > Contributor > Detail summary tab or Step tab > (Actions) Edit windows > Edit Entity Journals > select row > ⋮ > Periodic Management

Navigation panel > Processes > select process > Consolidator > Overview tab or Step tab Consolidation journals > (Actions) Edit windows > Edit Entity Journals > select row > ⋮ > Periodic Management

Navigation panel > Processes > select process > Consolidator > Overview tab or Step tab Consolidation journals > (Actions) Edit windows > Edit Consolidation journals > select row > ⋮ > Periodic Management

Purpose of the page

This page is only available for individual headers, on single submission processes and on journals which have the **Periodic journal** option active and do not have "Draft" status. Allows you to enter the journal data for all periods until the end of the process.

Actions on this page

Action	Description
	Show Amount in other currencies: allows you to set a currency other than the journal currency in which to show the amounts.

Page fields

Action	Description
Scenario	Journal header scenario. Editable with another scenario of the process.
Period	Journal header period. Editable with another period of the selected scenario.
Entity	Only for consolidation journals. Entity, out of the two present in the header, to which to allocate the value.
Account	Amount, from those related to the process, on which to write.
Journal currency amount	Only for consolidation journals. Journal currency amount.
Entity currency amount	Only for entity journals, or for consolidation journals if the **Show Amount in other currencies** option has been selected.
CTP entity	Counterparty entity from the two entities involved in the journal.
Entity currency	Only for consolidation journals if the **Show Amount in other currencies** option has been selected.
Transaction currency	Only for entity journals. Transaction currency.
Transaction currency amount	Only for entity journals. Transaction currency amount
Override FX rate	Only visible if the **Show Amount in other currencies** option has been selected.
Notes	Any explanatory notes
Segment CTP Entity	If data management by segment is active, this reports the transaction's segment counterparty. For more details on the segment property in Table of row/column filter properties in the Reporting section.

Action	Description
Additional notes	Any additional notes
Ownership structure register event	Number of the financial investment event existing between the various pairs of entities in the group.

Overridden FX rates page

User

Processes tile > select process > Contributor > Detail summary tab or Step tab > (Actions) Edit windows > Edit Entity Journals > select row > ⋮ > Override > Overridden FX rates

Processes tile > select process > Consolidator > Overview tab or Step tab Consolidation journals > (Actions) Edit windows > Edit Entity Journals > select row > ⋮ > Override > Overridden FX rates

Processes tile > select process > Consolidator > Overview tab or Step tab Consolidation journals > (Actions) Edit windows > Edit Consolidation journals > select row > ⋮ > Override > Overridden FX rates

Navigation panel > Processes > select process > Contributor > Detail summary tab or Step tab > (Actions) Edit windows > Edit Entity Journals > select row > ⋮ > Override > Overridden FX rates

Navigation panel > Processes > select process > Consolidator > Overview tab or Step tab Consolidation journals > (Actions) Edit windows > Edit Entity Journals > select row > ⋮ > Override > Overridden FX rates

Navigation panel > Processes > select process > Consolidator > Overview tab or Step tab Consolidation journals > (Actions) Edit windows > Edit Consolidation journals > select row > ⋮ > Override > Overridden FX rates

Purpose of the page

This page is only available for individual headers, if the consolidation engine type is “defined by the process” and for processes that do not manage “In memory” consolidation. It allows you to select the journal rows to be overridden with the indicated FX rate.

Page fields

Action	Description
Consolidation scenario	Consolidation scenario on which to override the FX rate.
Row to override	Opens a window to select the journal rows on which to override the FX rate.
FX rate	FX rate to be used for the selected rows.
Currency	Currency to use
Notes	Any explanatory notes

Submit from workflow page

User

Processes tile > select process > Contributor > Detail summary tab or Step tab > (Actions) Edit windows > Edit Entity Journals > select row > ⋮ > Submit > Submit the selected journal via workflow

Processes tile > select process > Consolidator > Overview tab or Step tab > (Actions) Edit windows > Edit Entity Journals > select row > ⋮ > Submit > Submit the selected journal via workflow

Processes tile > select process > Consolidator > Overview tab or Step tab > (Actions) Edit windows > Edit Consolidation journals > select row > ⋮ > Submit > Submit the selected journal via workflow

Navigation panel > Processes > select process > Contributor > Detail summary tab or Step tab > (Actions) Edit windows > Edit Entity Journals > select row > ⋮ > Submit > Submit the selected journal via workflow

Navigation panel > Processes > select process > Consolidator > Overview tab or Step tab > (Actions) Edit windows > Edit Entity Journals > select row > ⋮ > Submit > Submit the selected journal via workflow

Navigation panel > Processes > select process > Consolidator > Overview tab or Step tab > (Actions) Edit windows > Edit Consolidation journals > select row > ⋮ > Submit > Submit the selected journal via workflow

Purpose of the page

This page shows a tab for every journal submission step. You can select the desired step and view the related workflow to use to run the submission of the journal. See Journal submission in the Data Processing section.

For every entity involved in the journal, it shows a tab for the journal submission step and the relative task workflow to submit the journal.

Actions on this page

For every workflow task shown, right click to display the **Run** action to run the action.

Submission data processing runs the diagnostic and checks that there are no blocking errors.

Journal log

User

Processes Tile > select process > Contributor > Detail Summary tab or Step tab > (Actions) Edit Windows > Edit Entity journals > select row> ⋮ > Show Journal log

Processes Tile > select process > Consolidator > Overview tab or Step tab > (Actions) Edit Windows > Edit Entity Journals > select row> ⋮ > Show Journal log

Processes Tile > select process > Consolidator > Overview tab or Step tab > (Actions) Edit Windows > Edit Consolidation journals > select row> ⋮ > Show Journal log

Navigation Panel > Processes > select process > Contributor > Detail summary tab or Step tab > (Actions) Edit Windows > Edit Entity Journals > select row> ⋮ > show Journal log

Navigation Panel > Processes > select process > Consolidator > Overview tab or Step tab > (Actions) Edit Windows > Edit Entity Journals > select row> ⋮ > Show Journal Log

Navigation panel > Processes > select process > Consolidator > Overview tab or Step tab > (Actions) Edit windows > Edit Consolidation journals > select row> ⋮ > Show Journal log

Purpose of the page

This page shows the history of submission and publication activities for the selected journal.

If the entity to which the journal is related is associated with a task workflow formed of the submission task and one or several approval tasks, the following rows are tracked:

- one row with “Approval” and **Task Activities** equal to the submission task code, when the submission task is run: the journal changes status to “in submission”.
- one row with “Approval” and **Task Activities** equal to the approval task code, when one of the approved tasks is run: the journal keeps “in submission” status.
- a final row with “Submission” and **Task Activities** equal to the submission task code, when the last approval task is run: the journal changes status to “submitted”.

If the journal category is one of those for which the status 'Draft Journal' is managed, the following rows are drawn:

- a row with 'Draft' **Activity**, when the journal is in draft mode
- a row with 'Publication' **Activity**, when the journal is published
- a row with **Activity** 'Unposting', when the journal is cancelled

Data on the page

Element	Description
Date	Date on which the activity was run.
Activities	Activity run. This can be one of the following: • Approval • Submission • Rejection • In progress • Publication • Unposting

Element	Description
Task flowchart	Code of the task workflow specified for the entity to which the journal is related. Only defined if a task workflow different from the default task workflow has been specified for the entity to which the journal is related and if the type of activity being run is Approval or Submission.
Task	Code of the task performed. Only defined if a task workflow different from the default task workflow has been specified for the entity to which the journal is related and if the type of activity being run is Approval or Submission.
Task description	Description of the task performed. Only defined if a task workflow different from the default task workflow has been specified for the entity to which the journal is related and if the type of activity being run is Approval or Submission.
User	Code of the user who ran the activity.
User description	Description of the user who ran the activity.

Copy window

User

Processes tile > select process > Contributor > Detail summary tab or Step tab > (Actions) Edit windows > Edit Entity Journals > select row > ⋮ > Copy

Processes tile > select process > Consolidator > Overview tab or Step tab > (Actions) Edit windows > Edit Entity Journals > select row > ⋮ > Copy

Processes tile > select process > Consolidator > Overview tab or Step tab > (Actions) Edit windows > Edit Consolidation journals > select row > ⋮ > Copy

Navigation panel > Processes > select process > Contributor > Detail summary tab or Step tab > (Actions) Edit windows > Edit Entity Journals > select row > ⋮ > Copy

Navigation panel > Processes > select process > Consolidator > Overview tab or Step tab > (Actions) Edit windows > Edit Entity Journals > select row > ⋮ > Copy

Navigation panel > Processes > select process > Consolidator > Overview tab or Step tab > (Actions) Edit windows > Edit Consolidation journals > select row > ⋮ > Copy

Purpose of window

This window allows you to create a copy of a journal.

Fields in window

Element	Description
Amounts	The amounts in the journal rows are also copied. If amounts are not selected, the rows are copied, but the amounts are left as zero.
Documents	Any documents attached to the journal are also copied.
Amortisation/Depreciation	Any amortisation or depreciation plan is also copied.
Copy From	
Scenario	You can see the active original scenario from which to copy the data. This is the header scenario by default.
Period	Period of the selected scenario from which to copy the data. This is the header period by default.

<table>
<tr><th>Element</th><th>Description</th></tr>
<tr><td>Journal number</td><td>Journal belonging to the selected scenario and period from which the data are copied. The header journal number is proposed by default.
<table>
<tr><th>If the journal is...</th><th>And is opened from...</th><th>Then the system proposes...</th></tr>
<tr><td>by entity</td><td>Contributor cockpit</td><td>journals on categories with “contributor entity journals” type.</td></tr>
<tr><td>by entity</td><td>Consolidator cockpit</td><td>journals on categories with “contributor entity journals” or “consolidator entity journals” type.</td></tr>
<tr><td>consolidation</td><td>Consolidator cockpit</td><td>journals on categories whose type is “consolidation journals”.</td></tr>
</table></td></tr>
<tr><td>Origin</td><td>Origin of the journal rows that will be copied. You can select one or several origins from among those present in the rows of the selected journal.</td></tr>
<tr><td>Copy To</td><td></td></tr>
<tr><td>Scenario</td><td>Active original scenario, editable by the user and belonging to the process from which to copy the data. This is the header scenario by default, if the conditions are fulfilled.</td></tr>
<tr><td>Period</td><td>Non-locked period of the selected scenario onto which to copy the data. This is the header period by default, if the conditions are fulfilled.</td></tr>
<tr><td>Journal number</td><td>Journal number generated.

***IMPORTANT**: if the journal already exists, it will be overwritten.*</td></tr>
</table>

Edit category window

User

Processes tile > select process > Contributor > Detail summary tab or Step tab > (Actions) Edit windows > Edit Entity Journals > ⋮ Edit category

Processes tile > select process > Consolidator > Overview tab or Step tab > (Actions) Edit windows > Edit Entity Journals > ⋮ > Edit category

Processes tile > select process > Consolidator > Overview tab or Step tab > (Actions) Edit windows > Edit Consolidation journals > ⋮ > Edit category

Navigation panel > Processes > select process > Contributor > Detail summary tab or Step tab > (Actions) Edit windows > Edit Entity Journals > ⋮ > Edit category

Navigation panel > Processes > select process > Consolidator > Overview tab or Step tab > (Actions) Edit windows > Edit Entity Journals > ⋮ > Edit category

Navigation panel > Processes > select process > Consolidator > Overview tab or Step tab > (Actions) Edit windows > Edit Consolidation journals > ⋮ > Edit category

Purpose of window

This window allows you to edit the category of the journals if the following conditions are fulfilled:

- None of the selected headers is locked.
- All of the selected headers have their origin equal to INPUT_WEB or INPUT_DEFORM or COPY_SEGMENT or EF1 or MAP_%.
- None of the rows in the selected headers are related to any restore operations (PREL_RESTORE or PREL_RESTORE_RED or PRCO_RESTORE or PRCO_RESTORE_RED_1_DECO or PRCO_RESTORE_RED_2_

CONV or SUB_%).

- No row of the selected headers with their origin equal to INPUT_WEB or INPUT_DEFORM or QDL or BREAK_BACK or MAP_% is locked.

Fields in window

Element	Description
Category	Allows you to select a category from among those that are editable for the user and belong to the selected process. If the journal is... / And is opened from... / Then the system proposes... by entity / Contributor cockpit / categories whose type is "contributor entity journals". by entity / Consolidator cockpit / categories whose type is "contributor entity journals" or "consolidator entity journals". consolidation / Consolidator cockpit / categories whose type is "consolidation journals".
Apply the category modification to all the consolidation rows	The category edit is also applied to the consolidated rows. Otherwise the consolidated rows will be removed.

Actions from the journal rows

Processes tile > select process > Contributor > Detail summary tab or Step tab > (Actions) Edit windows > Edit Entity Journals > > Rows

Processes tile > select process > Consolidator > Overview tab or Step tab > (Actions) Edit windows > Edit Entity Journals > > Rows >

Processes tile > select process > Consolidator > Overview tab or Step tab > (Actions) Edit windows > Edit Consolidation journals > > Rows >

Navigation panel > Processes > select process > Contributor > Detail summary tab or Step tab > (Actions) Edit windows > Edit Entity Journals > > Rows

Navigation panel > Processes > select process > Consolidator > Overview tab or Step tab > (Actions) Edit windows > Edit Entity Journals > > Rows >

Navigation panel > Processes > select process > Consolidator > Overview tab or Step tab > (Actions) Edit windows > Edit Consolidation journals > > Rows >

Actions on this page

	Description
Original and consolidated rows	Opens a page that shows the original and consolidated rows (Original and consolidated rows page). Also checks the balancing on the various types of amount.
Control group balancing	Only available if diagnostic is enabled on the process. Opens a page where you can edit the control groups to which the accounts adjusted in the journal belong (Control Group Balancing page).

	Description
Financial investments congruence	Only available if diagnostic is enabled on the process. • **Diagnose**: runs the journal diagnostic. • **Diagnose and update log**: only available if the scenario/period is not locked and diagnostic log management is active on the process. Runs journal diagnostic and updates the diagnostic results log. See Diagnostic data processing Diagnostic data processing in the Data Processing module.
Submission and posting	Only available if journal submission is enabled for the entity to which the journal is linked, or the journal category is one of those for which the 'Draft' status is available. • **Submit**: opens a page to select the step for which to submit the journal. • **Submit via workflow**: opens a page with a tab for every journal submission step. The workflow to be used to submit the journal is shown for every step. • **Reject**: opens a page to select the step to be used to reject the journal. • **Post**: publishes the journal, making it visible to data processes and reports. • **Unpost**: cancels the publication of the journal, so it will no longer affect data processing results and data reporting. • **Switch journal to draft mode**: sets the journal status to 'draft'. Newly inserted rows will have no impact on the data processing result and data reporting. • **Submit and post** : opens the page where you can select the step for which to submit the journal and, once submission is complete, post the journal. • **Reject and unpost:** opens a page where you can select the step for which to submit the journal and, when submission is complete, cancels the posting of the journal. • **Show journal log**: opens a page showing the history of the submission and publication activities of the journal. See Journal Log Page. See Submission data processing Submission data processing in the Data processing and Draft Journals module
Depreciation proposal	Only available if the event scenario has been defined on the process and the journal is not a “draft” journal. Opens a page to define the journal’s depreciation plan. See Amortisation/Depreciation data processingAmortisation or depreciation data processing in the Data Processing module.

	Description
Generate rows from template	Only available if the window is in write mode and the journal does not have “draft” status. If the journal template has been defined for the journal category, it opens rows automatically. CCH Tagetik allows you to define a journal template for every category, i.e. a list of accounts that normally comprise the journal. See Categories listCategories list in the Data Model section.
Generate rows from another journal	Available only when the window is in edit mode. Opens a window to automatically open the rows of the journal from another journal. The following fields must be filled in: • **Scenario**: you can choose one active original scenario visible to the user. The header scenario is proposed by default. • **Period**: you can choose one period of the selected scenario. The header period is proposed by default. • **Journal number**: you can choose a source journal belonging to the selected scenario and period. For entity journals, if the window is opened from the Contributor cockpit, journals on categories whose type is “contributor entity journals” will be proposed, if the window is opened from the Consolidator cockpit, journals on categories whose type is contributor entity journals” or “consolidator entity journals” will be proposed. For consolidation journals, journals on categories whose type is “consolidation journals” will be proposed. The header journal number is proposed by default. • **Origin**: you can choose one or several origins from among those present in the rows of the selected journal.

Original and consolidated rows page

User

Processes tile > select process > Contributor > Detail summary tab or Step tab > (Actions) Edit windows > Edit Entity Journals > ⋮ > Rows > 🪄 > Original and consolidated rows

Processes tile > select process > Consolidator > Overview tab or Step tab > (Actions) Edit windows > Edit Entity Journals > ⋮ > Rows > 🪄 > Original and consolidated rows

Processes tile > select process > Consolidator > Overview tab or Step tab > (Actions) Edit windows > Edit Consolidation journals > ⋮ > Rows > 🪄 > Original and consolidated rows

Navigation panel > Processes > select process > Contributor > Detail summary tab or Step tab > (Actions) Edit windows > Edit Entity Journals > ⋮ > Rows > 🪄 > Original and consolidated rows

Navigation panel > Processes > select process > Consolidator > Overview tab or Step tab > (Actions) Edit windows > Edit Entity Journals > ⋮ > Rows > 🪄 > Original and consolidated rows

Navigation panel > Processes > select process > Consolidator > Overview tab or Step tab > (Actions) Edit windows > Edit Consolidation journals > ⋮ > Rows > 🪄 > Original and consolidated rows

Purpose of the page

This page allows you to view, directly from the journal, the consolidated data that result from the original amount entered (or from the carry forward) and the original amount.

For each amount type, it also shows the **Balancing** value, i.e. the sum of all the amounts of accounts with “Balance Sheet” nature and “Normal” type.

Consolidated rows are not editable; however, you can delete them or change some of their attributes using the override functions (Actions from journal headers).

Page tabs

Tab	Description
Original and consolidated rows	When the page is opened, the original rows are show. If a consolidation scenario is selected in **Consolidation scenario**, it will show the consolidated rows for that scenario.
Documents	Lists any documents attached to the journal. Allows you to download any attachments. For document management, see Documents page.

Actions in the Original and consolidated rows tab

Element	Description
Consolidation scenario	Allows you to select a consolidation scenario to view its consolidated rows.
Amount Type	Allows you to select the type of data to view. • **Original** • **Consolidable** • **Converted** • **Proportional**

Fields in the Original and consolidated rows tab

Field	Description
Amount Type	Allows you to reconstruct the steps that involved the original amount entered: • from original to proportional • from proportional to converted • from converted to consolidable
Scenario	Scenario set in the header. Not editable.
Period	Period set in the header. Not editable.
Journal number	Journal number in the header. Not editable.
Entity	Entity set in the header. Not editable.
Account	Account on which a value is entered. The chosen account must meet the following requirements: • Editable for the user. • Linked to the data model process associated with the entity to which the journal belongs. • Start date and end date, if set, must be between the start date and end date of the scenario/period to which the journal belongs. If the **CTP entity** field is defined, it must allow intercompany data management.
Category	Category set in the header. Not editable.

Field	Description
Custom dimension	For every custom dimension that is managed and enabled in the process's journal rules, you can select an element of the custom dimension which meets the following requirements: • Editable for the user. • Visible from the entity to which the journal row belongs. • Visible from the selected account. If no value is selected, the custom dimension will be shown as the entity's default custom dimension or the custom dimension with the lowest code from among those which meet the above requirements. ***IMPORTANT**: the custom dimension 2 is managed even if it is not enabled in the process's journal rules, but the process's relationship type is "entity - custom dimension 2" or "entity - synthetic custom dimension 2".*
CTP entity	Counterparty entity in the journal. An entity can be chosen, provided it meets the following requirements: • Belong to the selected process. • Must belong to the selected scenario/period. • Start date and end date, if present, must be between the start date and end date of the selected scenario/period. You can define a list of most frequently used counterparty entities, see Entities list in the Data Model section. To use only a subset of entities as counterparties, it may be useful to create a group of counterparties (Dynamic counterparty groups). You can also declare IC data in the context of the same entity (and therefore use the same code for both the entity and the counterparty). This is only possible if the **Allow intercompany declarations towards same Declaring entity** option is active (Amount & Intercompany rules page). *For example, this is useful for eliminating dividends received from group companies towards profits carried forward, or for eliminating self-invoicing results.*
CTP custom dimension 2 override type	Only present under the following conditions: • Custom dimension 2 is managed. • The process' relationship type is "entity - custom dimension 2" or "entity - synthetic custom dimension 2". • The **Spreading - Show CTP custom dimension 2 override type** option is active in the process's gross and IC amount rules. • The user's role contains function 0002274. It can be set as follows: • To allocate • None • Override

Field	Description
Counterparty custom dimension 2	Only present under the following conditions: • Custom dimension 2 is managed. • The process' relationship type is "entity - custom dimension 2" or "entity - synthetic custom dimension 2". It is only mandatory under the following conditions: • A CTP entity has been specified. The field is only editable if the **Spreading - Display CTP custom dimension 2 override type** option is active in the process's gross and IC amount rules, or if that option is active and: • The user's role contains function 0002274. • **CTP custom dimension 2 override type** is not "To allocate" If the field is editable, it is defined as the CTP entity's default custom dimension 2 or, if the **Spreading - Show CTP custom dimension 2 override type** and **Show CTP custom dimension 2 with entity's default element** options are not active in the process's gross and IC amount rules, the field is defined as the default custom dimension 2 element specified in the custom dimension 2 settings.
Consolidation currency	Currency of the consolidated rows, generated by the consolidation process. Only defined on the converted and consolidable rows.
Consolidation currency amount	Amount of the consolidated rows, generated by the consolidation process. Only defined on the converted and consolidable rows.
Conversion	Conversion type applied to generate the consolidated rows. Only defined on the converted and consolidable rows.
Company currency	Currency set in the header, not editable.
Entity currency amount	Amount expressed in the entity currency. Regardless of the number of decimals inserted, amounts are shown with a number of decimals that is consistent with those assigned to the currency in which they are expressed, with the exception of "Other stocks" and "Other variations" accounts where the **Manage maximum number of decimals** option is active (see Accounts list in the Data Model section). For these accounts, it is possible to insert up to 9 decimals. The amount may be shown in two different columns: **Entity currency amount - debit** and **Entity currency amount - credit**. This happens if the Amounts option is set to **Write amounts in Debit & Credit columns in absolute value** in the journal rules definition (Default Settings window).
Override FX rate	Only present if the transaction currency is managed on entity journals in the process's journal rules. If selected, you can edit all the amounts in the current row, thereby indirectly overriding the field applied to change from the entity currency amount to the transaction currency amount. Otherwise, only the transaction currency will be editable, but the transaction currency amount will not be. On saving, it automatically defines the amount in the transaction currency based on the account's conversion type.
Transaction currency	Only present if the transaction currency is managed on entity journals in the process's journal rules. If not entered, it will be defined as the entity currency.
Transaction currency amount	Only present if the transaction currency is managed on entity journals in the process's journal rules. If the transaction currency has not been entered or is the same as the entity currency, the field is defined as the entity currency amount. Otherwise, if the **Override FX rate** option is not selected, the entity currency will be defined automatically based on the account's conversion type. For the rest, the considerations made for the **Entity currency** amount will be valid.
Notes	Any explanatory notes
Additional notes	Any additional notes

Control group balancing

Purpose of the function

In the data collection process, financial statement amounts can be gathered using forms. These forms contain accounts for which you need to insert detailed information or for which you need to explain the adjustment compared to the previous year. Typically, a formula shows the balancing of adjusted amounts.

The control group balancing function allows you to run the same operation for entity and consolidation journals. In fact, for every control group it is possible, through a drill down, to view and potentially edit the adjusted accounts. The balancing totals are updated on every save and give information on the accuracy of the data.

This function uses the Diagnostic engine to identify the adjusted control groups in the journal and allows you to perform analyses and data entry. Using the control group structure allows you to view all the adjusted accounts in the journal.

Restrictions

This function has restrictions on the editing of data in specific cases.

- If the system does not manage the counterparty on individual data items.
- If, in the default settings of the general journal rules, the **Amounts** field is set to **Write amounts in Debit & Credit columns in absolute value** (Default Settings window).
- If the journals manage IC Spreading (IC spreading function in the Consolidation section).
- If, in the process's journal rules, the flags related to transaction currency management on journals are disabled (Journal rules and settings page in the Processes section).

Control Group Balancing page

User

Processes tile > select process > Contributor > Detail summary tab or Step tab > (Actions) Edit windows > Edit Entity Journals > ⋮ > Rows > 🪄 > Control group balancing

Processes tile > select process > Consolidator > Overview tab or Step tab > (Actions) Edit windows > Edit Entity Journals > ⋮ > Rows > 🪄 > Control group balancing

Processes tile > select process > Consolidator > Overview tab or Step tab > (Actions) Edit windows > Edit Consolidation journals > ⋮ > Rows > 🪄 > Control group balancing

Navigation panel > Processes > select process > Contributor > Detail summary tab or Step tab > (Actions) Edit windows > Edit Entity Journals > ⋮ > Rows > 🪄 > Control group balancing

Navigation panel > Processes > select process > Consolidator > Overview tab or Step tab > (Actions) Edit windows > Edit Entity Journals > ⋮ > Rows > 🪄 > Control group balancing

Navigation panel > Processes > select process > Consolidator > Overview tab or Step tab > (Actions) Edit windows > Edit Consolidation journals > ⋮ > Rows > 🪄 > Control group balancing

Purpose of the page

This page allows you to identify the control groups that have been adjusted in the journal and, through a drill-down, view and edit the adjusted accounts. When this page is opened, CCH Tagetik runs a dedicated diagnostic on the control groups to which the adjusted accounts in the journal belong. It therefore shows not only the unbalanced control groups, but also the balanced ones. This allows you to check the composition of the groups themselves and potentially make adjustments.

Actions on this page

	Description
	**Drill down**: shows the accounts that belong the selected control group (Drill down on control groups page).

Page fields

Action	Description
Balancing	Indicates whether or not the error row detected by the diagnostic is balanced. If it is not, the row will be reported (✖).
In progress	Indicates whether the error row detected by the diagnostic includes any rows marked “draft” (♟). Information only available if management of “Draft journals” is active (Categories for draft journals page).
Entity	For entity journals, it shows the entity for which the data was entered. For consolidation journals, it shows the node of entities. However, for consolidation journals, if the **Check consolidation journals by Entity** option has been activated on the control group, the balancing check will be performed by journal and entity. This field therefore shows the entity.
Control group	Code and description of the control group
Control group type	Control group type: • Variation • Balancing • Detail • Coherence
Data type	Only for entity journals. Type of data that was diagnosed: • Gross • Net • IC
Step	Step in which the control group is diagnosed
Custom dimension	Based on how the control group has been defined, it can show the following information: • an element of the custom dimension, for control groups with check custom dimension “by lowest level element” • a node of the custom dimension, for control groups with check custom dimension “by hierarchy nodes” If the control group provides for a “total” custom dimension check, the field is empty.
CTP entity	Only for entity journals, it contains the counterparty entity if the data type to be diagnosed is Intercompany.
CTP Custom dimension 2	Only for entity journals and if the process’s relationship type is “entity - custom dimension 2” or “entity - synthetic custom dimension 2”, it contains the counterparty custom dimension 2 if the data type to be diagnosed is Intercompany.
Currency	Journal currency, in which the amounts are expressed.
Parent accounts/Set1 amount	Sum of the amounts entered in the journal on the parent accounts of the control group. For control groups whose type is Balancing, this is the sum of the amounts entered on the accounts belonging to Set 1.
Parent accounts/Set2 amount	Sum of the amounts entered in the journal on the child accounts of the control group. For control groups whose type is Balancing, this is the sum of the amounts entered on the accounts belonging to Set 2.
Difference	Difference between Child accounts/Set2 amount and Parent accounts/Set1 amount

Action	Description
Operator	For the Variation, Detail and Balancing types, this can be one of the following: =, <, >, >=, <= or <>. Coherence may be as follows: • Bi-directional coherence • Bi-directional coherence by element • Coherence • Coherence by element
Severity	Severity of the error for submission purposes

Drill down on control groups page

User

Processes tile > select process > Contributor > Detail summary tab or Step tab > (Actions) Edit windows > Edit Entity Journals > ⋮ > Rows > 🪄 > Control group balancing > select control group > ⋮ > Drill down

Processes tile > select process > Consolidator > Overview tab or Step tab > (Actions) Edit windows > Edit Entity Journals > ⋮ > Rows > 🪄 > Control group balancing > select control group > ⋮ > Drill down

Processes tile > select process > Consolidator > Overview tab or Step tab > (Actions) Edit windows > Edit Consolidation journals > ⋮ > Rows > 🪄 > Control group balancing > select control group > ⋮ > Drill down

Navigation panel > Processes > select process > Contributor > Detail summary tab or Step tab > (Actions) Edit windows > Edit Entity Journals > ⋮ > Rows > 🪄 > Control group balancing > select control group > ⋮ > Drill down

Navigation panel > Processes > select process > Consolidator > Overview tab or Step tab > (Actions) Edit windows > Edit Entity Journals > ⋮ > Rows > 🪄 > Control group balancing > select control group > ⋮ > Drill down

Navigation panel > Processes > Consolidator > Overview tab or Step tab > (Actions) Edit windows > Edit Consolidation journals > ⋮ > Rows > 🪄 > Control group balancing > select control group > ⋮ > Drill down

Purpose of the page

This page shows the details of the selected control group. In particular, it shows the entries of the accounts of which it is composed. You can add/edit/delete accounts based on the generic editability rules and specific rules originated by restrictions linked to the selected control group.

The page also shows a **Balancing** total which indicates the unbalanced amount of the control group as a whole.

***IMPORTANT**: when a control group's drill down window is closed to return to the diagnostic window with the list of control groups, if changes have been made, the diagnostic is repeated to calculate any repercussions on other control groups.*

The fields shown vary depending on whether the journals are consolidation journals or entity journals.

Page fields - Entity Journals

Field	Description
Account	**Parent accounts/Set1**: shows the parent accounts belonging to the control group. **Child accounts/Set2**: shows the child accounts belonging to the control group.
Entity currency amount	Amount expressed in the entity currency

<table>
<tr><th>Field</th><th>Description</th></tr>
<tr><td>Custom dimension</td><td>
<table>
<tr><th>If the control group has this type of check on the custom dimension...</th><th>Then it will show...</th></tr>
<tr><td>by lowest level element</td><td>the custom dimension element shown in the diagnostic results window (non-editable)</td></tr>
<tr><td>by hierarchy node</td><td>only the custom dimension elements present in the hierarchy node specified in the control group list</td></tr>
<tr><td>total</td><td>all elements of the custom dimension</td></tr>
</table>

Only the custom dimension elements that meet the following requirements will be shown:
• Be allowed for the entity to which the journal belongs, if the entity is restricted on the custom dimension.
• be allowed for the selected account, if the account is restricted on the custom dimension.
• Be allowed for the control group, if the control group is restricted on the custom dimension.
• Be valid for the control group, if the control group is defined by “account/custom dimension”.
• Be editable for the user.
If not specified, on saving, the field is filled in with the entity’s default custom dimension, if this meets the above requirements. Otherwise it will be filled in with the custom dimension with the lesser code that meets the requirements.
</td></tr>
<tr><td>CTP entity</td><td>Depends on the type of data present in the diagnostic results window.
<table>
<tr><th>If the data is...</th><th>Then...</th></tr>
<tr><td>Gross</td><td>all the entities in the process will be shown.</td></tr>
<tr><td>Net</td><td>the field will remain empty.</td></tr>
<tr><td>IC</td><td>shows the CTP entity present in the diagnostic results window (not editable).</td></tr>
</table>
</td></tr>
<tr><td>CTP Custom dimension 2</td><td>Only if the process’s relationship type is “entity - custom dimension 2” or “entity - synthetic custom dimension 2”. Depends on the type of data present in the diagnostic results window.
<table>
<tr><th>If the data is...</th><th>Then...</th></tr>
<tr><td>Gross</td><td>all the custom dimension 2s will be shown.</td></tr>
<tr><td>Net</td><td>the field will remain empty.</td></tr>
<tr><td>IC</td><td>shows the CTP custom dimension 2 present in the diagnostic results window (not editable).</td></tr>
</table>

Mandatory if a CTP Entity has been specified.
</td></tr>
<tr><td>Transaction currency</td><td>If not entered, it will be defined as the entity currency.</td></tr>
<tr><td>Transaction currency amount</td><td>If the Transaction currency field has not been filled in or is the same as the entity currency, this is defined as the entity currency amount.
Otherwise, if Override FX rate is not selected, it is defined automatically based on the account’s conversion type.</td></tr>
<tr><td>Override FX rate</td><td>If selected, this allows you to edit all the amounts of the current row, thereby indirectly overriding the applied FX rate to change from the entity currency amount to the transaction currency amount.
If not selected, only the transaction currency will be editable, but the transaction currency amount will not be, and when the row is saved it will show the transaction currency amount based on the account’s conversion type.</td></tr>
<tr><td>Notes</td><td>Any explanatory notes</td></tr>
<tr><td>Additional notes</td><td>Any additional notes</td></tr>
</table>

Page fields - Consolidation journals

<table>
<tr><th>Field</th><th>Description</th></tr>
<tr><td>Entity</td><td>If the control group is to be diagnosed by individual entity on the consolidation journals, it shows the entity present in the diagnostic results window and is not editable. Otherwise, the system behaves as follows:

<table><tr><th>If the journal...</th><th>Then it will show...</th></tr><tr><td>is not many to many relationship</td><td>the two entities in the header.</td></tr><tr><td>is many to many relationship</td><td>the entities of the process which belong to the scenario/period and are editable for the user.</td></tr></table></td></tr>
<tr><td>Account</td><td>Parent accounts/Set1: shows the parent accounts belonging to the control group.
Child accounts/Set2: shows the child accounts belonging to the control group.</td></tr>
<tr><td>Journal currency amount</td><td>Amount expressed in the journal currency</td></tr>
<tr><td>Custom dimension</td><td><table><tr><th>If the control group has this type of check on the custom dimension...</th><th>Then it will show...</th></tr><tr><td>by lowest level element</td><td>the custom dimension element shown in the diagnostic results window (non-editable)</td></tr><tr><td>by hierarchy node</td><td>only the custom dimension elements present in the hierarchy node specified in the control group list</td></tr><tr><td>total</td><td>all elements of the custom dimension</td></tr></table>
Only the custom dimension elements that meet the following requirements will be shown:
Be allowed for the entity to which the journal belongs, if the entity is restricted on the custom dimension.
be allowed for the selected account, if the account is restricted on the custom dimension.
Be allowed for the control group, if the control group is restricted on the custom dimension.
Be valid for the control group, if the control group is defined by “account/custom dimension”.
Be editable for the user.
If not specified, on saving, the field is filled in with the entity’s default custom dimension, if this meets the above requirements. Otherwise it will be filled in with the custom dimension with the lesser code that meets the requirements.

For the custom dimension 2, if the journal is many-to-many relationship and the process’s relationship type is “entity - custom dimension 2”, the custom dimension 2s in the header will be proposed.</td></tr>
<tr><td>CTP entity</td><td>Depends on the type of data present in the diagnostic results window.

<table><tr><th>If the data is...</th><th>Then...</th></tr><tr><td>Gross</td><td>if the process manages the CTP entity and CTP custom dimension 2 independently from the header relationship or the journal is many to many relationship, it will show all the entities of the process which belong to the scenario/period. Otherwise, it will show the header entities.</td></tr><tr><td>Net</td><td>the field will remain empty.</td></tr><tr><td>IC</td><td>shows the CTP entity present in the diagnostic results window (not editable).</td></tr></table></td></tr>
</table>

<table>
<tr><th>Field</th><th>Description</th></tr>
<tr><td>CTP Custom dimension 2</td><td>Only if the process's relationship type is "entity - custom dimension 2" or "entity - synthetic custom dimension 2". Depends on the type of data present in the diagnostic results window.

<table><tr><th>If the data is...</th><th>Then...</th></tr><tr><td>Gross</td><td>if the process manages the CTP entity and CTP custom dimension 2 independently from the header relationship or the journal is many to many relationship, it will show all the custom dimension 2s. Otherwise, it will show the header entities.</td></tr><tr><td>Net</td><td>the field will remain empty.</td></tr><tr><td>IC</td><td>shows the CTP custom dimension 2 present in the diagnostic results window (not editable).</td></tr></table>
Mandatory if a CTP Entity has been specified.</td></tr>
<tr><td>Entity currency</td><td>If not entered, it will be defined as the journal currency.</td></tr>
<tr><td>Entity currency amount</td><td>If the Entity currency field has not been filled in or is the same as the journal currency, it will be defined as the journal currency amount.

Otherwise, if Override FX rate is not selected, it is defined automatically based on the account's conversion type.</td></tr>
<tr><td>Transaction currency</td><td>If not entered, it will be defined as the journal currency.</td></tr>
<tr><td>Transaction currency amount</td><td>If the Transaction currency field has not been filled in or is the same as the journal currency, it will be defined as the journal currency amount.

Otherwise, if Override FX rate is not selected, it is defined automatically based on the account's conversion type.</td></tr>
<tr><td>Override FX rate</td><td>If selected, this allows you to edit all the amounts of the current row, thereby indirectly overriding the FX rates so they are no longer the FX rate that would be automatically applied to the account.

If not selected, only the transaction currency and the entity currency will be editable, but the transaction currency amount and the entity currency amount will not be. When the row is saved, it shows the transaction currency amount and the entity currency amount, based on the account's conversion type.</td></tr>
<tr><td>Notes</td><td>Any explanatory notes</td></tr>
<tr><td>Segment CTP Entity</td><td><table><tr><th>If the journal...</th><th>Then...</th></tr><tr><td>is not many to many relationship</td><td>it will be defined automatically as the header entity that has not been selected in the Entity field and is not editable.</td></tr><tr><td>is many to many relationship</td><td>it will show the entities of the process which belong to the scenario/period and are editable for the user.</td></tr></table></td></tr>
<tr><td>Segment CTP custom dimension 2</td><td>Only if the process's relationship type is "entity - custom dimension 2" or "entity - synthetic custom dimension 2".

<table><tr><th>If the journal...</th><th>Then...</th></tr><tr><td>is not many to many relationship and the process's relationship type is "entity - custom dimension 2"</td><td>it will be defined automatically as the header custom dimension 2 that has not been selected in the Custom dimension 2 field and is not editable.</td></tr><tr><td>is many to many relationship</td><td>it will show the custom dimension 2 elements.

If the segment CTP entity has been defined, it will only show the elements of the custom dimension 2 that can be managed by that entity.</td></tr></table></td></tr>
<tr><td>Additional notes</td><td>Any additional notes</td></tr>
<tr><td>Ownership structure register event</td><td>Number of the financial investment event existing between the various pairs of entities in the group.</td></tr>
</table>

Overrides on amounts and journals

Contents

This section covers the following topics:

Override journals and amounts 74
Override on the consolidation scenario - Proportional page 75
Override on the consolidation scenario - Converted and Consolidable page 76
Override journals on the original scenario - Carry forward page 78
Override amounts on the consolidation scenario - Proportional page 79
Override amounts on the consolidation scenario - Converted and consolidable page 79
Override gross amounts on the original scenario - Carry forward on Original scenarios page 80
Override IC amounts on the original scenario - Carry forward on Original scenarios page 80

Override journals and amounts

Introduction

Typically, data generated by the system are not editable. However, you may need to supplement the “final” data. For example, this may be the case when the data to be extracted from the reporting system are identical to data that were published previously, but have been reprocessed (e.g. due to a change of consolidation tool).

The data are gathered on the original scenario and processed on the consolidation scenario. To edit data present on the consolidation scenario, and generated data in particular, the override function must be used.

The override pages are accessible both as actions on the headers of entity journals and consolidation journals, and as override actions directly from the consolidator cockpit.

Override data processing (In Memory consolidation engine)

The data processing copies the override rows of the consolidation scenarios from the override tables to the consolidated data tables. The override rows are generated by the individual data processes that are overridden.

Rows with a "Final" override type are generated by the last data process of the amount type to which they relate.

If the data processing to which the override relates is not active on the process, the data processing will not be run, but the override rows will still be inserted. For example, this happens with the deconsolidation for the final override.

The origin generated for the overriding of a data process is treated like an origin generated by the data processing to which it relates. It is therefore managed as follows:

- It is read by the subsequent data processing.
- It is not read by previous data processing or the same data processing.
- For periodic data processing that reads data of the previous period generated by the same data processing (deconsolidation from previous period, conversion at period average FX rate and periodic minorities), the origin is considered in the reading of the previous period’s data.

Each type of override on the consolidation scenario generates its own origin per data type:

Data type	Override type	Origin
Proportional	Carry forward	PRCO_RESTORE
Proportional	Proportional calculation	CONS_FORCE_1_PROP

Data type	Override type	Origin
Proportional	Final	CONS_FORCE_1_FINAL
Converted	Carry forward	PRCO_RESTORE
Converted	Method	CONS_FORCE_2_CONV
Converted	Minorities	CONS_FORCE_2_MIN
Converted	Final	CONS_FORCE_2_FINAL
Consolidable	Carry forward	PRCO_RESTORE
Consolidable	Equity evaluation	CONS_FORCE_3_EQUITY
Consolidable	Final	CONS_FORCE_3_FINAL

This does not occur when the override is incorporated into the origin of the carry forward.

Override on the consolidation scenario - Proportional page

User

Processes tile > select process > Contributor > Detail summary tab or Step tab > (Actions) Edit windows > Edit Entity Journals > ⋮ > Override > Overridden rows - Proportional

Processes tile > select process > Consolidator > Overview tab or Step tab > (Actions) Edit windows > Edit Entity Journals > ⋮ > Override > Overridden rows - Proportional

Processes tile > select process > Consolidator > Overview tab or Step tab > (Actions) Edit Windows > Edit Consolidation journals > ⋮ > Override > Overridden rows - Proportional

Processes tile > select process > Consolidator > Overview tab or Step tab > (Actions) Override Journals > Consolidation scenario - Entity Journals - Proportional data

Processes tile > select process > Consolidator > Overview tab or Step tab > (Actions) Override Journals > Consolidation scenario - Consolidation Journals - Proportional data

Navigation panel > Processes > select process > Contributor > Detail summary tab or Step tab > (Actions) Edit Windows > Edit Entity Journals > ⋮ > Override > Overridden rows - Proportional

Navigation panel >Processes > select process > Consolidator > Overview tab or Step tab > (Actions) Edit Windows > Edit Entity Journals > ⋮ > Override > Overridden rows - Proportional

Navigation panel > Processes > select process > Consolidator > Overview tab or Step tab > (Actions) Edit windows > Edit Consolidation journals > ⋮ > Override > Overridden rows - Proportional

Navigation panel > Processes > select process > Consolidator > Overview tab or Step tab > (Actions) Override Journals > Consolidation scenario - Entity Journals - Proportional data

Navigation panel > Processes > select process > Consolidator > Overview tab or Step tab > (Actions) Override Journals > Consolidation scenario - Consolidation Journals - Proportional data

Page fields

The significant fields for running this override are listed below. You can specify various attributes depending on the path followed to access the page.

Fields	Description
Account	Indicates the account on which to run the override. The restrictions applied to the original scenario are not applied, so you can edit values on accounts that are locked on the original scenario.
Override type	Data processing to which the override relates. For the In Memory consolidation engine, it can be one of the following • Carry Forward • Proportional calculation • Final
Consolidation scenario	Scenario on which to perform the override. Only editable if run as an action from the consolidator cockpit.
Period	The period on which to perform the override. Only editable if run as an action from the consolidator cockpit.
Journal number	The journal on which to perform the override. Only editable if run as an action from the consolidator cockpit.

Override on the consolidation scenario - Converted and Consolidable page

User

Processes tile > select process > Contributor > Detail summary tab or Step tab > (Actions) Edit windows > Edit Entity Journals > ⋮ > Override > Overridden rows - Converted and Consolidable

Processes tile > select process > Consolidator > Overview tab or Step tab > (Actions) Edit windows > Edit Entity Journals > ⋮ > Override > Overridden rows - Converted and Consolidable

Processes tile > select process > Consolidator > Overview tab or Step tab > (Actions) Edit windows > Edit Consolidation journals > ⋮ > Override > Overridden rows - Converted and Consolidable

Processes tile > select process > Consolidator > Overview tab or Step tab > (Actions) Override Journals > Consolidation scenario - Entity Journals - Converted and Consolidable data

Processes tile > select process > Consolidator > Overview tab or Step tab > (Actions) Override Journals > Consolidation scenario - Consolidation Journals - Converted and Consolidable data

Navigation panel > Processes > select process > Contributor > Detail summary tab or Step tab > (Actions) Edit windows > Edit Entity Journals > ⋮ > Override > Overridden rows - Converted and Consolidable

Navigation panel >Processes > select process > Consolidator > Overview tab or Step tab > (Actions) Edit windows > Edit Entity Journals > ⋮ > Override > Overridden rows - Converted and Consolidable

Navigation panel > Processes > select process > Consolidator > Overview tab or Step tab > (Actions) Edit windows > Edit Consolidation journals > ⋮ > Override > Overridden rows - Converted and Consolidable

Navigation panel > Processes > select process > Consolidator > Overview tab or Step tab > (Actions) Override Journals > Consolidation scenario - Entity Journals - Converted and Consolidable data

Navigation panel > Processes > select process > Consolidator > Overview tab or Step tab > (Actions) Override Journals > Consolidation scenario - Consolidation Journals - Converted and Consolidable data

Page fields

The significant fields for running this override are listed below. You can specify various attributes depending on the path followed to access the page.

Fields	Description
Amount Type	• Consolidable • Converted
Account	Indicates the account on which to run the override. The restrictions applied to the original scenario are not applied, so you can edit values on accounts that are locked on the original scenario.
Override type	Data processing to which the override relates. For the In Memory consolidation engine, it can take on various values: For the converted amount type: • Carry Forward • Conversion • Minorities • Final (deconsolidation) For the consolidable amount type: • Carry Forward • Equity evaluation • Final (formulas)
Consolidation scenario	Scenario on which to perform the override. Only editable if run as an action from the consolidator cockpit.
Period	The period on which to perform the override. Only editable if run as an action from the consolidator cockpit.
Journal number	The journal on which to perform the override. Only editable if run as an action from the consolidator cockpit.

IMPORTANT: *for Entity journals, this override function may have restrictions for processes whose relationship type is not Entity.*

Override journals on the original scenario - Carry forward page

User

Processes tile > select process > Contributor > Detail summary tab or Step tab > (Actions) Edit Windows > Edit Entity Journals > ⋮ > Override > Overridden rows - Carry forward on Original scenarios

Processes tile > select process > Consolidator > Overview tab or Step tab > (Actions) Edit Windows > Edit Entity Journals > ⋮ > Override > Overridden rows - Carry forward on Original scenarios

Processes tile > select process > Consolidator > Overview tab or Step tab > (Actions) Edit Windows > Edit Consolidation journals > ⋮ > Override > Overridden rows - Carry forward on Original scenarios

Processes tile > select process > Consolidator > Overview tab or Step tab > (Actions) Override Amounts > Override on Original Scenario - Carry Forward on Gross Amounts

Processes tile > select process > Consolidator > Overview tab or Step tab > (Actions) Override Amounts > Override on Original Scenario - Carry Forward on IC Amounts

Navigation panel > Processes > select process > Contributor > Detail summary tab or Step tab > (Actions) Edit windows > Edit Entity Journals > ⋮ > Override > Overridden rows - Carry forward on Original scenarios

Navigation panel >Processes > select process > Consolidator > Overview tab or Step tab > (Actions) Edit windows > Edit Entity Journals > ⋮ > Override > Overridden rows - Carry forward on Original scenarios

Navigation panel > Processes > select process > Consolidator > Overview tab or Step tab > (Actions) Edit windows > Edit Consolidation journals > ⋮ > Override > Overridden rows - Carry forward on Original scenarios

Navigation panel > Processes > select process > Consolidator > Overview tab or Step tab > (Actions) Override Amounts > Override on Original Scenario - Carry Forward on Gross Amounts

Navigation panel > Processes > select process > Consolidator > Overview tab or Step tab > (Actions) Override Amounts > Override on Original Scenario - Carry Forward on IC Amounts

Page fields

The significant fields for running this override are listed below. You can specify various attributes depending on the path followed to access the page.

Fields	Description
Account	Indicates the account on which to run the override. The restrictions applied to the original scenario are not applied, so you can edit values on accounts that are locked on the original scenario.
Override type	It is always Carry forward type. When carry forward data processing is run, the override edits the generated rows. ***Note**: only carry forwards can be overridden on the original scenario, since the other rows can be inserted directly from the original row management window without the need to override them.*

Override amounts on the consolidation scenario - Proportional page

User

Processes tile > select process > Consolidator > Overview tab or Step tab > (Actions) Override Amounts > Override on Consolidation scenario - Proportional data - Amounts

Navigation panel > Processes > select process > Consolidator > Overview tab or Step tab > (Actions) Override Amounts > Override on Consolidation scenario - Proportional data - Amounts

Page fields

The significant fields for running this override are listed below.

Fields	Description
Account	Indicates the account on which to run the override. The restrictions applied to the original scenario are not applied, so you can edit values on accounts that are locked on the original scenario.
Override type	Data processing to which the override relates. For the In Memory consolidation engine, it can be one of the following • Carry Forward • Proportional calculation • Final

Override amounts on the consolidation scenario - Converted and consolidable page

User

Processes tile > select process > Consolidator > Overview tab or Step tab > (Actions) Override Amounts > Override on Consolidation scenario - Converted and Consolidable data - Amounts

Navigation panel > Processes > select process > Consolidator > Overview tab or Step tab > (Actions) Override Amounts > Override on Consolidation scenario - Converted and Consolidable data - Amounts

Page fields

The significant fields for running this override are listed below.

Fields	Description
Amount Type	• Consolidable • Converted
Account	Indicates the account on which to run the override. The restrictions applied to the original scenario are not applied, so you can edit values on accounts that are locked on the original scenario.
Override type	Data processing to which the override relates. For the In Memory consolidation engine, it can take on various values: For the converted amount type: • Carry Forward • Conversion • Final (deconsolidation) For the consolidable amount type: • Carry Forward • Equity evaluation • Final (formulas)

Override gross amounts on the original scenario - Carry forward on Original scenarios page

User

Processes tile > select process > Consolidator > Overview tab > (Actions) Override Amounts or Step tab > Override on Original Scenario - Carry Forward on Gross Amounts

Navigation panel > Processes > select process > Consolidator > Overview tab > (Actions) Override Amounts or Step tab > Override on Original Scenario - Carry Forward on Gross Amounts

Page fields

The significant fields for running this override are listed below.

Fields	Description
Account	Indicates the account on which to run the override. The restrictions applied to the original scenario are not applied, so you can edit values on accounts that are locked on the original scenario.
Override type	It is always Carry forward type. When carry forward data processing is run, the override edits the generated rows. ***Note**: only carry forwards can be overridden on the original scenario, since the other rows can be inserted directly from the original row management window without the need to override them.*

Override IC amounts on the original scenario - Carry forward on Original scenarios page

User

Processes tile > select process > Consolidator > Overview tab or Step tab > (Actions) Override Amounts > Override on Original Scenario - Carry Forward on IC Amounts

Navigation panel > Processes > select process > Consolidator > Overview tab or Step tab > (Actions) Override Amounts > Override on Original Scenario - Carry Forward on IC Amounts

Page fields

The significant fields for running this override are listed below.

Fields	Description
Account	Indicates the account on which to run the override. The restrictions applied to the original scenario are not applied, so you can edit values on accounts that are locked on the original scenario.
Override type	It is always Carry forward type. When carry forward data processing is run, the override edits the generated rows. ***Note**: only carry forwards can be overridden on the original scenario, since the other rows can be inserted directly from the original row management window without the need to override them.*

Reconciliation accounts and Notes

Contents

This section covers the following topics:

Reconciliation accounts 81
Reconciliation accounts page 81
Data entry notes 86
The Edit Notes page 87

Reconciliation accounts

Introduction

Once all the IC declarations have been inserted, it is possible that the intercompany declarations between two entities might not be balanced.
To justify these imbalances, entries called *reconciliation accounts* are used.

An entity has declared a foreign-currency sale of $125 to a counterparty (around €96 at the current FX rate). The counterparty, however, has declared a purchase of €100. The difference of € 4 can be justified by inserting a reconciliation account identified as "FX rate difference".

The reconciliation accounts can only be inserted on scenarios/periods that are not stored offline and are visible to the user.

Reconciliation account management

These accounts are inserted directly onto the process from the cockpit. If the process is not a single submission process, you must also specify the scenario/period.

Only reconciliation accounts inserted on contributor amounts and contributor entity journals can be managed from the contributor cockpit whereas from the consolidator cockpit, you can also manage reconciliation accounts inserted on consolidator amounts and consolidator entity journals.

Reconciliation accounts page

User

Processes tile > select process > Contributor > Detail summary tab or Step tab > (Actions) Other Edit windows > Edit Reconciliation accounts

Processes tile > select process > Consolidator > Overview tab or Step tab > (Actions) Other Edit windows > Edit Reconciliation accounts

Navigation panel > Processes > select process > Contributor > Detail summary tab or Step tab > (Actions) Other Edit windows > Edit Reconciliation accounts

Navigation panel > Processes > select process > Consolidator > Overview tab or Step tab > (Actions) Other Edit windows > Edit Reconciliation accounts

Purpose of the page

This page allows you to manage the reconciliation accounts of the selected entities. If nodes are selected, it shows the reconciliation accounts of all the entities belonging to those nodes, going down recursively to the

last level.

The page may show a subset of accounts according to the specific filters set in the page ( ).

Entries inserted manually have “INPUT_WEB” indicated as their **Origin**.

***Note**: you can configure CCH Tagetik so that entries with different origins are different colours. See **Colours by origin** option in the Settings window in the General Introduction section.*

Icons on this page

Element	Description
	Reconciliation accounts cannot be edited. The reason for the lock is reported.
	Reconciliation accounts on data that are no longer consistent. For example, the reconciliation account relates to an account or an entity that no longer belongs to the process. The reason for the inconsistency is reported and the reconciliation account can be deleted.

Page fields

The **Additional fields** tab is only shown if the **Enable additional fields on IC** option is not set to “No” in the process’s gross and IC amount rules.

***Note**: these fields contain information that is necessary for the automatic document relationship procedure, which relates an entity’s IC declarations to a counterparty’s declarations based on information related to the invoice.*

Element	Description
General	
Scenario	Scenario to which the reconciliation account belongs. You can choose an active original scenario, which you can edit and for which there exists at least one unblocked period belonging to the selected process.
Period	Period to which the reconciliation account belongs. You can choose a different period, provided that it is not locked and is linked to the selected scenario.
Entity	Entity to which the reconciliation account belongs. You can choose a different entity from the one proposed, provided that it meets the following requirements: • Editable for the user. • Belong to the selected process. • Belong to the selected scenario/period and, on that scenario/period, cannot be an “Only CTP” entity. • Start date and end date, if defined, must be between the start date and end date of the selected scenario/period.
IC matching logic	Matching logic in which the reconciliation account is inserted. The chosen logic must belong to the matching logic filters defined on the IC cockpits associated with the selected process. See Intercompany matching and elimination logics in the Consolidation section.

Element	Description
Category	Reconciliation account category. The chosen category must meet the following requirements: • Editable by the user. • Belong to the selected process. • Belong to the categories for reconciliation accounts defined on the IC cockpits associated with the selected process. • If the page is opened from the Contributor cockpit, the category type must be “contributor amount” or “contributor entity journal”. • If the page is opened from the Consolidation cockpit, the category type must be “contributor amount”, “consolidator amount”, “contributor entity journal” or “consolidator entity journal”.
Account	Account on which the necessary value is inserted to match the two declarations. The chosen account must meet the following requirements: • Enabled for IC management. • Editable for the user. • Linked to the data model process associated with the selected entity. • Start date and end date, if defined, must be between the start date and end date of the selected scenario/period. • Belong to the selected IC matching logic.
Custom dimension	For every managed custom dimension, if enabled in the process’s gross and IC amount rules, you can select an element of the custom dimension which meets the following requirements: • Editable for the user. • Visible from the selected entity. • Visible from the selected account. If no value is selected, CCH Tagetik will choose the custom dimension to be the entity’s default custom dimension or the custom dimension with the lowest code from among those which meet the above requirements. The custom dimension 2 is managed even if it is not enabled in the process’s gross and IC amount rules, but the process’s relationship type is “entity - custom dimension 2” or “entity - synthetic custom dimension 2”.
CTP entity	An entity can be chosen, provided it meets the following requirements: • Belong to the selected process. • Must belong to the selected scenario/period. • Start date and end date, if present, must be between the start date and end date of the selected scenario/period. You can define a list of most frequently used counterparty entities, see Entities list in the Data Model section. To use only a subset of entities as counterparties, it may be useful to create a group of counterparties (Dynamic counterparty groups). You can also declare IC data in the context of the same entity (and therefore use the same code for both the entity and the counterparty). This is only possible if the **Allow intercompany declarations towards same Declaring entity** option is active (Amount & Intercompany rules page). *For example, this is useful for eliminating dividends received from group companies towards profits carried forward, or for eliminating self-invoicing results.*

Element	Description
CTP custom dimension 2 override type	Only present under the following conditions: • Custom dimension 2 is managed. • The process' relationship type is "entity - custom dimension 2" or "entity - synthetic custom dimension 2". • The **Spreading - Show CTP custom dimension 2 override type** option is active in the process's gross and IC amount rules. • The user's role contains function 0002274. It can be set as follows: • To allocate • None • Override
CTP Custom dimension 2	Only present under the following conditions: • Custom dimension 2 is managed. • The process' relationship type is "entity - custom dimension 2" or "entity - synthetic custom dimension 2". It is only mandatory under the following conditions: • A CTP entity has been specified. The field is only editable if the **Spreading - Display CTP custom dimension 2 override type** option is active in the process's gross and IC amount rules, or if that option is active and: • The user's role contains function 0002274. • **CTP custom dimension 2 override type** is not "To allocate" If the field is editable, it is defined as the CTP entity's default custom dimension 2 or, if the **Spreading - Show CTP custom dimension 2 override type** and **Show CTP custom dimension 2 with entity's default element** options are not active in the process's gross and IC amount rules, the field is defined as the default custom dimension 2 element specified in the custom dimension 2 settings.

<table>
<tr><th>Element</th><th>Description</th></tr>
<tr><td>Row</td><td>Indicates the IC cockpit row on which the reconciliation account is shown and must be set according to the following criteria:
<table>
<tr><th>If, for the selected IC matching logic, ...</th><th>And the selected entity code is, in alphanumeric terms, ...</th><th>Then select</th></tr>
<tr><td>the reconciliation accounts must be inserted by the entity that has the primary accounts.</td><td>greater than the code of the selected CTP entity.</td><td>Primary Entity ></td></tr>
<tr><td>the reconciliation accounts must be inserted by the entity that has the primary accounts.</td><td>less than the code of the selected CTP entity.</td><td>Primary Entity <</td></tr>
<tr><td>the reconciliation accounts must be inserted by the entity that has the dependent accounts.</td><td>greater than the code of the selected CTP entity.</td><td>Primary Entity <</td></tr>
<tr><td>the reconciliation accounts must be inserted by the entity that has the dependent accounts.</td><td>less than the code of the selected CTP entity.</td><td>Primary Entity ></td></tr>
<tr><td>the reconciliation accounts can be inserted by both entities.</td><td>-</td><td>Primary Entity > or
Primary Entity <</td></tr>
<tr><td>the selected matching logic only manages single adjustment relationships.</td><td>-</td><td>Primary Entity <</td></tr>
</table></td></tr>
<tr><td>Company currency</td><td>Currency assigned to the entity in the process. Defined automatically and non-editable.</td></tr>
<tr><td>Entity currency amount</td><td>Amount expressed in the entity currency.
Field not editable because it is defined based on the transaction currency amount. If the transaction currency has not been entered or is the same as the entity currency, it is defined as the transaction currency amount. Otherwise, it is defined automatically based on the account’s conversion type.</td></tr>
<tr><td>Transaction currency</td><td>Transaction currency; if not entered, it is defined as the entity currency.</td></tr>
<tr><td>Transaction currency amount</td><td>Amount expressed in the transaction currency.
Regardless of the number of decimals inserted, amounts are shown with a number of decimals that is consistent with those assigned to the currency in which they are expressed, with the exception of “Other stocks” and “Other variations” accounts where the Manage maximum number of decimals option is active (see Accounts list in the Data Model section). For these accounts, it is possible to insert up to 9 decimals.</td></tr>
<tr><td>Notes</td><td>Any explanatory notes.
Mandatory if the Mandatory notes when inserting reconciliation accounts option is selected in the process’s gross and IC amount rules.</td></tr>
<tr><td>Additional fields</td><td></td></tr>
<tr><td>Relationship</td><td>Any information on the relationship between an entity’s IC declarations and the counterparty declarations.</td></tr>
<tr><td>Invoice number</td><td>Document identifier. Used by the automatic document relationship procedure if it has been requested to relate documents which have the same document number.</td></tr>
<tr><td>Invoice date</td><td>Document date. Used by the automatic document relationship procedure if it has been requested to relate documents which have the same document date.</td></tr>
<tr><td>Document Type</td><td>Document type:
Document
Bill
Accrual</td></tr>
<tr><td>Accounting date</td><td>Date on which the document was booked.</td></tr>
</table>

Element	Description
Sent/received	Indicates whether the document has been sent or received.
Invoice matching number	Identifier of the relationship created between an entity's IC declarations and a counterparty's declarations. It is generated by the automatic invoices relationship procedure. In some cases, it is not possible to automatically create relationships between IC declarations, for example, if an entity has entered the booking date instead of the invoice date. However, you can relate the IC declaration manually by setting the **Invoice matching number** field with the same number used in the counterparty entity's IC declaration. You can also edit an automatic relationship number that has been generated by the system. ***Note**: for the manual relationship, do not use a code that starts with $, as this symbol is used by the system to automatic relationships.*

You can also view certain additional information in the list of reconciliation accounts ( ):

Field	Description
Account nature	Nature of the account, which may be: Balance Sheet, Profit & Loss, Order, Other Variation, Other Stocks.
Account type	The account type may be: Normal, Variation, Detail.
Account attributes	Only if enabled in the Account list settings. Custom attributes that are useful in the reporting step to view information that cannot be managed using the attributes provided in the list.

Data entry notes

Introduction

Values inserted during data entry activities may require a short description. This may, for example, help the person responsible for approving the data to better understand the values that have been inserted. This type of explanation can be inserted in the form of a note. Notes can be either visible or hidden in the form, based on what is specified by the options related to comments in the general configuration settings; **Display data entry comments in reports navigation**" can be particularly useful for the person responsible for approving the data (see the Settings window in the General Introduction section).

Notes can only be managed on scenarios/periods that are not stored offline and are visible to the user.

Activities Log

When the **Save data in form incrementally** option is enabled in the process's gross and IC amount rules, in the data entry from form step a row is created every time the data is edited, whenever the user saves the form (see Amount & Intercompany rules page). The system behaves in the same way for notes: both the content of the notes and the activity carried out on them is logged.

The Edit Notes page

User

Processes tile > select process > Contributor > Detail summary tab or Step tab > (Actions) Other Edit windows > Edit Notes

Processes tile > select process > Consolidator > Overview tab or Step tab > (Actions) Other Edit windows > Edit Notes

Navigation panel > Processes > select process > Contributor > Detail summary tab or Step tab > (Actions) Other Edit windows > Edit Notes

Navigation panel > Processes > select process > Consolidator > Overview tab or Step tab > (Actions) Other Edit windows > Edit Notes

Purpose of the page

This page allows you to insert notes on values.

Only notes on contributor balances can be managed from the contributor cockpit, whereas from the consolidator cockpit it is also possible to manage notes inserted on consolidator amounts.

If entities are selected, the page shows the notes for the selected entities. If nodes are selected the page shows the notes for the entities belonging to those nodes, going down recursively to the last level.

The page may show a subset of notes, depending on the specific filters set in the page ( ).

Icons on this page

Element	Description
	Notes cannot be edited. The reason for the lock is reported.
	Notes on data are no longer consistent. For example, the note relates to an account, or an entity, that does not belong to the process. The reason for the inconsistency is reported. The notes can be deleted.

Page fields

Element	Description
Scenario	Scenario to which the note belongs. You can choose an active original scenario, which you can edit and for which there exists at least one unblocked period belonging to the selected process.
Period	Period to which the note belongs. You can choose a different period from the proposed period, provided that it is not locked and is linked to the selected scenario.
Entity	Entity to which the note relates. You can choose a different entity from the one proposed, provided that it meets the following requirements: • Editable for the user. • Belong to the selected process. • Belong to the selected scenario/period and, on that scenario/period, cannot be an “Only CTP” entity. • Start date and end date, if defined, must be between the start date and end date of the selected scenario/period.

Element	Description
Account	Account on whose balance the note is inserted. The chosen account must meet the following requirements: • Editable for the user. • Linked to the data model process associated with the selected entity. • Start date and end date, if defined, must be between the start date and end date of the selected scenario/period.
Custom dimension	For every managed custom dimension, if enabled in the process's gross and IC amount rules, you can select an element of the custom dimension which meets the following requirements: • Editable for the user. • Visible from the selected entity. • Visible from the selected account. If no value is selected, CCH Tagetik will choose the custom dimension to be the entity's default custom dimension or the custom dimension with the lowest code from among those which meet the above requirements. The custom dimension 2 is managed even if it is not enabled in the process's gross and IC amount rules, but the process's relationship type is "entity - custom dimension 2" or "entity - synthetic custom dimension 2".
Category	Note category. The chosen category must meet the following requirements: • Editable by the user. • Belong to the selected process. • If the page is opened from the Contributor cockpit, the category type must be "contributor amount". • If the page is opened from the Consolidator cockpit, the category type must be "consolidator amount" or "consolidator amount".
CTP entity	An entity can be chosen, provided it meets the following requirements: • Belong to the selected process. • Must belong to the selected scenario/period. • Start date and end date, if present, must be between the start date and end date of the selected scenario/period. You can define a list of most frequently used counterparty entities, see Entities list in the Data Model section. To use only a subset of entities as counterparties, it may be useful to create a group of counterparties (Dynamic counterparty groups). *For example, this is useful for eliminating dividends received from group companies towards profits carried forward, or for eliminating self-invoicing results.*
CTP Custom dimension 2	Only present under the following conditions: • Custom dimension 2 is managed. • The process' relationship type is "entity - custom dimension 2" or "entity - synthetic custom dimension 2". It is only mandatory if a CTP entity has been specified. If the field is not set manually, it is defined as the default custom dimension of the CTP entity or, if the **Define CTP custom dimension 2 as the entity's default element** option is not active in the process' gross and IC amount rules, it is defined as the custom dimension 2 specified in the custom dimension 2 settings.
Notes	Note contents

You can also view certain additional information in the list of notes ( ):

Field	Description
Account nature	Nature of the account, which may be: Balance Sheet, Profit & Loss, Order, Other Variation, Other Stocks.
Account type	The account type may be: Normal, Variation, Detail.
Account attributes	Only if enabled in the Account list settings. Custom attributes that are useful in the reporting step to view information that cannot be managed using the attributes provided in the list.

Introduction to Reporting

Contents

This section covers the following topics:

The reporting system

Introduction

CCH Tagetik has a reporting system based on specifically designed Excel sheets called *forms*. Using these forms, users can interact with the application databases to which they have access to insert, extract, consult and compare data.

These forms can be used both from the CCH Tagetik web interface and in Excel directly. Some jobs, like planning and designing a form, are carried out exclusively in Excel, while others, like running a form to navigate data, can be run both from Excel and from the CCH Tagetik Web interface. For more details on web forms, see I web form.

A dedicated add-in must be installed to use reporting functions in Excel (see Add-in Excel: caratteristiche tecniche).

Ways of working on forms

In CCH Tagetik, forms can be used:

- as reports (also called output forms), to consult data from the database
- as data entry forms, to enter data in the database

However, regardless of the purpose for which the form was designed, the run mode and actions that can be run in the form depend on the tool being used.

Element	Working mode	Actions on the form
Excel Add-in	Allows you to run: • all types of form in design mode • data entry forms in data entry mode • all types of form in navigation mode	• Creation and management of the structure of standard and transactional forms. • Data entry and form navigation.
Web interface	Allows you to run: • only data entry forms in data entry mode from the contributor cockpit • all types of form in navigation mode from the Forms tile.	• Creation and management of the structure of transactional forms. • Data entry and form navigation. • Inclusion of data entry forms as process tasks.

***Note**: however, the general settings on forms are run in the CCH Tagetik settings (see Settings window).*

Form types

Depending on how they are used, forms can ideally be divided into two fundamental types:

Type	Description
Report	These forms are used to extract and view data that is directly present in the database or calculated data. They are not editable and can be either shared or ad hoc (Form accessibility ("Form accessibility" below).
Data entry forms	These forms are used to enter data in application databases. The use of these forms depends on the user's role and restriction on data handled by the form. They are divided into two groups: • **Standard forms**: allow data to be entered or modified in the database related to the dimensions of and can also be used to extract and consult data, i.e. as reports.. • **Transactional form** :they allow new elements to be created and data to be inserted or modified in the database. They also make it possible to manage dimensions other than standard dimensions and custom dimensions (e.g. SQL formulas), in order to increase the level of detail of the data entered. (see Elements of the transactional forms model).

Form accessibility

Forms can be saved, and therefore made accessible, in several ways.

Accessibility	Description
Shared	Report or data entry form saved in the application database and therefore accessible to all users with the relative rights. They can be exported and saved locally, thus becoming ad hoc.
Ad hoc	Report forms saved on a local computer by a specific user and therefore accessible to that user only. They can be loaded onto the application database and thus become shared. They are created specifically for data consultation.

The function of forms

Depending on their settings, forms can be classified as follows:

- *system form*, i.e. forms predefined by the administrator which can be used as models for developing customised reports. They are not editable, but can be copied and edited to be adapted to various business needs.
- *user form*, or forms created and managed entirely by the user according to their needs.

Web forms

Web forms are forms which can both be opened in the Excel add-in and be run from the CCH Tagetik web interface. They allow the contributor user to access information contained in the database and to perform data entry jobs without having to use the Excel add-in.

All forms are created in Excel and potentially enabled so they are also available as web forms (see Enable web forms by default).

***IMPORTANT**: compared with forms accessible from Excel, web forms have certain limitations (see Features supported by web forms).*

Form advanced selection

Advanced selection rules can be set in the form.

Selection type	Description
Static forms	Manage a fixed structure, i.e. data from the database called up by the filters set in the matrix (see "Form matrices" on page 178).
Dynamic forms	Manage a structure that can change over time, i.e. elements calculated and called up when the form is run using advanced selection rules (see "Dynamic matrices" on page 211).

Origin of the data

Depending on the project's needs, Financial Workspace data, on CCH Tagetik dimensions, or Analytical Workspace data can be managed in forms. Analytical Workspaces are used when the project is useful for creating datasets containing customised dimensions that supplement the CCH Tagetik dimensions.

For more details on Financial Workspaces, see The dimensions of CCH Tagetik.

For more details on Analytical Workspaces, see Forms on Analytical Workspace data.

Reporting: user roles

User roles associated with reporting

A user's ability to design, modify and navigate forms of any type depends on the roles associated with the user in the specific application database. A list of the system roles, correlated with reporting jobs, is provided below. For more details, see Roles.

Role	Description	Licence requested
$ADMINISTRATOR	Has administrator privileges for an application database and can: • design data entry forms and reports • define financial statement templates	Administrator
$USER	Has contributor privileges and, based on the reading and editability rights for the entities for which they are responsible, can: • enter data from data entry forms • run reports and view the data they contain	Power User
$ALL	Can access all $ADMINISTRATOR and $USER functions.	Administrator
$DEREPORT	Can do the following: • run reports • enter data in data entry forms • run data processing included in data entry forms or configured in a process workflow.	Data Entry & Reporting or higher

***Note**: custom roles can be created for specific needs (e.g. create a contributor role with the possibility of creating ad hoc forms).*

Specific dimensions for reporting

What they are for

With the reporting module, data can be fine tuned using the module's specific Amount Type and Period Length dimensions.

Amount type

This dimension specifies the type of data displayed by the matrix and, for data entry forms, the type of data that the user can insert. This dimension is not mandatory.

The dimension's attributes are provided below.

Element	Description
Original in Entity currency	Indicates an amount expressed in the entity currency. This is the value indicated in the process for the entity and, if data are gathered outside of Tagetik, corresponds to the currency inserted by the user in their own system (ERP or Data Warehouse). Default value.
Original amount in transaction currency	Indicates an amount expressed in the currency with which the transaction is carried out (may be different from the entity's default currency).
Description	Allows you to insert notes or comments.
Proportional in Entity currency	Indicates amount types calculated by the system during the consolidation process and allows you to see the corresponding amount for each step. To generate the proportional data, the data processing applies the entity's proportionality percentage, as deployed in the consolidation area, to the original data (expressed in the entity currency).
Converted into Consolidation currency	The amount converted into consolidation currency is generated on the basis of the proportional amount type by multiplying the values by the consolidation currency FX rate.
Consolidable in Consolidation currency	The consolidable amount type is calculated by copying the converted amount, as is the case with consolidated entities using the integrated or proportional method, or by generating the equity evaluation journals for consolidated entities using the equity method.
Converted in Transaction currency	Indicates the amount types calculated by the system during the consolidation process and allows you to see the corresponding amount in the transaction currency for each step.
Proportional in Transaction currency	
Consolidable in Transaction currency	

The Period Length dimension

By default, CCH Tagetik saves data entered by the user on a cumulative basis, i.e. through the cumulative addition of amounts. However, data may be available to the user by period (monthly, bimonthly, etc.). In such cases, the user can calculate and then enter the cumulative data. However, this method is also liable to possible calculation or data entry errors. To prevent this situation, the specific Report dimension can be used, namely the **Period Length** dimension. The user inserts the period data in the data entry forms and CCH Tagetik calculates the corresponding cumulative values.

Example

This example shows the conversion of period data into cumulative data.

Period data	Cumulative data
• Q1 (January - March) = 100 • Q2 (April - June) = 150 • Q3 (July - September) = 250 • Q4 (October - December) = 300	• March = Q1 = 100 • June = Q1 + Q2 = 250 • September = Q1 + Q2 + Q3 = 500 • December = Q1 + Q2 + Q3 + Q4 = 800

To use the Period Length dimension, it is necessary to use length LUN_3 - Quarter.

Period Length values

The values for this dimension are as follows:

Element	Description
Cumulative (LUN_0)	Default value in the CPM (Corporate Performance Management). The system does not carry out any calculation and the amount shown coincides with the amount in the database. In both the CPM and Analytical Workspace multidimensional matrices, the cumulative data are calculated based on the figures from the end of the previous period to the current period.
Monthly (LUN_1)	The cumulative data are calculated taking into account the amount of period n (the period set as a filter in the template) and the amount of period n-1. Generally used for scenarios whose open periods are 01, 02, 03, ... 12.
Bimonthly (LUN_2)	The cumulative data are calculated taking into account the amount of period n and the amount of period n-2. Generally used for scenarios whose open periods are 02, 04, 06, 08, 10 and 12.
Quarterly (LUN_3)	The cumulative data are calculated taking into account the amount of period n and the amount of period n-3. Used for scenarios whose open periods are from 03, 06, 09 and 12.
Every four months (LUN_4)	The cumulative data are calculated taking into account the amount of period n and the amount of period n-4. Generally used when weeks are managed as part of the periods.
Every five months (LUN_5)	The cumulative data are calculated taking into account the amount of period n and the amount of period n-5. Generally used when weeks are managed as part of the periods.
Half Year (LUN_6)	The cumulative data are calculated taking into account the amount of period n and the amount of period n-6. Generally used for scenarios whose open periods are 06 and 12.
Annual (LUN_12)	The cumulative data are calculated taking into account the amount of period n and the amount of period n-12. Generally used for scenarios that only have period 12.
Quarter to date (LUN_QTD)	The cumulative data are calculated from the end of the previous quarter to the current period.
Semester to date (LUN_STD)	The cumulative data are calculated from the end of the previous half-year period to the current period.
Life to date (LUN_YTD)	The cumulative data are calculated from minus infinity to the current period. Useful for multi-year projects.

Period Length is not an obligatory dimension. If not specified, by default the system uses cumulative (LUN_0) in the CPM and monthly (LUN_1) in Analytical Workspaces.

Form Design

Introduction

Data Entry in CCH® Tagetik requires familiarity with the principles and mechanisms of the Reporting system (see The Reporting System), which is based on specially designed Excel sheets, referred to as forms. Forms can be used in two ways:

- As reports (also called output forms), to view data from the database
- As data entry forms, to input data into the database

Depending on the task, reporting functions can be accessed either via the web interface or directly in Excel.

***IMPORTANT**: some activities—such as designing and building a form, can only be performed in Excel. Others, such as running a form to browse data, can be done either in Excel or via the web interface, see Web forms.*

In CCH® Tagetik, the overall definition of the data managed by a form depends on the configuration of data filters applied at different levels of the form structure (see Form Structure).

Livello	Descrizione
Form	Data managed at the global level of the form (see Form Design)
Sheet	Data managed at the template level
Matrix	Data managed and displayed within a specific area of the sheet (see Form Matrix)
Row/column	Data managed and displayed in the rows/columns of the matrix.

Design: basic concepts

Contents

This section covers the following topics:

Structure of the data in the forms and filters ... 96
Designing forms ... 97
Design toolbar ... 98
Creating forms ... 99
New form window ... 102
Batch import window (Import Wizard) ... 102
Batch export window (Export Wizard) ... 103
Managing forms ... 103
Cell fields ... 105
Cell Fields Wizard ... 105
Configuring cell fields ... 106
Validations ... 106
Configuring validations ... 107
Validations window ... 108
Examples of validation ... 110
Dictionaries ... 112
Working on dictionary items ... 113
Form - Import Dictionary window ... 114
Dictionary Items window ... 114
Example: importing dictionaries ... 114

Structure of the data in the forms and filters

Introduction

In CCH Tagetik , the global definition of the data managed by the form depends on the setting of filters on specific data for different levels of the form's structure.

Level	Description
Form	Data handled at the global level in the form
Sheet	Data handled at the template level
Matrix	Data handled and viewed in a specific area of the sheet
Row/column	Data handled and viewed in the rows/columns of the matrix

Applying filters therefore means limiting the data handled in the form, the sheet and the matrix to certain dimensions and categories. When a filter is applied to one of the form's structure levels, it has a domino effect on the levels below.

It is in any case possible to override the exclusion of a filter from a level of the structure of the form that inherited it. For more details, see "Overrides" on page 185.

Saving the Point of View (POV)

Once the run filters have been set and a form has been run, it is possible to save the run settings used via the **Save Point of View** function ( ). In this way, the filters will be set automatically when the form is run. The filter settings window is no longer shown if the POV contains all the filters required by the form.

> ***Note**: in data entry mode, this function also allows you to save the form code so it can be reopened automatically, always in data entry mode, when next accessed.*

Filter settings can be changed and a different POV can be saved, or a POV can be deleted, using the **Delete Point of View** function (). See Finestra Parametri.

Designing forms

Introduction

In CCH Tagetik, forms can be designed for reporting purposes, i.e. to consult and browse the data in the application database, and for data entry purposes, i.e. to edit or enter data in the application database. The design of the structure and the content is identical, but there are specific restrictions on the dimensions, as necessary for the data to be displayed and entered in forms correctly.

Mandatory dimensions

Depending on the selected form type and dataset, some dimensions are mandatory.

Form type	Mandatory dimensions
Report with Financial Workspace data	• scenario • period • amount type • accounts
Data entry with Financial Workspace data	• scenario • period • amount type • accounts • entity • category • all enabled custom dimensions If the details of a custom dimension are not available for certain data, the generic element can be used (see Impostazioni nuova dimensione). For example, if a certain cost is available by product but not by cost centre, when designing the data entry form, a filter can be set on the product dimension and, for the cost centre, the generic element.
Report with Analytical Workspace datasets	• scenario • period • a measure of the dataset • (only with datasets partitioned by business cycle and entity) entity • (only with datasets containing the account dimension) account ***Note**: the scenario and period filters must be specified and must be present in the dataset or inferable from the partition type.*
Data entry with Analytical Workspace datasets	The set of mandatory dimensions for a Data Entry form are the same as those required for an Output Form of the same type.

Specific behaviours per dimension for multidimensional Analytical Workspace matrices

A multidimensional Analytical Workspace matrix can only be run using the in Memory Reporting engine (see Tipi di motori di reporting).

Only matrices with the following characteristics can be used:

- Only with numerical and/or text-based measures. This measure is only managed if the dataset has the data update mode set to "Update the existing record".
- Without Advanced selection (pruning at 0 + Lowest Level)

Also note the following behaviours:

- When the form is saved, if one or more mandatory dimensions are missing from a matrix, the system shows a message with the requirements that are not met.
- If used in at least one of the original datasets, the Account- and Reason-type dimensions, must be used explicitly in the matrix or as global filters on the form.
- When an optional dimension is not specified in the form filters, the system shows aggregate data for that dimension, i.e. it shows the sum of the value of all its elements. For example, if the Product dimension is present in the dataset but not set as one of the form filters, the system shows the sum

of all its products. If the form is a data entry form, it is not possible to write over these aggregate dimensions.

Data entry configuration

A data entry form must contain at least one of the following elements:

- cells editable by user (see "Cell editability" on page 156)
- other formulas (see "Formula filters" on page 237)
- query on cells (see Query)

For more details, consult the relevant pages.

Design toolbar

Excel > CCH Tagetik > Design > select existing form/create new form

Introduction

The design toolbar is shown when a form has been opened from the **Design** tab in the worksheet.

Buttons on the Design toolbar

Element	Description
Definition	
	**Form filters**: opens a window to set the filters to be applied to all templates included in the selected form. See "Form filters window" on page 217.
	**Tab filters**: opens a window to set the filters to be applied to the selected template. See "Tab filters window" on page 220.
	**Matrix**: runs the **Matrix Wizard** to create a matrix based on the cell selected in the work desktop. See "Matrix Wizard - Window structure" on page 187.
	**Query** opens the **Query Wizard** to define an SQL query in the selected cell in the work desktop. See Finestra Wizard query.
	**Cell field**: opens the **Cell fields wizard** to create a cell field in the selected cell in the work desktop. See "Cell Fields Wizard" on page 105.
	**Dictionary item**: opens the **Dictionary item** window to create a dictionary item in the selected cell in the work desktop. See "Dictionary Items window" on page 114.
	**Data processing**: allows you to link data processing to the form and set parameters for it. See Finestra Setup e Amministrazione - Elaborazioni.
	**Hyperlink**: opens the **Action List Wizard** to create a hyperlink in the selected cell in the work desktop. See "Action List Wizard window" on page 303.
	**Report list**: opens the **Report List Wizard** to manage Report lists. See Report List Wizard window.
	**Validation**: opens the **Validation** window to define a validation expression in the selected cell in the work desktop. See "Validations window" on page 108.
	**Slicer**: opens a window to define a slicer in the selected cell in the work desktop. See "New Slicer window" on page 176.
	**Index**: opens the **Report List Wizard** to insert an index of the sheets in the current form. Useful for Report lists which publish the result on a single file and for all forms containing more than one template. See Report List Wizard window.
Overrides	

Element	Description
	**Editable cells preview**: highlights cells on which editability rules have been set. The cell's colour depends on the editability rule set on it. For more details on colour allocation, see "Layout options details" on page 134.
	**Override content**: overrides the content of an element of the matrix with the value entered by the user in the selected cell. See "The Override content on cells function" on page 186.
	**Override editability**: changes the editability of the cell of the selected matrix in the work sheet. For more details on the available options, see "Editability" on page 194.
Parameters	
	**Definition**: opens the **Parameters Definition** window. See "Parameters Definition window" on page 146.
	**Management**: opens the **Parameters Configuration** window. See "Parameters Configuration window" on page 149.
Miscellaneous	
	**Cell properties**: in the left-hand panel, opens the **Cell properties** tab showing information on the selected cell and filters in place.
	**Form options**: opens the **Form options** window to define the form's graphical and functional properties. See "Form options window" on page 133.
	**Export as an ad hoc form**: exports the current form as an ad hoc form, in a folder chosen by the user.
	**Structure check**: checks that the form's structure is correct.
	**List of filters used**: opens the **List of filters used** window showing a list of the form's filters, templates and matrices.
	**Save a copy in the table**: only available in the design phase for ad hoc forms. Save a copy of the current form in the table.
Run	
	**Run**: generates a preview of the form in navigation mode.
	**Partial run**: only available for Report lists. Runs and updates the data for some of the Report list's form only.
	**Print Filters**: generates a preview of the form, highlighting cells containing specific filters requested by the user.
	**Run Web preview**: only for forms available as web forms. Generates a preview of the form on the web interface and activates navigation mode.
	**Run pivot preview**: generates a preview of the form, displaying the content in the form of a pivot table. See Tabelle pivot.
Dashboard	
	**Definition**: only available for forms with the **Enable dashboard** option active. Opens a window to define a dashboard based on the data present in the form template matrices. See "Define Dashboard window" on page 175.

Creating forms

Create a standard form

Excel > CCH® Tagetik > Design > select form grouping >

This procedure explains how to create a standard form from CCH Tagetik's Excel add-in.

1. In the **New form** window, enter a code and one or several descriptions for the form, based on the languages supported by the CCH Tagetik project.
2. Select the desired options.
3. To exclude the form from data entry and navigation, click **Do not display**.
4. To enable/disable the form as a web form, choose the desired option in **Enable as web form**.
5. To enable the form as a Dashboard report, select **Enable dashboard**.
6. To enable the form as a Pivot table report, select **Run as pivot table**.
7. To make the form non-editable, select **Lock Structure**.
8. To use an ad hoc form as a model for the new form, click next to **Ad hoc form** and select the desired file.
9. Click **OK**: the form will be created and opened in Design mode.

Create a multi-template form

Excel > CCH® Tagetik > Design > select form >

See Come accedere alle finestre for alternative paths.

It is possible to create multi-template forms both in the standard form creation step and from pre-existing forms, by adding one or more templates to the default template.

1. Run the desired form in design mode.
2. Click the button at the bottom-left next to the template name.
3. Enter the template name.
4. Alternatively, click on the toolbar, click in the column to the left of the opened document: the new template will appear below the existing template in the form.
5. Design the template with matrices, filters, etc., following the general procedures for reporting.

   ***Note**: we advise against adding spreadsheets that are not associated with a CCH Tagetik template, because they are not managed correctly when the form is run.*

Create an ad hoc form

Excel > CCH® Tagetik > Ad hoc form > New ad hoc form

Excel opens a new spreadsheet in design mode, the structure of which can be defined in accordance with the standard procedures for forms.

***IMPORTANT**: to save the ad hoc form, proceed as you would for a normal Excel document.*

IMPORTANT: In order to save the ad hoc form on OneDrive, at least one of the following variables must be configured with the path of the OneDrive folder:

- *One Drive folder* configured on the excel addin by following the path, *Options -> Local Settings*
- *OneDriveTagetik* configured as Custom environment variable
- *OneDrive* configured as an environment variable

The system follows the following logic:
If the variable One Drive Folder is populated, the relevant path will be evaluated. If the path is correct, the form can be saved correctly, but if the path is wrong, the user will be notified when opening the form that the wrong path has been used and the form will not be retrievable.
If the One Drive Folder variable is not populated, the system checks whether the OneDriveTagetik custom environment variable is present. The evaluation of the correctness of the path is identical to the previous variable.
Only if the One Drive Folder and OneDriveTagetik variables are not populated, the OneDrive environment variable is evaluated with the same logic as the previous ones.

The three variables must have the given names otherwise they are not considered by the system. In the absence of all three variables, the user is informed when saving that one of the variables needs to be set.

Create the structure of a transactional form

Admin | <application database>

Application database > Forms management tile > Elements > ⊕

This procedure explains how to create the structure of a transactional-type form from CCH Tagetik's web interface.

1. In the **Attributes** tab, insert a code and a description for the form.
2. In **Type**, choose the type of form to be created.
3. In **Input type**, select the type of information to be managed in the form. In the **Input properties** section, the system automatically selects input properties that are consistent with the selected input type.
4. (Optional) Change the selected input properties as desired.
5. In **ETL**, select the desired job and period length for running the ETL routine.
6. (Optional) In the **Relationships** tab, select a group of forms with which to associate the form.
7. Click **Save**.

Create a transactional form

1. Create a data entry form, see "Create a standard form" on page 99.
2. Insert the COUNTER element, contained in the **Counter** folder in the dimensions tree, as a row filter.
3. Insert the columns of one of the transactional forms present in the **Column form** folder in the dimensions tree as a column filter: the columns defined in the web interface for that form will be shown.

   ***Note**: the same (measure or dimension) column cannot be inserted on an editable basis more than once.*
4. To be able to subsequently delete data present in a row of the transactional form, the DELETE column must also be included.

   ***Note**: if the DELETE column is not inserted, it will only be possible to edit the data already in the form or insert new data.*

Create a form with a Line by Line matrix

After having created the form structure, it is possible to insert a transactional matrix into the form to create the finalised form.

Excel > CCH® Tagetik > Design > select form grouping > ⊕

1. In the **New form** window, enter a code and one or several descriptions for the form.
2. Select the desired options for the form.
3. Select the cell in which to insert the matrix, the click .
4. In the **Choose the dataset** window, click the desired dataset from the Analytical Workspace.
5. Select the **Transactional** option.
6. Click **OK**.

Once the matrix has been created, the system assigns a default name (e.g. Matrix00, Matrix01...), which can be edited in the matrix wizard by the **Matrix options** tab in the **Code** field.

Create and multidimensional form

Excel > CCH® Tagetik > Design > select form > Matrix

***Note**: a multidimensional form is a form containing multidimensional matrices, which manage data on both rows and columns. For more details, see "Multidimensional matrices" on page 179.*

1. In the **Choose the dataset** window, click the desired dataset.
2. Click **OK**.

Once the matrix has been created, the system assigns a default name (e.g. Matrix00, Matrix01...), which can be edited in the matrix wizard by the **Matrix options** tab in the **Code** field.

***IMPORTANT**: multidimensional matrices cannot be designed on datasets for which the "Show user data only" property is active.*

New form window

Excel > CCH® Tagetik > Design > select form grouping >

Purpose of window

This window allows you to create a new form.

Options in window

Element	Description
Code	Form code.
Description	Form description. In multilingual projects, there is a description field for each supported language.
Run as pivot table	In navigation mode, this allows the form to be opened in pivot mode. This allows you to optimise the matrix formatting and cell rendering processes in Excel. When it is active and several matrices are present, then the form is opened in Excel it becomes mandatory to choose a matrix to display. In the case of Web Forms, only forms containing a single matrix can be run.
System	When selected, this indicates that the form is a system form, i.e. a pre-defined form that can be used as a template to develop customised forms depending on the business at hand. ***IMPORTANT**: once created, these forms cannot be edited. To edit them, this property must be disabled.*
Use as dashboard	This allows you to enable the form to be used as a dashboard. See "Dashboard reports" on page 173.
Lock structure	Only the user who created the form can edit it. Forms with this option active are identified by the icon. It can only be enabled and disabled by users who have function 0000415 – Reporting Excel – Lock templates active in their role.
Do not display	Do not display the form in data entry or navigation modes. This option can be used to prevent forms from being seen by users in the configuration or editing phases.
Enable as web form	Defines whether the form is available as a web form. • **From configuration**: depends on how the *Enable all forms as web forms* option is set in CCH Tagetik's general settings. See Finestra Impostazioni. • **Yes** • **No**
Ad hoc form	Allows you to select an **Ad hoc form** to be used as the template for the new form. The new form will inherit the ad hoc form's structure and configuration.

Batch import window (Import Wizard)

Excel > CCH® Tagetik > Design > select form > Batch import

Purpose of window

This window allows you do load one or more ad hoc forms into the CCH Tagetik application database and save them as standard forms.

Options in window

Element	Description
Input folder	Allows you to select the path in the application database indicating the location from which to read the ad hoc forms.
Grouping	Allows you to select the rule according to which forms will be saved in the application database. • **Imports all forms in the selected node or the *N.A. - Unrelated* node of the grouping**: all ad hoc forms will be saved under the node selected in the left-hand panel, or the *N.A. - Unrelated* node, if no specific mode is selected. • **Recreates nodes using the folder structure based on the selected node or the *N.A. - Unrelated* node of the grouping**: based on the node selected in the left-hand panel, the system creates the nodes in which it saves the ad hoc forms by copying the folder structure in which the forms to be imported are organised in the file system's input folder. If no specific node is selected, the new nodes are saved in the *N.A. - Unrelated* node.

Batch export window (Export Wizard)

Excel > CCH® Tagetik > Design > select form > Batch export

Purpose of window

This window allows the user to download one or more forms from the CCH Tagetik application database onto their device and save them as ad hoc forms.

Options in window

Element	Description
Input folder	Allows you to select the path in the file system indicating the location in which to save the ad hoc forms.
Create grouping	This allows you to recreate, when the form is saved, a folder structure in which the forms will be saved, that is the same as that of the nodes of the grouping to which the forms to be exported are related.

Managing forms

Open a form in Design mode

Excel > CCH® Tagetik > Design

In the left-hand panel, double click on the desired form, or click .

Copy an existing form

Excel > CCH® Tagetik > Design

This procedure describes how to create a form with a similar structure to that of an existing form, by creating a copy of the existing form. After the form has been created, it is possible to make changes to it.

1. In the left-hand panel, select the form to be copied and click , or right click, then click **Copy**.
2. Select the desired folder, then click to paste the new form: the **New form** folder will open.
3. Set the basic configurations for the new form as desired (see "Create a standard form" on page 99).

Transform an ad hoc form into a shared form

Excel > CCH® Tagetik > Design

This procedure describes how to load an ad hoc form onto the application database, to make it accessible to other users.

1. In the left-hand panel, select the grouping node in which you intend to save the form.

   ***Note**: if the grouping node is not selected, the system saves the form in the "N.A. - Unrelated" node.*

2. On the **Design** toolbar, click : the **Import** window will open.
3. Configure the general form settings (see "New form window" on page 102).
4. Click **OK**: the shared form will open.

   ***Note**: if the form is not shown in the left-hand panel when opened, click .*

Transform several ad hoc forms into shared forms

This procedure describes how to load several ad hoc forms onto the application database, to make them accessible to other users.

1. On the **CCH Tagetik** toolbar, click : the **Import Wizard** window will open.
2. In **input folder**, select the path leading to the ad hoc forms to be saved onto the application database.
3. In **Grouping** select the rule according to which the forms must be saved, choosing whether or not to recreate the system of subfolders that may be present in the input folder.
4. (Optional) If you also want to copy the system of subfolders present in the input folder, select **Recreate nodes using the folder structure from the selected node or...**.
5. Click **Next**.
6. Insert the code and description of the form (these are shown in the table of CCH Tagetik forms).
7. Click **Next**: the **Export Wizard Logs** will appear showing details of the exported forms and/or groupings.

   *Click **Copy** to copy the log in text-based format.*

8. Click **End**.

Transform a shared form into an ad hoc form

Excel > CCH® Tagetik > Design

This procedure describes how to export a shared form to create a local copy of it, i.e. an ad hoc form.

1. Open the form.
2. On the **Design** toolbar, click : the **Save As** window will open.
3. Select the file system path to indicate where the form should be saved.
4. Click **Save**.

Transform several shared forms into ad hoc forms

This procedure describes how to export several shared forms in ad hoc format, to create a local copy of them that is only accessible to the user who exported them.

1. On the **CCH Tagetik** toolbar, click : the **Export Wizard** window will open.
2. Select the desired forms or groupings of forms.
3. Click next to **Output folder** and select the file path leading to the location in which the selected forms and/or groupings are to be saved.
4. (Optional) Select **Create groupings** to copy any hierarchies into which the selected forms and/or groupings are organised.

5. Click **OK**: the **Export Wizard Logs** will appear showing details of the exported forms and/or groupings.
6. Click **End**.

Cell fields

Function of cell fields

In the matrix configuration phase, when a dimension element is not defined in the form as a row or column filter, it is clearly not possible to retrieve its description from among the matrix headers. To do this, it is useful to insert *Cell fields* directly into the spreadsheet to allow you view the desired attribute, related to the dimensions used in the form or otherwise, in a header cell (e.g. details of elements defined as matrix filters, form filters or tab filters). Cell fields are also useful for audit purposes.

For example, when the user wants to view, in a cell, information on the last user to open the form and the date on which it was opened, it is possible to create a cell field with the following phrase, for example: User USER1 ran the form on 10/08/2020. This phrase contains two text-based parts ("User" and "ran the form on"), one piece of parametric information that refers to the user name (User function) and one that refers to the date on which the form was opened (runDate function).


Cell Fields Wizard

Excel > CCH® Tagetik > Design > open form > select cell > Cell field

Purpose of window

The Cell Fields Wizard allows you to insert into the form cell fields in which to display specific descriptions.

What it looks like



Element	Description
A	Tree of functions with attributes that can be inserted as cell fields ( )
B	Action buttons
C	Syntax associated with the cell field

Buttons in the window

Element	Description
	Inserts the whole expression associated with the cell field.
	Inserts the current function only, not the entire expression. Useful for manually building cell fields not available in the predefined functions.

Configuring cell fields

Excel > CCH® Tagetik > Design > open form > select cell > Cell field

Inserting a dimensional cell field

1. Select the desired dimension element in **Predefined functions** and click . The syntax for the selected element will be shown in the cell definition area.
2. Repeat step 1 to insert other dimension elements. Elements are separated by the "." symbol.
3. Click **OK**: the cell will be inserted into the form.
4. If useful, edit the cell format.
5. If useful, add a brief description of the cell field's content in the cell next it.

When the form is run, the cell field is defined with the chosen element. By changing the entity or node when opening the form, the cell value changes depending on the selected element.

Inserting text with parametric elements

This procedure shows how to insert parametric text into a cell of the work desktop using parts of text and cell fields.

1. In the definition area of the cell fields wizard, insert the desired text between double quotation marks (e.g. "text"), and concatenate it to the text with operators such as + or -.

   ***Note**: if no operator is inserted by default, they are automatically concatenated using the operator + ", " +.*

2. To insert parametric information, select the desired element from the functions tree and click . The syntax for the selected element will be shown in the cell definition area, next to the inserted text.
3. (Optional) Edit the text-based content as desired and repeat step 2 for every desired dimension element.
4. Click **OK**.

When the form is run, the inserted text and the values of the parametric information to which the syntax refers are shown in the cell.

Delete a cell field

Excel > CCH® Tagetik > Open items

In the left-hand panel **Open items**, select the desired cell field and click .

Validations

Purpose of data validation

When using data entry forms, it is useful to perform *validation* to check that the entered data are correct, before saving them. To do this, CCH Tagetik uses *validation checks*, i.e. conditions defined by the user that the data must fulfil in order to be saved.

There are the following types of validation:

- **Free validations**, performed on the content of an individual Excel cell in a template
- **Matrix validations** performed on the content of each of the cells belonging to a row or column of the matrix

For example, in the presence of a matrix in which users enter the prices of software products sold, if all the products are priced at between EUR 200 and EUR 4000, validations can be used to prevent users from accidentally entering prices outside of the correct range.

The check can be set to run when a form is opened or saved. When the outcome of the check is negative, depending on the configuration, the data will be prevented from being saved, or the system will display non-blocking error messages (warnings) containing details of the cells containing errors.

Levels of matrix validation

The following validation levels can be set:

- On all columns/rows, i.e. the system only saves the data when all columns/rows are correct.
- On at least one column/row, i.e. it only saves the data when the check is successfully passed on at least one of the cells of the column/row.
- On a formula containing the sum of the values of all the columns/rows, i.e. the system only saves the data when the sum of the data remains within a specific value limit.

Validation tolerance threshold

For every form, it is possible to set a threshold below which the system does not report a validation as incorrect (see "Other options details" on page 135).

By default, the value of this threshold is 0.00000001.

Configuring validations

Define a free validation on a cell

Excel > CCH® Tagetik > Design > open form > select cell > Validation

1. Select the operator.
2. Select the data type.
3. Enter a reference value for the check.
4. (optional) Click to add a term to the validation expression.
5. (optional) Change the relationship between the terms of the validation expression.
6. Repeat steps 1 and 2 for the added term.
7. Insert the warning message to be shown when validation is impossible, for every system language.
8. Define the rules for running the validation check.
9. To save the validation, click **OK**.

The validation element will appear in the **Open items** panel, below the node of the current template.

Define matrix validation on a row/column

Excel > CCH® Tagetik > Design > select form > Matrix

1. Select the row/column on which to set the validation check.
2. In the properties table, click ..., next to **Validation**: the **Validation** window will appear.
3. Select the operator.
4. Select the data type.
5. Enter a reference value for the check.
6. (optional) Click to add a term to the validation expression.
7. (optional) Change the relationship between the terms of the validation expression.
8. Repeat steps 3 and 4 for the current term.
9. Insert the warning message to be shown when validation is impossible, for every system language. The message can be defined by applying shared dictionary items (see "Dictionaries" on page 112).

10. Define the rules for running the validation check.
11. To save the validation, click **OK**.

Validations window


Excel > CCH® Tagetik > Design > open form > select cell > Validation

Excel > CCH® Tagetik > Design > open form > open matrix > select row/column filter > (Properties grid) Validation > ...

Purpose of window

This window allows you to define the validation expression based on a validation check.

What it looks like



Element	Description
A	Validation expression definition area
B	Error message definition area
C	Validation performance rules definition area
D	Selection of the validation run mode in matrix

Window sections

Element	Description
Validation check	Allows you to define the conditions of the validation expression.
Error message	Allows you to set, in all system languages, the error message shown in case validation is impossible.
Validation performance rules	The following options are available: • **Blocking**: if validation of the data is impossible, the system prevents it from being saved. If the option is not selected, the system shows a warning message and asks the user for confirmation before continuing. • **Validation on save**: in the data entry phase, validation is performed when the form is saved. • **Validation on close**: in the data entry phase, validation is performed when the form is closed. This option does not allow you to select the **Blocking** option.
Validation run mode in matrix	Only shown during the definition of a matrix validation. Allows you to define the rows/columns on which to run the validation check.

Validation check details

Element	Description
Operator	• **isTrue** and **isFalse**: operator referring to a cell containing a Boolian or numeric value (0=false, <>0= true). • **=, <>, >, >=, <, <=** • **Between** (included between): defines a range of numerical, string or data values within which the insertions must fall. • **IsEmpty**: the validation is passed if the cell is empty. • **IsNotEmpty**: the validation is passed if the cell is not empty. • **IsNumeric**: the validation is passed if the cell contains a numerical value. • **IsString**: the validation is passed if the cell contains a text-based value. • **IsInteger**: the validation is passed if the cell contains a whole number. Any decimal figures introduced by copying and pasting will not be saved.
Type	Defines the type of data on which to run the validation check. Is only required for some operators. The available options are: • **Number** • **Body** • **Date**
Reference value	Defines the reference value to run the validation check.
Concatenation of several conditions	Only with several conditions in the validation expression. Defines the relationship between the individual conditions. • **AND** • **OR**
	Adds a condition to the validation expression.
	Removes a condition from the validation expression.

Error message details

Element	Description
	s you to create a dictionary item for the error message.

Details of validation run mode in matrix

Only shown when the validation is defined on a property of a matrix row/column filter.

Element	Description
The validation must be successful in all columns/rows	Validation is run individually on every cell in the selected row/column and is only successful if the outcome is positive for all cells (there is an 'AND' relationship between the validations)
The validation must be successful in at least one column/row	Validation is run individually on every cell in the selected row/column and is only successful if the outcome is positive for at least one of the cells (there is an 'OR' relationship between the validations).
The validation is performed by summing up the values of the formula in all columns/rows	Validation is run on the sum of the values of all the cells in the selected row/column. This option is particularly useful when you want to define a condition on the total of a row/column without inserting a formula.


Buttons in the window

Element	Description
OK	Saves the validation.
Delete	Only for matrix validations, this is used when the validation definition window is opened and a previously defined validation is present, allowing the user to delete it.

Examples of validation


Introduction

Suppose you have a matrix in which the products sold by a certain company appear on the rows and the user must enter the prices for the scenario/period of budget 2012BDG/12 in the columns. All the products must have a price of between EUR 100 and 150. Given that the values must be entered in the matrix column, let's define a validation on the column.



Example 1: The validation must be successful in all columns/rows.

Let's suppose that incorrect prices of below EUR 100 have been entered. On saving, the system reports that there are errors in the saved data. In the window containing the error message, the system provides a description of the error and the cells in which incorrect values have been entered. In the below example, we have errors in cells C5 and C9.



To successfully save the entered prices, the data in those cells must be edited to ensure that the values fall within the range. Once the values have been changed, the system will correctly save the data.

	2012 Budget
	Dic
Antivirus	120
Operating System	100
Multimedia Player	120
Spyware Removal	130
Utilities	120
Games	120
Total	**710**

Example 2. The validation must be successful in at least one column/row.


Suppose all the prices have been entered incorrectly. On saving, the system reports an error.

To successfully save the entered prices, at least one price must be edited. If one price falls within the range defined in the validation expression, the system saves the data.

	2012 Budget
	Dic
Antivirus	120
Operating System	70
Multimedia Player	155
Spyware Removal	95
Utilities	40
Games	160
Total	**640**

Example 3. The validation is performed by summing up the values of the formula in all columns/rows.

In this case, the data are validated not on the individual values within the column, but on the sum of the values present in it. In the below example, despite the fact that all the individual values are within the defined range, saving failed because the total of the value does not fall within the range of values specified in the validation.



To successfully save the entered prices, they must be edited so that the sum total falls within the specified range.

	2012 Budget
	Dic
Antivirus	10
Operating System	50
Multimedia Player	10
Spyware Removal	50
Utilities	10
Games	10
Total	**140**

Dictionaries

Purpose of dictionaries

To create a multilingual form, it is necessary to prepare the translation for all tables (accounts, reporting forms, FST items, custom dimension elements, form names), so that the descriptions can be shown in the language defined for the specific user, with which the form is accessed (see Impostazioni utente).

> ***Note**: in CCH Tagetik, it is possible to specifically set a reporting language that is different from the system language and the language set in the user profile. For more details, see Pagina impostazioni Localizzazione.*

However, a form may contain other useful fields that are not included among the tables. All these fields can be translated into several languages using a *dictionary item*.

In particular, a dictionary item is useful for obtaining the following outcomes:

- set a description for a placeholder or formula (e.g. "Total")
- override the description used as the existing header of an element within a matrix (e.g. when the filter on the column contains several 'OR' elements)
- insert multilingual text in the form

Dictionary items can be defined both within the matrix and outside of it. The same item can also be used in several forms by creating shared items. Each dictionary item is identified by two elements:

- a **code**
- a **description** in the configured languages.

Some dictionary items may be very frequently used (e.g. "Total"). To save the translations of these items once only and make them available for use in several forms, *shared dictionary items* are created. These items can then be retrieved when necessary.

The **Dict** cell field allows you to retrieve the description of the shared dictionary item in a certain language, based on the code. See "Non-dimensional functions" on page 273.

In particular, web forms support the translation of dictionary items for all Reporting languages, only for dictionaries set up on the web.

Whereas translation of dictionary items is not supported for local dictionaries entered directly into the Excel add-in.

Importing a dictionary

It is possible to create a table of shared items using the **Import dictionary** wizard, which allows you to generate items with descriptions corresponding to those used in the primary language forms, but with codes generated on the fly by the system. In particular, the new codes have the following characteristics:

- they only contain permitted characters (see Creare nuovi codici)
- they do not contain spaces at the start or end
- they concatenate words up to a maximum of 25 characters

Alternatively, it is possible to import items into the shared table by generating the relative codes based on progressive numbering.

Working on dictionary items

Create a dictionary item outside of a matrix

Excel > CCH® Tagetik > Design > open form > Dictionary item

For every managed language, enter the desired text then click **OK**.

***Note**: when the dictionary item is created outside of the matrix, to view the dictionary item in a cell of the form, select the cell before clicking .*

Create a dictionary item within a matrix

Excel > CCH® Tagetik > Design > open form > open or create matrix > Row/column filters

1. Select the element on which to set the description or override the header.
2. In the properties table, click next to **Dictionary**: the **Dictionary item** window will open.
3. For every managed language, enter the desired text then click **OK**: the language set is shown in bold.

Delete a dictionary item

Excel > CCH® Tagetik > Open items

In the left-hand panel, select the dictionary item to be deleted, then click or select the item to be deleted, right click and select **Dictionary items**> **Remove dictionary item**.

Alternatively, click the cell containing the item to be deleted, right click **Tagetik** > **Delete dictionary item**.

Edit a dictionary item

Excel > CCH® Tagetik > Open items

Select the item to be edited then right click and select **Dictionary items** > **Edit dictionary item**.

Alternatively, click the cell containing the desired item, right click **Tagetik** > **Insert/Edit dictionary item**.

Create shared dictionary items

Excel > CCH® Tagetik > Design > open form > Dictionary item

1. From the **Dictionary item** window, click : the **Shared dictionary** window will appear showing a list of the dictionary items that have already been shared.
2. To add a new item, click .
3. Enter a code and a description for the dictionary item.
4. Insert the translations in the system languages.
5. Click **OK**.

***Note**: to view the shared dictionary item in a cell of the form, select the cell before clicking .*

Create shared dictionary items within a matrix

Excel > CCH® Tagetik > Design > open form > open or create matrix > Row/column filters

1. Select the element on which to set the description or override the header.
2. In the properties table, click next to **Dictionary**: the **Dictionary item** window will open.
3. Click : the **Shared dictionary** window will appear showing a list of the dictionary items that have already been shared.
4. To add a new item, click .
5. Enter a code and a description for the dictionary item.

6. Insert the translations in the system languages.
7. Click **OK**.

Form - Import Dictionary window

Excel > CCH® Tagetik > Form - Import Dictionary

Purpose of window

This window allows you to import dictionary items to create a table of shared items.

Import options

Element	Description
Import table	Imports the dictionary items present in the selected forms into the table of shared items.
Replace the instances with a link to the dictionary items in the table	Replaces, in the selected forms, the dictionary items with links to the shared items.
Primary language	Select the language to be used to compare dictionary items.
Consider two items to be equal if	Select the rule according to which two items are to be considered equal so no duplicates are created.
Generate codes automatically	Select the rule according to which codes for the imported dictionary items will be generated.

Dictionary Items window

Admin | <application database>

Forms management tile > Elements > Form Dictionary items

Purpose of the page

This page allows you to create dictionary items shared among the forms. Changes made to dictionary items via this page are also visible in the Excel add-in.

Attributes tab

Element	Description
Code	Dictionary item code
Description <language>	Text of the dictionary item in the supported language.

Example: importing dictionaries

Import with code generation

Let's look at an example of how this wizard can be used. Suppose the user has the following form in which the displayed rows are almost all dictionary items,



report.desc

Entity

Investment Plan

				2013 Plan	
	Description	Fiscal Category	Type	Investment Cost	Need for L/T Financing
Line Item Nodes (for dynamici	1,000	1,000	1,000	1,000	100000%
Invested Total				**1,000**	


Long Term Financing Plan

	Existing Loans	Est. Prepayments on Ex. Loans		
	2012 Actual	2013 Plan	2014 Plan	2015 Plan
Loans	-1,000	999,000	-998,001,000	########
PrePayment	1,000	100000%	100000%	100000%
Debt Rate	-50.0%	-50.0%	-50.0%	-50.0%
Long Period Financial Exp	**1,000**	**499,000,500**	**#######**	**#######**

Depreciation Plan

	2013 Plan	2014 Plan	2015 Plan
Intangible Assets			
Rate	100000%	100000%	100000%
Investment	0	0	0
Amortization	0	0	0
Fund	0	0	0
Tangible Assets			
Rate	100000%	100000%	100000%
Investment	0	0	0
Amortization	0	0	0
Fund	0	0	0


and that they want to import those items into the shared table, generating codes based on the primary language (English). The outcome is:



i.e. based on the description of the dictionary item in the primary language, the system tries to generate a mnemonic code by completing the following steps:

- deleting from the description any characters that are not permitted in codes, e.g. the "/" character from the "Need for L/T Financing" item
- deletes any spaces at the start or end
- concatenates the remaining words, removing any characters at the end if the concatenation exceeds 25 characters

If, however, the items were imported into the shared table with an indication that the codes of the new items must be determined on the basis of a progressive number, the outcome is:


Shared dictionary
1 / 1
New
Edit
Cancel
Save
Code
italiano
English
français
español
000001 ricavo revenue revenue revenue
000002 acquisti purchases purchases purchases
000003 Piano di investi... Investment Plan Investment Plan Investment Plan
000004 Piano di finanzi... Long Term Fina... Long Term Fina... Long Term Fina...
000005 Piano di ammor... Depreciation Pl... Piano di ammor... Piano di ammor...
000006 Amortization Plan Amortization Plan Amortization Plan
000007 Intangible Assets Intangible Assets Intangible Assets
000008 Tangible Assets Tangible Assets Tangible Assets
000009 Existing Loans Existing Loans
000010 TOTAL TOTAL
000011 Tangible Tangible Tangible
000012 Intangible Intangible Intangible
OK
Cancel

Design: style sheets

Contents

This section covers the following topics:

Tagetik styles 118
Applying style sheets 120
Tagetik style window 121
Styles window 122
Styles window - Defined Styles tab 123
Styles window - Styles to use tab 123
Style settings window (Styles) 125
Defining Tagetik styles 125
Example of the definition of style sheets 126

Tagetik styles

Tagetik styles function

Tagetik styles are a reporting formatting tool that allows you to define and customise the appearance of a form: for example, it is possible to highlight certain data and improve the legibility of a table, by applying a specific font or changing the colour of the borders and cells.

To use Tagetik styles, style sheets must be created in the Excel add-in, their attributes must be defined and the style sheet must be applied to the desired forms or matrices.

Applying styles

Once a Tagetik style has been defined, it can be applied at two different levels:

- The form level. In this case, the user can choose whether to use the style defined as the default in the table or a customised style.
- At the matrix level. In this case, the user can choose to apply no style or to apply the style chosen for the form to the matrix's rows only or to its columns only

The style sheet is defined in Excel and therefore becomes available for all forms. Any changes to the style sheet affect all the forms with which it is associated.

Elements of the form to which to apply the styles

Styles can be set on the following elements:

- numbers
- alignment
- fonts
- borders
- fill
- protection

It is useful to create a different style for every attribute, e.g. one for the fonts, one for the numbers, one for alignment and one for the borders, rather than one style containing several definitions. Thus, it is possible to design a flexible layout and create several combinations of styles.

Levels of style application in the matrix

A customised style is applied by associating the styles on the matrix with the elements that make up its structure, shown as a hierarchical tree. The style is then applied downstream from the highest level; the

lower sections inherit the settings of the higher levels, unless a different style is specified.

***Note**: styles can be associated with all sections of the matrix.*

The details of the tree hierarchy and descriptions of its elements are provided below:

Element	Description
(Level 1) Matrix	Highest level of the tree: styles are applied to all elements within the matrix.
(Level 2) Rows and columns	Styles on this level are applied to all the matrix rows/columns.
(Level 3) Row/column structure	Styles on this level are applied on the areas of the row/column structure. The following details are available: • **Only values**: the style is only applied to the row/column values area (numbers). • **Only headers**: the style is applied to the row/column headers. • **Whole area**: the style is applied both to the values area and to the row/column headers.
(Level 4) Row/column content	This is a further detail of the level 3 elements. Here, styles are applied only on the basis of specific content in the row/column values. • **Amounts**: the style is applied to the values read from the database. • **Placeholders**: the style is applied to placeholders defined in the matrix. • **Formulas**: the style is applied to formulas defined in the matrix. • **Subtotals**: the style is applied to subtotal-type formulas defined in the matrix. • **Hyperlink for new elements wizard**: the style is applied to hyperlinks for opening new rows in dynamic matrices. • **FST items** the style is applied to items of the financial statement template used in the matrix. ***Note**: at this level, several styles can be associated with every element.* ***Note**: If there are several elements of this level (e.g. amounts and FST items) in the matrix's row/column filter tree, then the system will apply the style set on the lowest element in the row/column filter tree.*
(Level 5) Formatting type	At this level, styles manage the formatting of FST items, formulas and subtotals. ***Note**: when FST items are defined (see "FST items page" on page 171), it is possible to define the **Formatting type** attribute, which specifies the format that will be applied only to lines with the same formatting.* If there are several levels of formulas and subtotals, this level represents the level at which they are nested within the matrix. *For example:* *- Level 0 subtotals/formulas only depend on non-formula elements (amounts),* *- Level 1 subtotals/formulas depend at the most on level 0 subtotals/formulas.*

When a style is applied to a given section, that section is shown in bold in the tree.

Conditional formatting

The conditional formatting function allows you to specify a condition subject to which the style will be applied when the form is run. Conditions are defined by inserting expressions in cell field syntax (see "Cell fields" on page 105). Some examples are provided below:

Condition	Description
$Period.code = '06'	Apply the formatting for period 06 only
CONTAINS($Scenario.version, "ACT")	Apply the formatting for the current scenarios only
OR($Period.code = "06", $Period.code = "12")	Apply the formatting for periods 06 or 12 only
$Cust_Dim2.attribute5 = "Yes"	Apply the formatting only for elements that have Custom dimension 2 with attribute 5 set as "Yes".

*To insert a condition that needs to be met for the style to be applied, click ... next to **Condition**, or use the predefined functions present in the left-hand column.*

Leading and trailing styles

The **leading** and **trailing** options allow you to apply the style only to the first or last row/column of a matrix. They are useful when you only want to apply an external border to a matrix, for example. In this case, the style must only be applied to the outermost elements of the matrix, leading and trailing.

Styles for the index

The defined styles include specific default styles to format index sheets. These styles can be modified.

Style	Description
TGK_TOC_PAGE_COLUMN	Style applied to the column containing page numbers
TGK_TOC_REPORT_ROW	Style applied to index rows representing a form
TGK_TOC_TEMPLATE_ROW	Style applied to index rows representing a template
TGK_TOC_SHEET_ROW	Style applied to index rows representing a sheet

Tagetik styles for web forms

The style settings configured in the Excel add-in are also valid for web forms. However, when styles are set in Excel, it is possible to determine the elements to be managed in the style, e.g. only fonts, only borders, etc. On the contrary, for web forms the system reads all the existing settings. Consequently, if previously formatted elements have been deselected in the style within Excel, the web form will in any case read all the elements that make up the style.

Applying style sheets

Associate a style sheet with a form

Excel > CCH® Tagetik > Design > open form > Form options

Select the **Layout options** tab and select the desired style sheet in **Tagetik Style**.

> ***Note**: the appearance of the form elements displayed in any working mode is determined when a style sheet is associated with the form. The **Layout options** tab includes parameters that manage the appearance and certain cell formatting characteristics, specifically for using the form in data entry mode.*

Associate a style sheet with a matrix

When a style sheet is associated with the form, its use at the matrix level needs to be activated in any case.

1. Open the matrix (see Come accedere alle finestre).
2. In the **Matrix options** tab, select the **Layout options** tab, then in **Formatting type**, select **Apply Tagetik style**.

The matrix will then be formatted via the style sheet associated with the form in the **Form options** window (see "Associate a style sheet with a form" above).

Associate a style sheet with matrix rows/columns

Even if a style sheet is associated with the form and in use in the matrix, it is possible to define a specific style for one or several rows/columns.

1. Open the matrix (see Come accedere alle finestre).
2. In the **Row/column filters** tab, select the **Layout options** tab, then in **Formatting type**, select **Apply Tagetik style**.
3. In the row/column filters tree, select a row/column filter, then click ... next to **Tagetik style** in the properties table. The system will open a window of styles to be applied. The elements hierarchy only shows elements contained in the row/column.

4. In the elements hierarchy, select the desired element.
5. In the list of styles, select the desired style.
6. Click to create the relationship.
7. Click **OK**.


Tagetik style window

Excel > CCH® Tagetik > Tagetik style

Purpose of window

This window shows a list of the existing Tagetik styles, allows you to create and delete them and change some of their management settings.

What it looks like



Element	Description
A	Action buttons
B	List of Tagetik styles
C	Manage Tagetik styles section

Window sections

Element	Description
List of existing Tagetik styles	Allows you to view a list of the existing Tagetik styles and manage some of their operational properties
Manage Tagetik styles	This allows you to manage the information (code and description) on the selected style sheet, and enter a specific description for every language supported by the system.

Buttons in the window

Element	Description
	Opens a window to define details and formatting in the style sheet.
	Creates a new style sheet.
	Creates a style sheet as a copy of the selected one.
	Edits the description and some characteristics of the selected style sheet.
	Undoes edits to the style sheet that have not yet been saved.
	Deletes the selected style sheet.
	Saves changes made to the style sheet.
	Exports the styles defined in the selected style sheet and makes them available in the currently open Excel file.  *Take advantage of this function in the Collaborative Office environment to produce external reports in the same formats as CCH Tagetik reports. Exported styles can overwrite pre-existing styles or be added to them.*

List of existing Tagetik styles

The following information is shown for each style sheet:

Element	Description
Code	Style sheet code.
Description	Description of the style sheet.
Default style sheet	Sets the selected style sheet as the default style sheet for all new forms created after the current window is closed.
System	Indicates a system style sheet: not editable.
Standard drill down	Indicates the style sheet which, in the absence of default style sheets on the reference form, the system applies to the Excel sheet containing the drill down result (see Drill-down).

Styles window

Excel > CCH® Tagetik > Tagetik style > Definition

Purpose of window

This window allows you to define the characteristics of the selected style sheet.

Tabs in window

Element	Description
Defined styles	Shows a list of the defined styles for the style sheet. ***Note**: the list will appear empty when defining a new style sheet. See "Styles window - Defined Styles tab" on the facing page.*
Style to use	Shows the relationships between the matrix sections and the style to be used and allows you to create styles that are applicable to the matrix sections. See "Styles window - Styles to use tab" on the facing page.

Styles window - Defined Styles tab

Excel > CCH® Tagetik > Tagetik style > Definition > Defined Styles tab:

Purpose of the tab

This tab allows you to see and manage the styles that have been defined on the style sheet from which they are being accessed.

Action buttons in the Defined Styles tab

Element	Description
	Opens a window to select the managed elements to create a new style.
	Opens a window to select the elements managed in the selected existing style.
	Deletes the selected style.
Open index styles	Inserts system styles for index sheets.


Styles window - Styles to use tab

Excel > CCH® Tagetik > Tagetik style > Definition > Style to use tab

Purpose of window

This window allows you to define the style to be used for every section of the matrix of the open form.

What it looks like



Element	Description
A	Hierarchy of matrix elements on which to define styles ***Note**: the elements with which a style is already associated are shown in bold.*
B	List of available default styles
C	List of styles associated with a section of the matrix. ***Note**: the order in which the styles are displayed corresponds to the order in which they are applied at runtime.*
D	Definition area for any conditional formatting
E	Prevailing formatting type selection

Buttons and fields in the window

Element	Description
	Relates the selected style to the selected matrix element.
	Removes the style/matrix element relationship.
	Moves the selected style up.
	Moves the selected style down.

Element	Description
Leading	Allows you to apply the style only to the first row/column of a matrix.
Trailing	Allows you to apply the style only to the last row/column of a matrix.

Prevailing formatting type

Element	Description
Rows Formatting: Prevailing	If several styles are defined on rows and columns for the same sections, the style set on the row will prevail.
Columns Formatting: Prevailing	If several styles are defined on rows and columns for the same sections, the style set on the column will prevail.

Style settings window (Styles)

Excel > CCH® Tagetik > Tagetik style > Definition > New

Purpose of window

This window allows you to create a style and define its characteristics.

Options on page

Element	Description
Style name	Allows you to set the style's name.
Format	Opens Excel's **Format Cells** window.
The style includes (according to selection)	Select one or more elements managed by the style. • **Number**: (default value: Standard) • **Alignment**: (default value: General, Bottom alignment) • **Font**: (default value: Calibri (Body) 11; text 1) • **Border**: (default: No borders) • **Fill**: (default: No colour) • **Protection**: (default value: Locked) When an element is selected, its default settings are shown, and can be customised (see "Styles window" on page 122).

Defining Tagetik styles

Introduction

Defining a Tagetik style involves several levels of configuration, to be carried out in the order indicated below

Create a style sheet

Excel > CCH® Tagetik > Tagetik style

1. Click . A row will appear in the list of Tagetik styles.
2. Insert a code and a description for the Tagetik style.
3. In the list, select the desired operational properties.
4. Click .

Create a style

Excel > CCH® Tagetik > Tagetik style > Definition

1. Click . The **Styles** window will open.
2. Insert a name for the style.
3. Select one or several elements to be defined in the style being created.

   ***Note**: to optimally manage Tagetik styles and correctly apply them in web forms, it is advisable to create one style for every element to be formatted.*

4. Click **Format...**: Excel's **Format Cells** window will open.
5. Set the formatting of the elements selected in step 3 in the relative tab in the window and click **OK**.
6. In the **Styles** window, click **OK**.

Create styles for index sheets

Excel > CCH® Tagetik > Tagetik style > Definition

1. Click **Open index styles**: the styles for index sheets will appear in the list of Defined styles.
2. Select the desired style
3. To change it, click : the **Styles** window will open.

   ***Note**: styles can be renamed*

4. Click **Format...**: Excel's **Format Cells** window will open.
5. Set the formatting of the elements selected in step 3 in the relative tab in the window and click **OK**.
6. In the **Styles** window, click **OK**.

Relate styles to matrix elements

Excel > CCH® Tagetik > Tagetik style > Definition > Style to use tab

1. In the hierarchy of matrix elements, select the desired element.
2. In the list of styles, select the desired style.

   ***Note**: the style related to the element is also applied to any nested elements, if possible and if no style has been associated with them. The sections to which the style is related are shown in bold.*

3. Click to create the relationship.
4. (Optional, if a style has been related to a row/column element) Select the **leading** option and/or the **trailing** option to apply the style to the first or last row/column of the matrix, respectively.
5. (Optional) To make the application of the style conditional, click ... and insert the desired parametric text in the **Cell Fields Wizard**. Alternatively, use the predefined functions present in the left-hand column (see "Inserting text with parametric elements" on page 106).
6. Click **OK** and close the **Styles** window.

Set the prevailing formatting type

Excel > CCH® Tagetik > Tagetik style > Definition > Style to use tab

In **Prevailing formatting type**, select the option to be applied if several styles are defined on rows and columns.


Example of the definition of style sheets

Defined styles

Suppose you want to define three different styles: one for the font to be used within the matrix, one for the numbers and one for the column headers.


It is advisable to create one style for every attribute, i.e. one for alignment and one for borders, instead of creating one style containing both definitions. This allows you to design the layout with greater flexibility, applying various combinations of styles.


To create a new style, click the **New** button in the definition window.




When the "New" button is clicked, the system will open a window in which a name must be assigned to the style being defined, e.g. Text, and the type of style to be applied must be selected. In this case, we have selected "Font" because we want to define the type of font to be used for the data displayed in the matrix. The format of the font can be changed by clicking on the **Format** button.

Web form 2.0 treats the options in the form below as if they were always selected. Consequently, if one of these options is not selected in Excel (e.g. the Fill flag), but one of the related settings has been previously customised (such as background colour or font), that setting will still be applied.







Now let's see how to create the second style to be applied to header columns in our matrix. Suppose you want the header columns to have a blue background, with white text aligned to the centre, and a black border. In this case, we will have to activate the Alignment, Border, Fill options and set the desired format for each of them



The last style to be defined is the one to apply to numbers. Suppose you want the numbers aligned to the right, with two decimal figures. In this case, we will need to activate the Number and Alignment options and set the desired format for each of them.



At this point, our style sheet contains three different styles. Any changes can be made using the **Edit** button.




Style to use

Now let's see how to associated the three styles defined in the previous example – *Column_Headers*, *Numbers andText* – to the various sections of the matrix.


The *Text* style, which sets the font to be used for the entire matrix, must be associated with level 1 of the tree. Then the steps to take are:

- in section (1) select level 1 "Matrix" of the tree;
- in section (2) select the Text style
- click the button 



The *Numbers* style must be assigned to all areas of the matrix in which numbers are shown or to the Rows / Only values section. Then the steps to take are:

- in section (1) select level 3 "Matrix/Rows/Only values" of the tree;
- in section (2) select the Numbers style
- click the button 




The *Column_Headers* style must be assigned to all column headers or to the Columns / Only headers section. Then the steps to take are:

- in section (1) select level 3 "Matrix/Columns/Only headers" of the tree;
- in section (2) select the Column_Headers style
- click the button 

The system shows the matrix sections for which a style has been defined are shown in bold

At this point, when the OK button is clicked, our new style sheet will be ready to be used



The results of applying the style sheet defined in the previous example are shown below. Matrix formatting can be further modified by fine-tuning our style sheet; for example, by adding formatting for row headers, borders and a different font/colour for subtotals and formulas.

	2012 Budget	2012 Actual
	Dec	Dec
Product Revenues	-1000,00	-1000,00
Sales Revenues	-1000,00	-1000,00
Other Revenues	-1000,00	-1000,00
Other Revenues	-1000,00	-1000,00
Total Gross Revenues	-2000,00	-2000,00
Cost of Good Sold	1000,00	1000,00
Variance to STD	1000,00	1000,00
Cost of Purchase	2000,00	2000,00
Direct Margin	-4000,00	-4000,00
Sales Deduction	1000,00	1000,00
Year-End Bonus	1000,00	1000,00
Sales Discounts	2000,00	2000,00
Royalties	1000,00	1000,00
Returned Goods	1000,00	1000,00
Advertising & Promotions	1000,00	1000,00
Salespeople Costs	1000,00	1000,00
Advertising and Promotions	4000,00	4000,00
Total direct costs	6000,00	6000,00
Operational Gross Margin	-10000,00	-10000,00

Design: form structure

Contents

This section covers the following topics:

Structure of a form ... 132
Multi-template forms ... 133
Form options window ... 133
Parameters ... 136
Types of parameter ... 138
Working with custom parameters ... 139
Automatic parameter definition ... 141
Examples of custom parameters ... 141
Parameters Definition window ... 146
Parameters Configuration window ... 149
Advanced selection: scenario and period parameters ... 151
Examples of using dynamic parameters ... 152
Cell editability ... 156
Conditional editability expression window ... 157
Forms grouping ... 158
Working with grouping nodes (Excel add-in) ... 158
Working with grouping nodes (web interface) ... 159
Forms grouping page ... 159
Form groupings page (Structure view) ... 160
Element/node relationships page ... 161
Financial statement templates ... 161
FSTs & KPIs page ... 163
Formulas in financial statement templates ... 165
Standard formula syntax ... 166
How to create a financial statement template ... 167
Setting up a financial statement template ... 168
Particular features of multidimensional formulas ... 170
FST items page ... 171
Relationships page ... 172
Copy From window ... 173
Dashboard reports ... 173
Working with dashboard reports ... 174
Define Dashboard window ... 175
Slicer ... 176
Working with slicers ... 176
New Slicer window ... 176

Structure of a form

Constituent elements

To design a form, the following elements must be defined in accordance with the purpose of the form.

Element	Description
Template	Spreadsheets, which represent the minimum structure of the form. A form may contain one or more templates (see "Multi-template forms" below).
Matrix	Tool for selecting data from the application database by setting filters on CCH Tagetik dimensions. A form may contain one or more matrices on one or more templates.
Filters	Selecting data from the application database to be managed in the form.

Multi-template forms

What they are

In CCH Tagetik, it is possible to create both reports and data entry forms that have several templates, in which every template contains specific matrices and filters.

In both data entry and navigation modes, when a multi-template form is opened, all the templates are run. Multi-template forms can be used for two purposes:

- to create reports (and therefore report books, at the highest level) containing several work folders that are useful in a specific operational context
- to create reports and data entry forms for complex data processing, using formulas that can target cells of other templates.

Example of a multi-template report

To create a report on data at the year-end, a form with three templates needs to be created:

- Profit and Loss
- Balance Sheet
- Indirect cash flow

Example of a multi-template form for data entry and reports

To create a data entry form in which to insert quantities sold by product (Q) and prices per product (P), the following templates must be included:

- one template for inserting the quantities sold
- one template for inserting prices
- one template the shows the result P*Q in order to calculate the total revenues for the products

Restrictions on the names of multi-template forms

The names of the sheets in the form cannot exceed 31 characters. When they are named automatically by the *Link the template name in the sheets* setting, the template name is concatenated to the sheet names, and the name generation algorithm removes excess characters (see "Form options window" below).

Form options window

Excel > CCH® Tagetik > Design > open form > Form options

Purpose of window

This window allows you to manage the general run settings and the layout and operational settings of the current form.

Window tabs

Element	Description
Run settings	Allows you to manage the form's run and save options, the data processing run mode and the query run mode.
Layout options	Allows you to manage the form's layout options and use Tagetik styles.
Other options	Allows you to manage specific operational functionalities of the form.

Run settings details

Element	Description
Data processing type	
Run **Saving** **Run data processing**	Defines how the form and the application server interact. • **Automatic** (default): the system determines how the form interacts with the application server. • **Synchronous**: form interacts with the application server in a synchronous manner. • **Asynchronous**: form interacts with the application server in an asynchronous manner. This option is advisable for slow forms that take more than one minute to run.
Reporting engine	Defines the reporting engine to be used to run the form. ◦ **From configuration**: the reporting engine is defined in advanced form settings (see Settings window). ◦ **Standard**: engine suitable for forms with a high number of filters and form runtimes in excess of one minute (see Standard engine). ◦ **In memory**: engine suitable for simpler forms that have advanced functionalities (see In-memory engine). ***Note**: when the In memory engine is selected, the system warns the user that the concurrency settings will be reset, because they are specific to every type of reporting engine (see Motori di reporting).*
Concurrency	
Concurrency level	Defines the maximum number of queries that can be run concurrently. • **Default**: the number of queries run concurrently is determined by the relative settings at the data processing level (see Data Processing page). • **1 overridden**: manages queries as if they were concurrent, but runs them individually. • **1 (2, 4, 8, ...32)**: the system runs queries one at a time, two at a time, etc. The maximum number of queries cannot exceed the number set for the specific data process in the data processing table (see Data Processing page).
Elements to run concurrently	Defines what elements to run concurrently. • **Templates + Queries** • **Templates + Matrices** • **Templates + Matrices + Queries** • **Templates**
Advanced options: Run in memory	• **Block size rows**: maximum row size of the blocks of data retrieved from the database. • **Size of the data loading threadpool**: number of database connections established. • **Size of the data processing threadpool**: number of blocks processed concurrently.

Layout options details

Element	Description
Colours	
Editable	Defines the background colour of editable cells.
Protected	Defines the background colour of protected cells.

Element	Description
Editable with IC allowed	Defines the background colour of editable cells that allow intercompany data.
With edit Transaction currency	Defines the background colour of editable cells that allow data in the transaction currency.
Layout rules	
Lock output sheets in navigation	Allows you to make the form non-editable when opened in navigation mode.
Tagetik style	Allows you to select the Tagetik style to be used in the form (see "Tagetik styles " on page 118).
Fields separator	Allows you to select the separator to be used in row/column headers when they are made up of a concatenation of several fields.
Generate sheet names according to	Only for forms in which tab filters have been set up. Defines the rule according to which the names of the various sheets are generated. • **Code**: sheet names correspond to the code of the element used as the tab filter. • **Description**: sheet names correspond to the description of the element used as the tab filter.
Link the template name in the sheets	(Only for multi-template forms) Defines the conditions under which the template name must be concatenated to the sheet names. • **Always** • **Never**
Additional information on the headers	(Only for matrices with headers on dimensions for which additional Segment, FX rate, Reference FX rate or Weight type information has been defined) Allows you to configure the headers on which the additional information is displayed. • **On all headers** (default): the additional information is shown on all headers of the dimensions that support it, e.g. Code (SEG.) and Description (SEG.). • **Only on the first header**: the additional information is shown on the first header of every dimension that supports it, e.g. Code (SEG.) and Description. • **Only on the last header**: the additional information is shown on the last header of every dimension that supports it, e.g. Code and Description (SEG.). • **On no header**: additional information is not shown on any header. ***Note**: additional information is shown between parentheses after the relative header.* ***Note**: the additional information is not shown if a dictionary item has been set on the row/column.*

Other options details

Element	Description
Handle custom event callbacks with unprotected sheets	(Only with VBA macros that are associated with a custom event and modify protected sheets generated when the form is run) Allows you to temporarily unlock sheets and lock them again after the macro has been run. For more details on VBA macros, see Custom macros.
Refresh value after saving	Sets the form to automatically refresh when data entered in data entry mode are saved.
Automatically close the form after saving data	Sets the form to automatically close when data are saved.
Disable custom functions	Disables the use of custom functions when the form is run (see "Parameters" on the next page).

Element	Description
Enable Save zero values	Manage cell values of zero. • Active: when a 0 is entered in a form cell, the system creates the corresponding 0 value in the database. • Not active: the system ignores the 0 value and does not edit the database. ***IMPORTANT**: it is not possible to enable the Enable Save zero values option and show data on a non-cumulative basis in the same form (see "Periodic value calculation" on page 191).* ***IMPORTANT**: when both the Enable Save zero values option and the Show zero values if the cells aren't defined option are enabled (see "Matrix options tab" on page 206), the system will also enter and save a zero value in cells with no value, provided they have not been edited directly by the user.* ***IMPORTANT**: When both the Enable Save zero values option is enabled and, on the process for which the form is being run, the Save data in form incrementally option is active (see Pagina Regole Saldi e IC), values that have already been saved on cells cannot be deleted, even if the value is zero.*
Enableschanges made in data entry mode to be tracked.	Enables changes made in data entry mode to be logged. When the form is saved, information on the added/edited rows is saved on the LOG_PROSPETTO_DATA table. The system does not track changes related to transactional forms, intercompany declarations and gross amounts made via the interface, or data processing run when the form is saved. For more details on the table, see "Data entry tracking log" on page 315.
Drill down	Enables drill down functionality (see Drill-down).
Allow Drill down only on used dimensions	Enables drill down only on the dimensions used in the form (see Drill-down).
Tolerance threshold for the check operations	Allows you to set a threshold within which a validation check will not be reported as invalid (see "Validations" on page 106). The default value is 0.00000001.
Validation of Transactional forms when saving data	For transactional forms with which dictionaries are associated, this enables the validation of values assigned to columns when the form is saved. • **Configuration**: validation depends on the value assigned to the relative setting in form settings (see Form tab Details). • **Yes**: allows you, for the current form, to override the setting defined in advanced form configuration and enable validation on saving. • **No**: allows you, for the current form, to override the setting defined in advanced form configuration and disable validation on saving.
Disable lock when reading values	Manage the data processing lock in the database. • **Configuration**: the lock depends on the value assigned to the relative setting in form settings (see Settings window). • **Yes**: disables the database lock when reading data. • **No**: enables the database lock when reading data. ***IMPORTANT**: removing the data lock allows the form to be run faster, but the accuracy of the data displayed cannot be guaranteed, e.g. if several users make changes to the same data simultaneously.*

Parameters

Parameter functionality

In general, designing a form means defining filters on the data in the operational database, on several levels. If fixed filters are defined, to display different elements of a specific dimension it would be necessary to change the form structure, or design several copies of the same form, every time. To make forms easier to read and allow them to be reused, the user can set *parameters*, i.e. filters whose value is not defined when the form is designed, but when it is run. Thus, the form can be run to show different data without its structure being changed, because parameters allow you to select the desired dimensional elements and/or aggregation structures on a dynamic basis. When running, the form therefore only shows the data that the user has chosen via the parameter. For more details on configuring parameters when a form is opened, see "Parameters Configuration window" on page 149.

Parameters can also be used in forms as row/column filters, matrix filters or tab filters. Using parameters to design forms makes increases flexibility when updating the form structure as every change made to the set of elements included in the parameter is automatically taken into account by the same parameter.

It is possible to use *system parameters*, managed by CCH Tagetik, or *ad hoc* or *shared custom parameters*, managed by the user.

Details of the existing types of parameters are provided below.

Supported types of data

Parameters can be based both on dimensional data and on non-dimensional data.

Parameter	Description
Dimensional	The value obtained from a set of elements of a specific dimension: • *Dimension*: element or node of a CCH Tagetik dimension/hierarchy • *Advanced Financial Statement Template*: parameter for advanced FSTs structured by account/custom dimension and/or control type • *Standard Financial Statement Template*: Parameter for standard FSTs structured by account
Non-dimensional	Parameters used for specific configurations typical of advanced selection scripts. • *Flag* • *Date*: date parameter selected from a calendar • *Dictionary*: dictionary item parameter • *Numeric*: number parameter • *Text*: free text parameter • *Process*: process parameter (see)

System parameter details

System parameters are created automatically when forms are deployed (*Application database* > *General deployment tile* > select *Forms* > *Detailed selection* > select *Data model* > *Other tables* > *Forms* > *Update Reporting dimension parameters*). These parameters allow you to choose any element of the dimensions or any of the nodes of the aggregation structures.

System parameters are available in the dimensions tree (in blue) and have a code generated in accordance with the following rule:

- Parameters related to elements of a dimension: *$ + <name assigned to the dimension by Tagetik> + _ P*. For example, the code of the parameter related to the entity dimension is *$AZI_P*, while the code of the origin scenario is *$SCE_P*.
- Parameters related to nodes of an aggregation structure: *$ + <name assigned to the dimension by Tagetik> + _ + <aggregation structure code> + _P*. For example, the code of the parameter related to entity hierarchy G01 is *$AZI_G01_P*, while the code of the group of scenarios is *$SCE_$_P*.

The description of a parameter corresponds with the description of the dimension or aggregation structure from which it originated.

System parameters are identified with the prefix $ and cannot be created, modified or deleted manually.

When the data model is modified, e.g. a new hierarchy is created, the application needs to be deployed in order to use the new system parameter.

Specific features of custom parameters

Custom parameters are created by the user and can contain hierarchy nodes and/or selected individual elements of a dimension. The user can choose a subset of a dimension's elements or nodes, e.g. all of a hierarchy's nodes except for one, lowest level elements only, certain specific elements and nodes, and so on. Creating custom parameters therefore means that you do not have to create specific system hierarchies for individual forms.

Custom parameters are available for all users and can be:

- *shared*, can be used on all forms.
- *ad hoc*, can only be used in the forms in which they have been defined.

When the custom parameter is created or modified, the application needs to be deployed in order to use the new parameter or updated parameter.

Specific features of ad hoc parameters

Ad hoc parameters have the same characteristics as shared parameters but they can only be used in the forms in which they were defined.

The use of parameters is only advisable in the following contexts:

- The parameter is not needed in other forms, e.g. due to overly specific restrictions.
- The form contains a high number of shared parameters and the parameter in question is only necessary for the specific form.
- The parameter does not need to be shared with another form.

In ad hoc parameters, process parameters or dimensional parameters that allow OR clauses cannot be defined on the period, because they are not supported by forms.

Restrictions on parameters

Certain restrictions can be defined on parameters, allowing you to fine tune the behaviour of the specific parameter.

Element	Description
Standard restrictions	These allow you to restrict the elements that can be selected as the parameter value when the form is opened. In particular, standard limitations allow you to do the following: • defined whether it is possible to select lowest level elements, nodes or several OR elements • select values manually from a dimensions tree, specifying them as explicit restrictions • exclude any restrictions defined at the process level on the dimension to which the parameter is linked
Dynamic restrictions	These allow you do define the list of values that can be assigned to the parameter. In particular, dynamic limitations allow you to do the following: • Define the list of values using a dynamic rule (e.g. insert children, insert lowest level elements). • Set dependent parameters using advanced selection script (see "Details of advanced selection scripts for calculating the default value" on page 141).

The concept of dependency allows you to restrict the set of values for a given parameter depending on the value taken on by another parameter.

> ***Note**: the parameter selection window shown when the form is opened (see Finestra Parametri) undoes the selection of a dependent parameter when the parameter on which it depends is changed. Dependent parameters are shown below the parameters on which they depend.*

Types of parameter

Multi-hierarchy parameter

When a parameter is defined on a hierarchy, the user must specify the hierarchy in question. When the form is opened, it will only be possible to choose values belonging to that hierarchy.
In certain types of configuration, it may be necessary to define multi-hierarchy parameters. These parameters are defined on a dimension which, when the form is opened, allows you to choose a hierarchy from among all those belonging to the dimension. Multi-hierarchy parameters can only be defined on the Entity and Target dimensions.

Multi-hierarchy parameters cannot be used within filters (form, tab, matrix, row, column) defined as OR clauses. When the multi-hierarchy parameter is used, it is not possible to select several elements belonging to different hierarchies as OR items.

If a multi-hierarchy parameter is created with a hierarchy that is already being used in the same position (rows, column, matrix filter), the system does not allow the form to be run.

When the form is run, to obtain the hierarchy to which the chosen dimension element belongs, the syntax *@MHP_PARAM.Dimension.HierarchyCode*, where *MHP_PARAM* is the code of the defined multi-hierarchy parameter, can be used in cell fields or in elements that allow advanced selection.

If you decide to use multi-hierarchy parameters on the rows/columns of a matrix, for the description and/or code to be displayed in the headers correctly, the parameter syntax must be added to the headers configured in the Matrix Wizard. For example, with a multi-hierarchy parameter on the Entity dimension, the syntax to use to obtain the description is *$Entity(false).desc*.

Process parameter

The process parameter allows you to view the list of processes included in the table.

It cannot be used in Reporting forms, but it can be used by DTP modules, QDL and Jobs. The following properties can be configured:

- code and description in the Properties tab
- the *Only show active processes* parameter in the Restrictions tab, which limits the display to the table's active processes available for data entry

***Note**: Process parameters are not shown in the dimensions tree for defining form, tab and matrix filters, because they are not supported.*

Dictionary parameter

The dictionary items available for the parameter depend on the dictionary associated with the form.

Dictionary parameters are associated with a transactional dictionary defined on the Financial layer, or an analytical dictionary belonging to an Analytical Information Hub workspace.

In the parameters definition window, after selecting the type "dictionary", you will be able to select its source by choosing whether to use a Financial Layer dictionary or a dictionary from a specific Analytical Workspace.

When Financial Workspace is selected, the system loads all the transactional dictionaries whereas when an Analytical Workspace is selected, the user can choose a dictionary from among all those belonging to the selected workspace.

Dictionary parameters cannot be defined in the following cases:

- The selected dictionary parameter uses an analytical dictionary belonging to a workspace with no dataset.
- The selected dictionary parameter uses an analytical dictionary defined using an SQL query containing dimensional attributes.

The running of the analytical dictionary query is not affected by user restrictions on dimensions.

Working with custom parameters

Create a shared custom parameter

Excel > CCH® Tagetik > Parameters Definition

1. Click : a row will appear in the **Shared parameters** list.
2. Enter a code and a description.
3. In the **Type** section, select the desired data type. If you choose a dimensional data type, select the desired node or dimension in the **Dimensions** pane.
4. In the **Attributes** section, define the properties and default input mode for the parameter when the form is run in the parameters selection window.
5. Click the **Restrictions** tab and, if desired, in the **Attributes** section, set the input options for parameters omitted and restrictions on selectable data in the parameters selection window.
6. In the **Advanced selection** section, define the rules for dynamic parameter input. To define an advanced selection script, select **Advanced selection** and insert the script in the dedicated box.
7. (Optional) In the **Long descriptions** section, set a detailed description of the parameter for the system languages.
8. Click .

Create an ad hoc custom parameter

Excel > CCH® Tagetik > Design > (Left-hand panel) open form > > Parameters Definition

1. Click the **Ad hoc parameters** tab.
2. Click : a row will appear in the list
3. Enter a code and a description.
4. In the **Type** section, select the desired data type. If you choose a dimensional data type, select the desired node or dimension in the **Dimensions** pane.
5. In the **Attributes** section, define the properties and default input mode for the parameter when the form is run in the parameters selection window.
6. Click the **Restrictions** tab and, in the **Attributes** section, set the input options for parameters omitted and restrictions on selectable data in the parameters selection window.
7. In the **Advanced selection** section, define the rules for dynamic parameter input. To define an advanced selection script, select **Advanced selection** and insert the script in the dedicated box.
8. (Optional) In the **Long descriptions** section, set a detailed description of the parameter for the system languages.
9. Click .

Enable automatic input of default values

Application database > (Settings) > Forms tab

When an optional run parameter is not defined by the user, it can be defined automatically by the system by enabling the automatic input of default values at the system settings level.

To do this, in the **Display** section, click **Automatically define parameters if omitted at the start** (see Finestra Impostazioni).

At runtime, based on the parameter settings, the system defines the parameter with a *default value*, or a value defined by a *script* associated with the parameter.

Set a default value for a parameter

Excel > CCH® Tagetik > Parameters Definition

1. Create a parameter (see "Create a shared custom parameter" on the previous page or " Create an ad hoc custom parameter" above).
2. In the **Properties** tab, next to **Input mode**, select **Set using a default value**. A drop-down menu will appear to select the default value.
3. Click and select the default value.
4. Click .

Set a default value using a script

Excel > CCH® Tagetik > Parameters Definition

1. Create a parameter (see "Create a shared custom parameter" on the previous page or " Create an ad hoc custom parameter" above).
2. In the **Properties** tab, next to **Input mode**, select **Script for default value**. A drop-down menu will appear.
3. Click . The **Cell Fields Wizard** will open.
4. Insert the script indicating the desired dimensional value (see "Inserting a dimensional cell field" on page 106).
5. Click .

Automatic parameter definition

Introduction

A form's run parameters can be defined *manually*, where the user chooses the desired value from a list of values, or *automatically*, where the system defines the parameter based on behaviours defined by the administrator user.

Automatic parameter definition methods

When the user does not define an optional parameter, it can be defined automatically according to two methods.

Method	Description
Input default value	The system automatically selects the value indicated as the *default value* in the parameter settings.
Define using dynamic script	The system reads a dynamic script defined by the user in the parameter settings to calculate the default value.

Details of dimensional parameters with default values

When a default value is has been set on a CCH Tagetik dimensional parameter in the definition step, the system will behave in one of the following ways:

- In the presence of parameters with a default value selected by the user or with a default value comprising the output of a TGKML script, when the *Do not display when the default value is specified* option is active, the parameter will not be shown in the parameters selection window (see Finestra Parametri), but the value will be shown directly in the form. When this happens for all the parameters that can be selected in the parameters selection window, the window will not be show.
- For web forms launched from workflow, from which the scenario, period and entity can be unambiguously inferred, when the form is run the default value will be ignored and the parameter will be defined with the value used in the context.
- In the presence of parameters set with default values, when the *Advanced restriction type* option is active, when the form is run the default value will be ignored and the parameter will be defined with the value selected in the adjacent dimensions tree.

The described behaviours are also valid when parameters are selected on opening a DTP (see Parametric DTPs).

Details of advanced selection scripts for calculating the default value

The requirements for defining an advanced selection script to define run parameters are as follows:

- The script must return a single dimensional element (if it returns more than one, the default parameter value will be the OR of all elements).
- The script does not depend on the value of other parameters that have already been set or filters present in the form.

When the script returns an error, an element that is not visible, or an element that is not compatible with the user restrictions and/or characteristics of the parameter, the default value will not be set.

***IMPORTANT**: if the element code set as default is changed, the attribute will be invalidated.*

For more details on the advanced selection, see "Dynamic matrices" on page 211.


Examples of custom parameters

Creating a custom parameter


Suppose we need to configure a form that can only be selected by American entities and we have a hierarchy that groups entities based on a geographical rule, i.e. based on countries and regions. To configure a form based on those requirements, we can create a shared custom parameter to restrict the choice to the North America node and all of its child nodes.

To create the parameter after the form has been opened in Design mode:

- click the **Parameters Definition** button on the Design ribbon bar;
- click the **New** button;
- insert a code (ENTITY_NORTH_AMERICA), a description (North America Entities), assign Dimension as the parameter type and select the hierarchy to be associated with the parameter (X00 - Geographical View).



At this point, we can set restrictions on the selected hierarchy. We only want the child elements of the America node to be selectable. To do this, we need to select the **Restrictions** tab and then select the node A01 America in the **Explicit restrictions** section. If a default node is selected, all of that node's child elements will also be selected. An element can be excluded by deselecting it from the hierarchy tree. In the example below, we have selected the America node and all of its children, except for element C00_E. Thus, when the user runs the form they will not be able to assign C00_E as the parameter value.




Since this parameter is not mandatory, if the user does not assign a value when running the form and automatic input is NOT active for that parameter, the system will not filter on the dimension associated with the parameter when reading the data to be shown.

However, if automatic input is active and the parameter is restricted to nodes X05 - Canada and X04 - USA with the exception of C00_E - Distribution New York then, when reading the data, the system will filter on the dimension associated with the parameter by establishing an OR relationship between the elements, in this case A01, C01, C00, C00_C.

Set restrictions on the selection of dimensional elements

Suppose we need to edit the form created previously for American entities and ensure that the results can only be seen at the individual entity level and not at the country node level. Or, for example, we want the individual entity managers to be able to see their entity's results but not the results for the whole country. We can restrict our previously created parameter by further limiting the set of data that the user can choose for that parameter. If the **Allow Nodes** option is deselected, it will not be possible to choose node elements. Therefore, the user will be forced to choose a single entity for this parameter at runtime.




Set up a dynamic parameter

Suppose we want to create a form that has the products sold by an entity on the rows. Since the products sold by the entity change continually (they are created and withdrawn very frequently) the best thing to do is to create a dynamic parameter so that it doesn't need to be maintained too often.

The process of creating a parameter follows the same steps as in the previous example, with the only difference being that the hierarchy to be associated with the parameter is the product hierarchy.

To make the parameter dynamic, a **selection type** that is not "None" must be defined in the **Restrictions** tab; more specifically, because we want the user to be able to select all the elements related to the products hierarchy, it must be defined as **Insert lowest level elements**.



At this point, this parameter can be used within matrices without the need for updates. When the elements in the hierarchy are changed (new elements added, nodes added/changed), the parameter does have to be changed.

Create a parameter that is dependent on another parameter

For example, supposing that, in the presence of an entity restricted to certain cost centres, once the user has specified the entity on which they want to work, the system will only show the cost centres enabled for that entity.


To obtain an outcome of this kind, the user must:

- create a shared Dimension-type custom parameter associated, for example, with hierarchy X00 - Department of the Cost centre dimension;

- tell the system that, as the parameter can have variable values, it is dynamic, i.e. define a **Selection type** that is not "None" in the **Restrictions** tab;
- activate the **Dependent** option in the **Restrictions** tab.

***Note**: the order in which the parameters are set within the form is important: a dependent parameter must always be placed after the parameters on which it depends.*

A dependent parameter must necessarily be inserted in the form using the Parameters management and positioned in the **Other parameters** group.




In the SP14 release, the concept of dependence was also introduced to the DTP run window, where there are parameters that depend on others. At the moment, only explicit dependency is supported in these situations (i.e. dependence that uses the TGKML 1.0 advanced selection scripts) whereas, if only the dependence check is being used (implicit dependence), then it has no effect on the parameters present in the run window and therefore the results are therefore not influenced.

***Note**: explicit dependence between Scenario-Period type parameters and between Process-Scenario type parameters has been added to both the Parametric Jobs run window and the DTP window.*

Create a parameter for a percentage value

Suppose we need to build a form in which users have to enter a percentage value to run what-if analyses. For example, you want to determine the revenues from a product based on a discount inserted using a parameter.

To obtain an outcome of this kind, a Numeric-type parameter can be used. As parameters of this type are not Dimension parameters, they are not visible within the dimensions tree and must therefore be inserted into the form using Parameters Configuration window.




Parameters Definition window

Excel > CCH® Tagetik > Parameters Definition

Purpose of window

This window allows you to manage shared and ad hoc parameters.

What it looks like



Element	Description
A	Buttons on the page
B	Shared parameters tab
C	Ad hoc parameters tab
D	Configuration tabs

Buttons on the page

Element	Description
	Undoes/repeats the last action.
	Add a parameter.
	Edit the parameter.
	Delete the parameter.
	Duplicate the parameter.
	Undo all unsaved changes to the current parameter.
	Save the current parameter.

Page sections

Element	Description
Shared parameters tab	Shows a list of shared parameters.
Ad hoc parameters tab	Shows a list of ad hoc parameters.
Properties tab	Allows you to define the type of parameter, give it a name and certain attributes. If the type is dimensional, it also allows you to define the dimension and hierarchy.
Restrictions tab	Allows you to define specific restrictions for defining omitted parameters at runtime, advanced selection and explicit restrictions.
Long descriptions tab	Allows you to insert an in-depth description of the parameter.

Properties tab

Element	Description
Code	Parameter code.
Description	Parameter description.
Type section	
Data type	Allows you to define the data type of the parameter. The data can be dimensional or non-dimensional. It is possible to choose dimensional parameters the value of which is obtained from a set of elements of a specific dimension: • **Dimension**: allows you to select elements or nodes of a CCH Tagetik dimension/hierarchy. • **Advanced financial statement templates**: parameter for advanced FSTs structured by account/custom dimension and/or control type, in which a dimension has been included. • **Standard Financial Statement Template**: Parameter for standard FSTs structured by account, with no dimension included When a dimensional option is selected, the **Dimensions** pane opens. It is possible to choose non-dimensional parameters for specific advanced selection script configuration. • **Flag**: yes/no parameters; • **Date**: Date parameter selected from a calendar; • **Dictionary**: Parameter selected from a list of elements; • **Numeric**: Number parameter; • **Text**: Free text parameter. • **Process**: Process parameter.
Parameter origin	Only for **Dictionary**. Shows all existing workspaces.

Element	Description
Dictionary	Only for **Dictionary**. Shows a list of the dictionaries available in the system.
Hierarchy types	Only for **Dimension**. Specifies the type of parameter selected in the dimensions tree below. • **Multi-hierarchy parameter**: to define a multi-hierarchy parameter, the root of the tree dimension (Entity or Target) must be selected. • **Single Hierachy Parameter** • **Flat**: all elements of the parameter (without distinction between hierarchies or groupings)
Dimensions	Only displayed with **Dimension** or **Advanced/Standard Financial Statement Template** in **Data type**. Shows the dimensions tree and allows you to select the desired dimension and hierarchy. For Advanced/Standard financial statement templates, only the account dimension can be selected.
Attributes section	
Mandatory	Makes it mandatory to define the parameter when the form is run. For non-mandatory parameters that are not defined, the system displays aggregated data. ***IMPORTANT**: parameters on the Scenario, Period and Account dimensions are always mandatory.*
Set the description automatically	Only for dimensional parameters. Enables the automatic insertion of the description of the dimension or grouping chosen in the parameter description.
System	Indicates whether the parameter is a system parameter or custom parameter.
Input mode	Defines the default method of defining parameters in the parameter selection window when the form is opened. • **Do not set**: do not enter any value. • **Set with a default value**: (only for **Dimension**-type parameters) allows you to specify a value to be shown by default at runtime. The available values depend on the restrictions defined on the parameter. ***IMPORTANT**: if the element code set as default is renumbered, the attribute will be invalidated.* • **Script for default value**: (only for **Dimension**-type parameters) allows you to specify a value to be shown by default at runtime using an advanced selection script (see "Dynamic matrices" on page 211).
...	(With **Input mode** set to **Set with default value**) Allows you to set the default value for the parameter.
Hide when a default value is specified	(With **Input mode** set to **Set a default value**) If selected, the system hides the parameter from the form run window, and inputs the default value. When the user does not have access to the default value due to restrictions on their user profile, it is not used and the system asks the user to define the parameter. ***IMPORTANT**: if active, the system will use the configuration option:**Automatically define if omitted at the start**.*

Restrictions tab

Element	Description
Explicit restrictions	Allows you to manually define the set of values that the parameter can take on by selecting elements from the dimensions tree.
Attributes	

Element	Description
Automatically define if omitted at the start	Indicates the input mode for parameters not defined by the user: • **From configuration**: the system behaves as specified by the *Automatically define parameters if omitted at the start* parameter, in advanced form configuration (see Dettaglio tab Form). • **No**: the system does not define the parameter. • **Yes**: the system automatically defines the parameter based on the restrictions specified in the definition of that parameter (OR), or as the root of the dimension to which it belongs, if it has no restrictions.
Allow lowest level elements	When the form is run, this allows you to select the lowest level elements of the hierarchy as the parameter's value.
Allow nodes	When the form is run, this allows you to select the nodes of the hierarchy as the parameter's value.
Disable Restrictions for Process	Excludes any restrictions defined by default at the process level from the dimension related to the parameter.
Dependent	(**Selection type** not equal to None) Makes the parameter dependent on the value of another parameter.
Allow OR	When the form is run, this allows you to select several values for the parameter simultaneously.
Advanced selection	
Selection type	Defines the parameter's advanced selection. • **None**: the parameter is not dynamic. **Insert children**: with the parameter, all the parameter's nodes and children are also selected. • **Insert lowest level elements**: with the parameter, all lowest level elements (leaves) of the node whose advanced selection is defined are also selected. • **Advanced selection**: enables an advanced selection script to be written.
Script	Only with **Selection type** set to **Advanced selection**. Allows you to insert an advanced selection script for the parameter.

Long descriptions tab

Element	Description
<languages supported by the system>	List of table languages managed by the system.
Insert text field	Allows you to insert in-depth information on the parameter for the relative language. Descriptions that will be shown in a tooltip when the user positions the cursor over the parameter in the parameters selection window.

Parameters Configuration window


Excel > CCH® Tagetik > Design > open form > Manage Parameters

Purpose of window

This window allows you to manage the run parameters of the current form.

***Note**: this window does not show process-type parameters or dimensional parameters on the period that allow OR clauses, as they are functional to the configuration of the parameters but not directly supported by the forms.*

What it looks like



Window sections

Element	Description
List of parameters	Shows a list of the current form's system, shared and ad hoc parameters and allows you to insert any parameters that are not present into the form as filters. The system automatically labels a manually inserted element as *Overridden*.
Parameter management section	Allows you to manage the parameters associated with the current form. The default parameters are grouped as follows: • **Prompt parameters**: these affect the editability of a cell when a form is run in data entry mode. When the form is run, in the presence of an entity parameter, for example, all the cells that refer to that parameter are locked for the chosen entity and other users cannot edit the data for that same entity. • **Other Parameters**: parameters that do not affect cell editability. For example, if an entity parameter of this type is defined, the entity will not be locked for other users in data entry mode

Parameter management buttons in the form

***IMPORTANT**: the order in which the parameters are displayed has an effect on the parameters that have a relationship of dependency with other parameters. A dependent parameter must necessarily come after the parameter on which it depends.*

Element	Description
	Adds the selected parameter to the list of form parameters, at the bottom of the list.
	Removes the selected parameter from the section.
	Moves the selected parameter up/down.

Buttons in the window

Element	Description
	Undoes/repeats the last action.
	Opens the **Parameters definition** window.
	Allows you to add parameters not included among the form filters as overridden parameters.
	Cancels all unsaved changes and closes the window.
	Saves the list of form parameters.

Advanced selection: scenario and period parameters

Using parameters in the Matrix Wizard

In CCH Tagetik, parameters can be used as row/column filters and matrix filters to create dynamic matrices.

In the dimensions tree, parameters are shown in blue and, once inserted as filters, their properties can be configured (see "Table of row/column filter properties" on page 190 and "Matrix filter properties table" on page 197).

For scenario and period parameters, the properties table can be used to manage additional properties for navigating between the possible values of the parameter.

> ***Note**: Dimensional parameters on the period that allow OR clauses are not shown in the dimensions tree for defining form, tab and matrix filters, because they are not supported.*

Navigating scenario parameters

Parameters on the scenario dimension allow you to create dynamic forms for comparing data saved on different scenarios. In particular, the Parameter **Navigation** property (see "Navigation" on page 197) can be used to create rows/columns between the scenarios of which there exist temporal and comparison logics.

Details and potential uses of the logics according to which navigation can be designed are provided below.

Logic type	Example
Temporal	Uses the temporal relationships defined in the **References** section of the scenarios table (see Anagrafica scenari). For example, in the presence of the *2012ACTUAL* scenario, which collects actual data for 2012, it is possible to create a *Previous*-type relationship with scenario *2011ACTUAL*, and a *Following*-type relationship with scenario *2013ACTUAL*. Chains of scenarios can be crated in relation to the scenario before the previous scenario or even previous/following scenarios in relation to scenarios set as *References #1-5*. For more details, see "Table of row/column filter properties" on page 190 and "Matrix filter properties table" on page 197.
Comparison	Uses the relationships defined in the **References** section of the scenarios table (see Anagrafica scenari), to compare data in forms. The user can indicate up to five *Reference scenarios* numbered from 1 to 5.

The order in which the elements are added to the Navigation list is very important because the system navigates the scenarios in the order in which they are added.

Navigating period parameters

Parameters on the period dimension allow you to see, on the rows/columns, periods calculated on the basis of an offset from the run period. For example, it is possible to define columns that show data for 6 months prior to the reference period.

> **Example**
>
> Choose period 12 if you want to show data for period 6
>
> To do this, set:
>
> - a row/column for the reference period parameter
> - a row/column for the period parameter with the Period Difference property set with the desired offset (-6).
>
> If the user runs the same report for period 11, the system will show period 5 for comparison, and so on.

If the difference is greater than the number of periods in the run scenario, the system obtains the excess periods from the scenario set as the previous or following (depending on whether you are going forwards or backwards).


> ***Note**: in Data Entry mode, the period navigation feature is not fully supported for matrices with Analytical Workspace data. The system does not calculate the value of the scenario dimension correctly if, due to a difference greater than the number of periods present in the run scenario, it is necessary to use the scenario set as the previous or following. This is the case in relation to the editability of multidimensional matrices, transactional matrices and data extracted from transactional matrices.*

Examples of using dynamic parameters

Using parameters

All parameters present in Tagetik (both system parameters and custom parameters) can be used within the Matrix Wizard to make the matrices dynamic.

In Tagetik, there is a parameter for every dimension and hierarchy. Parameters can be selected from the dimensions tree and are distinguished from the other elements by the colour blue. Both shared parameters and ad-hoc parameters can be chosen in the dimensions tree.



Once a parameter from the dimensions tree has been chosen, it can be inserted into the matrix as a row filter, a column filter or a matrix filter. Once inserted into a matrix, a parameter behaves the same way as a fixed value. They can also be nested into other elements and the properties that can be modified in the properties table are the same as for a fixed value (non-parametric) element.

For dynamic scenario and period parameter elements, there are additional properties that are activated in the properties table when inserted in the matrix as row filters or column filters. We will look at these properties in the next sections.

The dimensions tree used to define the Form, Tab and Matrix filters does not show Process-type parameters or dimensional parameters on the period that allow 'OR' operations, as these are not supported by the forms.


Navigating scenario parameters

Navigating scenarios allows the user to create dynamic forms for comparing data saved in the system in different scenarios. When scenarios are defined in Tagetik, temporal links and comparative links can be created between them.

For example, if I defined a scenario called 2012ACTUAL, which collects actual data for the year 2012, I could create a "Previous" type link to scenario 2011ACTUAL and in turn create a "Next" type link between scenario 2011ACT and 2012ACT.

In addition to temporal relationships, comparative relationships between different scenarios can also be defined. For example, a scenario called 2012BDG, which is a forecast for the year 2012, must be compared with the actual data for that year, e.g. 2012ACT. In Tagetik, up to 5 reference-type relationships between scenarios can be defined.

These chains of scenarios can be used within the Tagetik reporting client when scenario-type parameters are selected. When a scenario-type parameter is inserted in a row or column filter, the "Navigation" property is activated in the properties table.




In this window, we need to define the navigation chain for our scenario. Navigation starts from the element chosen by the user when the form is run. For example, if a user chooses scenario 2012ACT and a "Previous" navigation has been defined, scenario 2011ACT will be used.


Scenarios are navigated by choosing an element from the list and clicking the button. The element can be removed using the button. The order of the various scenarios can be changed using the and buttons. Several elements can be inserted to create navigation chains, e.g. the Previous --> Previous scenario or the Previous --> Reference #1 scenario.

The order in which the elements are added to the list is very important as the system navigates the scenarios according to the order in which they are added.


Let's look at an example in which a dynamic matrix is created to compare two actual data scenarios. First, we need to insert a parametric scenario within our matrix. This element will be the element chosen by the user, so we will not set any navigation for the element.



At this point, we must insert the second scenario, which will be the comparison scenario. In this column, we want to see the data for the scenario before the one selected by the user. So let's insert a parameter with the same code as the one inserted previously and set the navigation for the element.



Once navigation has been set for a parameter, the text in the filter window is changed to indicate which chain has been set.



At this point, the dynamic matrix is ready and can be used. Navigation chains between scenarios can be changed within the web interface without having to change the structure of the created form.

Navigating period parameters

The mechanism for navigating between period-type parameters is similar to navigating between scenarios. Offsets related to the parameter chosen as the filter can be defined between dynamic periods.


For example, I want to define a column which, depending on the chosen period, shows me data relative to 6 months earlier. If i choose period 12, the column will be defined with period 6, if I choose period 11, it will be defined with period 5, and so on.

A parameter of this type can be set using the "**Period Difference**" property present in the attributes table when we insert a period-type parametric element in a row or column filter. When we set a period difference, we must set the number of periods back or forward that we want to shift in relation to the chosen period. If the difference is greater than the number of periods in a scenario, the system obtains the periods from the scenario set as the previous or next scenario.

La navigazione del periodo non è totalmente supportata nell'AW, in particolare il sistema non ricava correttamente il valore della dimensione Scenario se, a causa dello scostamento maggiore del numero di periodi, è necessario usare lo scenario impostato come precedente o successivo. Questo si riscontra:

- nell'editabilità delle matrici multidimensionali
- nell'editabilità delle matrici LBL (Line By Line)
- nei dati estratti dalle matrici LBL (Line By Line)

Differences can be inserted directly within properties or using the scroll bar shown when properties are opened. The chosen difference is shown in the title of the edited parameter within the row or column filter.



Cell editability

Introduction

To configure data entry on the form, the user must define editable cells, i.e. cells in which the user can enter data that will be written in the database when saved. To do this, the *Editability* property on row/column filters can be configured in the Matrix Wizard. For details of the property values, see "Editability" on page 194.

The effective editability of a cell depends both on the filter properties and on the rights that the user has in their own role (see I ruoli) and the user's data restrictions. The editability rule on a cell can be overridden using the **Override editability** button on the design toolbar (see "Design toolbar" on page 98).

The cells of data entry forms are differentiated by colour:

Color	Cell status
White	Not editable
Yellow	Editable, but does not allow intercompany data
Green	Editable, and allows intercompany data
Blue	Protected

These colours can be changed for the individual form, via the **Form options** window (see "Layout options details" on page 134).

Editability in intersection cells

On the intersection cell between, for example, an editable row and a non-editable column, the system calculates the intersection between the row editability rules and the column editability rules and makes the cell editable or non-editable based on the rules shown in the table below.

		Column			
		Unspecified	Editable	Protected	Non-editable
Row	Unspecified	NON-ED.	EDITABLE	PROTECTED	NON-ED.
	Editable	EDITABLE	EDITABLE	PROTECTED	NON-ED.
	Protected	PROTECTED	PROTECTED	PROTECTED	NON-ED.
	Non-Editable	NON-ED.	NON-ED.	NON-ED.	NON-ED.

Placeholder element editability

For placeholder elements on the rows/columns, editable status is replaced with "unlocked". A placeholder for which editability has not been specify will be non-editable by default (see "Placeholder elements" on page 229).

Conditional editability

Conditional editability expressions allow you to subordinate the editability of a row/column filter to the occurrence of a condition on other rows/columns of the matrix. Thus, it is possible to unlock the editability of cells set as editable until the occurrence of a certain condition on another cell.

When the form is run in data entry mode, every time the content of the cells to which the expression refers is edited, the system runs a check on the condition.

When a row/column included in the conditional expression is the outcome of a formula, the system only considers the formulas contained in the same sheet that do not use the INDIRECT function.

In general, conditional editability allows you to edit the content of a cell, but not insert comments or attachments. Comments and attachments can only be inserted on multidimensional forms, see "Comments on matrices with conditional editability" on page 311.

Conditional editability and spreading in web forms

When a conditional editability expression contains one or several cell operands the value of which is changed by the running of spreading, a check is run on the expression's conditions after spreading or only

after any changes have been made to the spreading method.

The interaction between conditional editability and spreading is only managed in web forms (see "Spreading" on page 313).

Conditional editability expression window

Excel > CCH® Tagetik > Design > open Matrix Wizard > select a row/column filter > (Properties grid) Conditional editability expression > ...

Purpose of window

This window allows you to define the condition that needs to be met to make a matrix row/column filter editable.

Window sections

Element	Description
Minimum editability level	Defines the editability type to be assigned to the cell when the condition is not met: • **Protected**: the cell is not editable for direct entry, but only via formulas. • **Not editable**(default): the cell is not editable.
Row/column	Allows you to define the logical expression on rows/columns based on the condition to be met.

Details of the expression for the condition to be met

Element	Description
Row/column	Row/column on which to verify the condition. The row/column to which the check relates must be static.
Operator	• **isTrue** and **isFalse**: operator referring to a cell containing a Boolian or numeric value (0=false, <>0= true). • **=, <>, >, >=, <, <=** • **Between** (included between): defines a range of numerical values, a string or data within which the insertions must fall. The first and last values are included in the range. • **IsEmpty**: the condition is met if the cell is empty. • **IsNotEmpty**: the condition is met if the cell is not empty. • **IsNumeric**: the condition is met if the cell contains a numerical value. • **IsString**: the condition is met if the cell contains a text-based value. • **IsInteger**: the condition is met if the cell contains a whole number. Any decimal figures introduced by copying and pasting will not be saved.
Type	Defines the type of data on which to verify the condition. Is only required for some operators. The available options are: • **Number** • **Body** • **Date**
Reference value	Defines the reference value to run the check.
	Adds an expression to the condition.
	Removes an expression from the condition.
Concatenation of several conditions	Only with several conditions based on several expressions. Defines the relationship between the individual conditions. • **AND** • **OR**

Forms grouping

Definition and function

It is possible to create form aggregation structures, called *groupings*. These allow you to group forms according to specific business logics, depending on user restrictions on forms. Working with groupings in a node structure also allows you to optimise form consultation, both in the web interface and in the Excel interface, and to manage collected data more easily.

In CCH Tagetik, there is a predefined grouping called $ - *Forms*, which corresponds to the parent node, and to which all newly created forms are related by default. The grouping can be customised later.

It is also possible to create groupings that are useful for simplifying the management of restrictions on forms and delimiting the list of forms allocated to each individual process. Groupings can be hidden for both data entry and navigation.

Groupings can be defined both in the web interface, by the administrator user (see "Working with grouping nodes (web interface)" on the facing page), and in the Excel interface, by authorised users only (see "Working with grouping nodes (Excel add-in)" below).

Working with grouping nodes (Excel add-in)

Introduction

The following procedures describe how to work on grouping nodes via the Excel add-in.

Create a grouping node

Excel > CCH® Tagetik > Design

1. In the left-hand panel:

If...	Then...
you want to insert the grouping within a node	click on the desired node
you want to insert the grouping at the level of a specific form	click on the desired form

2. Click .
3. In the **New folder** window, insert the desired code and description for the folder.
4. (Optional) To hide the grouping node from the left-hand panel, select **Do not display**.
5. Click **OK**.

Move a form to another grouping node

Excel > CCH® Tagetik > Design

In the left-hand panel: select the form to be moved and drag it to the desired node, or select the form, click , then on the desired node and right click, then click **Paste**.

Add a form to a grouping node

Excel > CCH® Tagetik > Design

In the left-hand panel, proceed as follows:

1. Select the desired form and click , or right click, then click **Copy**.
2. Select the desired grouping node, then click to refresh the form.

***Note**: a form can be related to several grouping nodes.*

Working with grouping nodes (web interface)

Forms management tile > Groupings

Introduction

The following procedures describe how to work on grouping nodes via the web interface.

Create a grouping node

1. In **Forms grouping**

If...	Then...
you want to insert the grouping within a node	click on the desired node
you want to insert the grouping at the level of a specific form	click on the desired form

2. Click . a row will appear in the list of form groupings.
3. In **Attributes**, insert the desired code and description for the grouping.
4. (Optional) To exclude the grouping node from data entry, navigation and reporting jobs, select **Do not display in data entry and reporting modes**.
5. Click **Save**.

Move a form to another grouping node

1. In **Forms grouping**, select the form to be moved and drag it to the desired node, or select the form, click , then on the desired node and right click, then click .
2. Click **Save**.

Add a form to a grouping node

1. Select the desired form and click .
2. Select the desired grouping node, then click to refresh the form.
3. Click **Save**.

***Note**: a form can be related to several grouping nodes.*

Remove a form from a grouping node

1. In **Forms grouping**, select the desired form and drag it onto the **All elements** node.
2. Click **Save**.

Forms grouping page

Admin | <application database>

Forms management tile > Groupings

Purpose of the page

This page makes it possible to manage form groupings.

Page sections

Element	Description
Switch view	**Element/node relationships**: opens the "Element/node relationships page" on the facing page page. **Structure**: opens the "Form groupings page (Structure view)" below page.
Report Grouping	Shows the hierarchy of form groupings.
List of groupings and forms	Shows the form groupings and forms.
Attributes tab	Allows you to manage form groupings or individual forms.

Buttons on the page

Element	Description
	Adds a form.
	Adds a grouping.
	Duplicates a form/form grouping.
	Deletes a form/form grouping.

Attributes tab

Element	Description
Click	
See "Forms page" on page 336.	
Click	
Code	Define a name for the grouping.
Description	Define a description for the grouping.
Form default relationship	When selected every new form is automatically related to the grouping.
Do not display in data entry and reporting	Allows you to exclude the selected grouping of forms from data entry and reporting jobs. Useful for excluding forms created for configuration purposes only, or obsolete forms.

Form groupings page (Structure view)

Admin | <application database>

Forms management tile > Groupings > Forms grouping > Switch view > Structure

Purpose of the page

This page allows you to create form nodes. To associate the form with the node, see "Element/node relationships page" on the facing page.

Attributes tab

Element	Description
Node	Defines the node code.
Description	Defines the node description.
Node type	Indicates the node type. • **Root**: the node is the grouping's parent node. • **Normal**: the node is one of the grouping's nodes.

Element	Description
Parent node	Only with **Node type** set to **Normal**. Allows you to select the parent node of the current node.
Form default relationship	When selected, the system automatically relates every new form to the node. Can be selected on several nodes of the grouping, in which case the form is related to all nodes.
Exclude from reporting	Allows you to exclude the node from reporting. Useful for excluding forms created for configuration purposes only, or obsolete forms.
Sorting	Allows you to configure the order with which the forms and nodes are displayed in the forms tree.

Element/node relationships page

Admin | <application database>

Forms management tile > Groupings > Forms grouping > Switch view > Element/node relationship

Purpose of the page

This page allows you to associated individual forms with nodes of the grouping of forms.

***Note**: once saved, the relationship can no longer be changed from this window.*

Attributes tab

Element	Description
Form	Selects a form.
Forms node	Selects the group with which to associate the form.

Financial statement templates

What is a financial statement template

A financial statement template (FST) is a structure used to aggregate accounts or custom accounts/dimensions that can represent financial statements (IAS profit and loss statements and balance sheets, management reports, direct/indirect financial reports), KPIs and other indices for reporting. A financial statement template can be added to a matrix in its entirety or in part as a filter to be able to design its structure more quickly and efficiently.

***Note**: financial statement templates without accounts or with control type or multi-dimensional formulas cannot be added to matrices drawn on the Analytical Workspace.*

For each financial statement template, relationships can be defined based on account dimension, custom dimension, account/custom dimension pair, account/analytical dimension pair or account/control type pair.

Relationships can be defined synthetically by specifying, in the definition, the individual accounts (or dimensional elements) and/or hierarchy nodes that must be added to or removed from the various FST items: the effective resulting relationships are identified by applying the specifications according to the defined order.

Structure of a financial statement template

A financial statement template is structured into two levels:

Element	Description
First level	May contain the following elements, which constitute the *FST items*: • *Parent element*, or a node to which one or more accounts can be related, showing the sum of the amounts of the relative accounts. • *Formula*, or a formula-type node defined on the basis of a relatable items and/or other formulas. • *Description*, or a description-type node which allows you to customise the template header.
Second level	Contains all the accounts associated with relatable elements.

Specific FST items can be recalled from other financial statement templates.

Financial statement templates in row/column filters

The FST can be added to other row/column filters of the matrix in the following ways.

Element	Description
Analytic	Adds the whole FST structure to the row/column/matrix filters tree, organised over two levels according to the levels of the original template.
Synthetic	Adds the FST structure to the row/column/matrix filters tree, organised over one level, i.e. the first.

Accounts in the financial statement template

For every financial statement template, relationships can be defined based on the following criteria:

- account dimension
- custom dimension
- analytical dimension
- control type

Relationships can be defined synthetically by specifying, in the definition, the individual hierarchy nodes and/or dimensional elements that need to be added to or removed from the FST items.

The order in which relationships are specified in FST items determines the final content of the FST item.



For forms that use FST items with relationships with Accounts or Account/Custom Dimension nodes or Custom Dimension nodes, especially in the presence of relationships with Initial balance accounts/Custom Dimensions, it is advisable to use the in memory reporting engine.

***Note**: financial statement templates containing multidimensional formulas or defined on analytical dimensions can only be used in forms based on the in-memory engine.*

Multiple account relationships

By default, the account or account/custom dimension pair can only be related to a single FST item. Where there are several relationships between one account or account/custom dimension pair and several FST items, the system uses the most recently defined relationship on which deployment has been run. If multiple relationships are activated, the system considers all the FST items related to the account or the account/custom dimension pair and adds the amounts of all related FST items together.

This option may be useful in the following cases:

- For indirect cash flow forecasts in which, based on the annual profit, the depreciation account must be reclassified as two report items in order to obtain the *flow of net working capital generated by operations* and *flow of net working capital generated by investments and disposals*.
- To define an FST item with several relationships and specific items with details of the individual components.

Several FST items related by OR clauses can be concatenated in a formula. In this case, the final result is not equivalent to the sum of the amounts of the accounts involved, but the sum of the amounts of the FST items used. Thus, one single account can contribute several times to the final value of the amount.

***Note**: the in memory engine and the standard engine manage OR clauses in the same way, with the exception of OR clauses between FST items with multiple relationships and FST items without multiple relationships: for forms containing such clauses, the standard reporting engine is not recommended, as it cannot correctly manage multiple contributions for a single account.*

Tagetik styles on FST items

To highlight FST item data (formulas, subtotals), a specific formatting style can be related to FST items. This relationship can be established at the Tagetik style level, and therefore applied to all forms to which it is associated, or at the individual FST item level, and therefore applied to the specific FST item. For more details on styles, see "Tagetik styles " on page 118.

Financial statement template on Analytical Workspaces

For matrices drawn on analytical workspaces, it is possible to use:

- Standard FST defined for the account dimension
- Advanced FST with custom dimension and account dimension

The following are not supported:

- FST without account dimension
- FST with control type
- FST with multi-dimensional formulas
- FST on which on-the-fly conversion is applied
- FST on which onScenarioPeriod is applied

FSTs & KPIs page

Admin | <application database>

Dimensions tile > Account tile > ⋮ > FST & KPI

Purpose of the page

This page allows you to create headers for financial statement templates.

Attributes tab sections

Element	Description
Code and description	Allows you to assign a code and a description to the financial statement template.
Dimensionality	Allows you to associate accounts, custom dimensions and control types to the financial statement template, and to manage their relationships with items.
Advanced	Allows you to define options that regulate the use of the financial statement template: • use of the financial statement template in reporting • they system's behaviour in the event of a sign change on an FST item • types of formula supported in the financial statement template
Valid accounts	Allows you to define the types of accounts that can be related to the financial statement template.

Dimensionality details

Element	Description
Account	Enables FST items to be calculated as the sum of the accounts related to them. Financial statement templates created with this option are saved in the **Standard financial statement templates** folder.
Custom Dimensions	Allows you to select a custom dimension in order to calculate FST items as the sum of the elements of the selected custom dimension. With **Account** selected: FST items are calculated as the sum of the account/custom dimension element combinations. With **Account** not selected: FST items are calculated as the sum of the accounts that are valid on the custom dimension. Financial statement templates created with this option are saved in the **Advanced financial statement templates** folder.
Control type	Enables FST item accounts to be related based on the control type existing between the reference entity (the parent company for consolidated data, the entity for statutory data) and the counterparty entity. For example, the FI account can be related to the FI FST items in *subsidiaries*, *associates* or *other* mode, based on the type of relationship existing between the entity pairs. The Control type differentiates the relationships between an account and the FST items. An account declared to an owned entity can thus be linked to different FST items depending on the defined control type, and on the scenario/period. Financial statement templates created with this option are saved in the **Advanced financial statement templates** folder.
Multiple relationships	By default, every account or account/custom dimension pair can be related to one FST item only. If enabled, it is possible to relate a single account or account/custom dimension pair to several FST items. ***Note**: for this option to be valid on the financial statement template, dependence on the account dimension must be activated in dimensionality. Alternatively, if dependence is only active for the custom dimension, an account must be included in the custom dimension definition.*

Advanced details

Element	Description
Exclude from reporting	Excludes the financial statement template from being used in reporting and data entry forms.
Override Sign for class on the Account by FST item	Enables, on all accounts, the use of the sign class set on the item itself regardless of the class defined on the account.
Formula type	Defines the formula type to be used in the financial statement template for formula-type FST items. • **Standard Formula**: allows you to define standard formulas only (default value). • **MD formula**: allows you to define multidimensional formulas only. Once set, this can only be changed if the financial statement template contains no formula-type items. For more details, see "Formulas in financial statement templates" on the facing page.

Valid accounts details

Element	Description
Select accounts	Defines the characteristics of the accounts that can be related to the financial statement template. • **Account Type**: **Normal**, **Detail**, **Variation** • **Account Nature**: **Profit and Loss**, **Balance Sheet**, **Memorandum**, **Other Stocks**, **Other Variations** By default, the system includes standard accounts, P&L accounts, BS accounts and memorandum accounts. ***Note**: for financial statement templates that depend on the account, at least one account type and nature must be selected.*
Direct cash flow/Indirect cash flow	Only if no options have been selected in **Account types** and **Account nature**. Allows you to define a direct/indirect cash flow financial statement template. The system automatically opens all the corresponding accounts.

Buttons on the page

Element	Description
	• **FST items**: this opens the FST items definition page. • **Copy from**: opens a window to copy FST items between financial statement templates. • **Diagnostics**: downloads a PDF containing a list of all Accounts/Custom dimension elements/Control types that have not been related to any FST item. • **Set formula for cube**: starts the data processing to calculate the formula for cube on FST items containing standard formulas.

Formulas in financial statement templates

Standard formulas

When defining financial statement templates, *standard formulas* can be set on FST items. A standard formula can have the following elements as arguments:

- other FST items of the current template
- FST items of other templates with the same dimensionality (see "Dimensionality details" on the previous page)
- accounts, only in financial statement templates that depend on the account dimension only

For more details, see "Standard formula syntax" on the next page.

IMPORTANT: It is not possible to refer to an FST with multidimensional formulas (FST MD) from a standard FST.

Multidimensional (MD) formulas

Multidimensional formulas allow you to run operations between accounts and/or include other dimensions in operations. To create multidimensional formulas, called *TGKML MD*, the multidimensional script syntax TGKML is used. This syntax derives from the MultiDimensional eXpressions (MDX) language dedicated to OLAP analysis on the SQL Server. For more details on MGKML MD syntax, see Calculation logics of "Multi-Dimensional Script" type.

Financial statement templates containing multidimensional formulas can be used in forms based on the in-memory engine. For more details on multidimensional formulas, see "Particular features of multidimensional formulas" on page 170.

Formula for cube

Standard formulas are suitable for use in relational databases. However, a formula for cube can be created for every standard formula, to be used by external sources such as Microsoft Service. To create formulas for cube, the multidimensional script syntax TGKML is used. This syntax derives from the MultiDimensional eXpressions (MDX) language dedicated to OLAP analysis on the SQL Server. For more details on MGKML MD syntax, see Calculation logics of "Multi-Dimensional Script" type.

Standard formula syntax

Introduction

When a formula is created in a financial statement template, its arguments, i.e. the FST items and/or accounts, are defined, together with the logical operators that establish relationships between the arguments. In the formula definition area, once the desired element type has been indicated, CCH Tagetik provides suggestions to help with its creation.

Syntax of arguments in formulas

The definition, in formulas, of elements based on FST items or accounts is guided by CCH Tagetik.

***Note**: when you type [in the formula definition area, depending on the origin the system will show the elements of the chosen dimension of this financial statement template, other financial statement templates, or accounts depending on what is selected in the "add element from" field.*

If you want to add...	Then...	Example
an FST item of the same template	typing *[* in the formula definition area will open a drop-down menu showing a list of FST items in the template. The syntax for the element is *[<current FST code>|<FST item code>]*	With current financial statement template *010 - Sales revenue*, selecting item *015 - Discount & Promotions* will create the formula element *[010|015]*.
an FST item from other templates	typing *[* in the formula definition area will open a drop-down menu showing a list of all the other existing financial statement templates. The syntax for those items is *[<FST code>|<FST item code>]*.	With current financial statement template *010 - Sales revenue*, selecting item *030 - Depreciation & Amortization* for template *020 - Balance sheet* will create the formula element *[020|030]*.
an account	typing *[* in the formula definition area will open a drop-down menu showing a list of existing accounts in the table. The syntax for the element is *[<account code>]*.	With current financial statement template *010 - Sales revenue*, selecting account *10010 - Cash in Bank Accounts* will create the formula element *[10010]*.

Operators and functions in formulas

A list of supported operators is provided below.

Element	Description
Algebraic operators	• + • - • * • /
Logical operators	• = • <> • > • < • >= • <= • && • ||
Functions	• IF (logical_test, value_if_true, value_if_false) • OR (logical1, logical2) • AND (logical1, logical2) • NOT (logical) • 1 (= TRUE) • 0 (= FALSE)

***Note**: when items are saved, the system highlights any syntax errors.*

Scenario and period elements

The string syntax *onScenarioPeriod()* can be used to calculate KPIs with reference to scenarios and periods other than those present in the form to which the financial statement template belongs. This can be applied to FST items and accounts, and accepts the following arguments:

- a positive or negative number indicating the time difference in terms of period (e.g. *-2* = two previous periods, *2* = two subsequent periods)
- two strings between double inverted commas (") for the scenario code and period code
- reference to a scenario/period using cell fields (see "Cell fields" on page 105).

To separate the account code or account/item and the *onScenarioPeriod* element, "." is used as a separator.

Reference scenarios and periods	Element description	Example of syntax
Previous period of the current scenario	• financial statement template *PL* • *item 0010* • *2 previous periods of the current scenario*	*[PL|0010].onScenarioPeriod(-2)*
current scenario/period	• financial statement template *PL* • item *0010* • current scenario/period	*[PL|0010].onScenarioPeriod($Scenario.code, $Period.code)*, or *[PL|0010]* because the default scenario and period are the current scenario and period
a specific scenario (e.g. 2014BDG), period (e.g. 12):	• financial statement template *PL* • item *0010* • scenario *2014BDG* • period *12*	*[PL|0010].onScenarioPeriod("2014BDG","12")*
last period of the current quarter	• account *0010* • last period of the current quarter	*[00010].onScenarioPeriod(quarter().lastSP())*
last period of the third to last quarter 3	• account *0010* • last period of the third to last quarter 3	[00010].*onScenarioPeriod(quarter().offsetSP(-3).lastSP())*

Example

In a formula with reference to account *00010* read from the current period for period *01*, and read from the previous period for all other periods, the syntax is as follows:

IF($Period.code == "01", [00010], [00010].onScenarioPeriod(-1))

How to create a financial statement template

Admin | <application database>

Dimensions tile > Account tile > ⋮ > FST & KPI

Sequence of procedures to create a financial statement template

1. "Create the header of a financial statement template" on the next page
2. "Create FST items" on the next page
3. "Relate accounts, custom dimensions and control types to FST items" on the next page

Create the header of a financial statement template

1. Click ⊕. A new header will appear.
2. In the **Attributes** tab, insert a code and a description for the header of the FST.
3. In the **Dimensionality** section, select the type of element to relate to the financial statement template (filtered by accounts and/or custom dimensions and/or control type) and, if desired, enable **Multiple relationships**.
4. In the **Advanced** section, select the desired options for the use of the FST, for sign change management on FST items and for the supported types of formula.
5. In the **Valid accounts** section, define the types of accounts that can be related to the financial statement template.
6. Click **Save**.

Create FST items

Dimensions tile > Account tile > ⋮ > FST & KPI > ⋮ > FST Items

1. Click ⊕. A new FST item will appear.
2. In the **Attributes** tab, insert a code and a description for FST item.
3. In **Item type**, select the desired type of FST item.
4. In **Class**, select the FST item class.
5. In **Formatting type**, select the level of formatting for the desired Tagetik style.
6. Click **Save**.

Relate accounts, custom dimensions and control types to FST items

Dimensions tile > Account tile > ⋮ > FST & KPI > ⋮ > FST Items > Relationships

This procedure allows you to create relationships, provided elements that can be related to the form exist.

***IMPORTANT**: the order in which relationships are specified in FST items determines the final content of the FST item.*

1. In the **Attributes** tab, select the desired action for the account.
2. In **Account**, select the desired account or node of accounts.
3. In **FST item**, select the desired FST item.
4. If present, select the desired custom dimension and/or control type.
5. Click **Save**.
6. Run the procedure for all the desired relationships.
7. Click **Deployment**.

Setting up a financial statement template

Admin | <application database>

Relate an account to a parent FST item

Dimensions tile > Account tile > ⋮ > FST & KPI > ⋮ > FST Items

1. Select the desired FST item.
2. In **Description**, insert the desired description.
3. In **Item Type**, select **Parent Item**, then click **Save**.
4. Click the **Relationships** link and add the desired accounts to the FST item.
5. Click **Save**.

Insert a description on a description-type FST item

Dimensions tile > Account tile > ⋮ > FST & KPI > ⋮ > FST Items

1. Select the desired FST item.
2. In **Description**, insert the desired description.
3. In **Item Type**, select **Description**, then click **Save**.

Define a standard formula on an FST item

Dimensions tile > Account tile > ⋮ > FST & KPI > ⋮ > FST Items

Only when **Item type** is set to **Standard formula**.

1. Click ✎: the formula management fields will appear.
2. In **Add item from**, select a financial statement template, an account or a node of accounts to be inserted into the formula.
3. In the formula definition area, type *[*: a list of FST items or accounts available to the relationship will appear.
4. Double click the desired FST item or account: the argument will appear in the definition area.
5. Repeat the previous steps for every desired argument.
6. Create the formula logic using the desired logical connectors and functions

   ***Note**: click **Guide** for more details on formula syntax, or consult the dedicated page in the manual (see "Standard formula syntax" on page 166).*

7. Click **Save**.

Override a formula for cube on an FST item

Dimensions tile > Account tile > ⋮ > FST & KPI

***IMPORTANT**: to define a formula for cube, an FST item containing a standard formula from which to override the formula for MSService cubes must have already been created. For more details, see "Formula for cube" on page 165.*

1. Click ⋮ > **Set formula for cube**: a popup progress bar will open showing the progress of the data processing launched on the entire financial statement template. Wait for the data processing complete message.
2. Click ⋮ > **FST items** and select the desired FST item.
3. In the formula for cube definition area, check the syntax of the formula calculated by the data processing.
4. To edit the formula, select **Override formula for cube** and make the desired changes.
5. Click **Save**.

   ***Note**: when the formula for cube is edited manually, the edited formula is not edited by the subsequent running of data processing to calculate formulas for cube.*

Define a multidimensional formula

Dimensions tile > Account tile > ⋮ > FST & KPI > select an FST that allows the MD formula > ⋮ > FST items

1. Select a row with **Item type**: MD Formula.
2. In the **Formula** definition area, insert the multidimensional formula.

How to exclude individual items from a financial statement template

Dimensions tile > Account tile > ⋮ > FST&KPI > ⋮ > FST Items > Relationships

Normally, all the accounts that belong to the account nodes inserted in an FST item will be included in the relative financial statement template. To exclude some specific items, proceed as follows:

1. In the table, select the account not to be included.
2. In the **Attributes** tab, select the **Exclude** action, then click **Save**: the account is no longer related to the FST item.

How to check the accounts present in the FST items

Dimensions tile > Account tile > ⋮ > FST&KPI > ⋮ > FST Items > Relationships

To check which accounts have been inserted in an FST item after a formula has been applied, it is useful to follow the procedure below.

Select the desired FST item, then click **Definition result**: the **Definition results** page will open, showing all the accounts that have actually been inserted in the FST item.

Particular features of multidimensional formulas

Syntax

For multidimensional formulas, the TGKML MD syntax is used (see Logiche calcolo conti di tipo "Script Multi-Dimensionale"). Some specific elements are described below.

Element	Description
TGKML 1.0 header	Syntax required at start of script. It has the following characteristics: • mandatory in an MD Calculation Logic. • to be omitted in MD-type FST formulas.
The reserved @output clause	This identifies, on the cell containing the MD formula, the result returned by the calculation on a temporary account. This clause is reserved and case-sensitive. For example, *@output :={010, 50010}+{010, 50020};*.
Parent FST items associated with relationships dependent on the account dimension only	It is the only type of FST item to which the MD formula can refer.

Constructing multidimensional formulas

When constructing multidimensional formulas, the following restrictions must be respected:

- It is not possible to use temporary accounts as entire parameters of the 'time skip' or 'number of months' functions, for example *Lag()*, *Span()*.
- As an MD financial statement template can also be used on reporting forms (which are therefore not linked to a specific process), when reference is made to a company node (*Entity.[|NN]* syntax), the user must specify the organisational hierarchy being referred to, i.e. the organisational hierarchy specified in the definition of the data collection process.
- The conversion functionality (*ConvertOriginal*) is not available.
- Assignments to physical accounts to write to the database cannot be defined within a multidimensional formula, but it is possible to use assignments to temporary accounts, which can be reused to calculate the final result (identified by the @output specification. If there are several records in the temporary *@output* account at the end of the script, the amounts will be added up.
- The final result is always a dimensionless number, and so the output Pro directive (conversion of periodic result into *Year-to-date* value) does not need to be specified.

Particular features of cells with multidimensional formulas

Cells containing multidimensional formulas have the following characteristics:

- The script for a multidimensional cell is run separately for every cell in which it appears, applying at runtime all the specific filters set for the cell.
- The currency is always the one indicated for the cell of the form to which the calculation is being applied.
- The amount in the company currency coincides with the amount in the original currency.
- Data are always read from the cube identified by the definition of the matrix in which the financial statement template is being used.
- The result of a multidimensional formula is always a number shown on the relative cell of the report, and not an n-tuple saved in the database.

FST items page


Admin | <application database>

Dimensions tile > Account tile > ⋮ > FST & KPI > ⋮ > FST Items

Purpose of the page

This page allows you to create FST items.

What it looks like



Element	Description
A	List of FST items
B	FST item definition tab
C	Formatting section of formula-type FST items

Attributes tab

Element	Description
Code	FST item code
Description	Description of the FST item
Item type	Define the item type: • **Parent Item**: the item can be related to one or more accounts • **Description**: header line, cannot be related to accounts • **Standard formula**: item determined by a formula
Class	Only with **Parent Item**. Define the FST item class: • **None** • **Cost**: changes the sign. • **Revenue**: does not change the sign (default) • Active • Passive For details, see "Sign class" on page 180.
Formatting type	Allows you to indicate the formatting type of the desired Tagetik style for FST items. See "Levels of style application in the matrix" on page 118.

Formula section

Only with **Item type** set to **Standard formula**.

Element	Description
	Shows the **Add item from** field.
	Hides/shows the **Add item from** field.
Add item from	Indicates the desired dimension on which you want to insert the formula, to view relevant syntax suggestions in the formula definition area. • **Current FST**: items of the current FST (default) • **Other Financial statement templates**: items of other FSTs • **Accounts**
Formula definition area	Allows you to insert the formula text.
Guide	Shows information on the syntax to be used in the **Formula definition area**.
Override formula for cube	Enables the formula definition area for overridden cube.
Formula for cube	(Only with **Override formula for cube** selected) MDX operation to be run on formula-type FST items.

Buttons and/or links on the page

Element	Description
	Copies the selected FST item.
	Pastes a copied FST item below the selected FST item.
Relationships	Opens a window to define the relationships between accounts and FST items.

Relationships page

Admin | <application database>

Dimensions tile > Account tile > ⋮ > FST & KPI > ⋮ > FST Items > Relationships

Purpose of the page

This page allows you to relate accounts, custom dimensions and/or control types to FST items. The fields shown on this page vary based on the settings configured in the **Dimensionality** section of the FST header definition page (see "FSTs & KPIs page" on page 163).

Relationship definition tab

Element	Description
Action	• **Include**: includes the account/custom dimension/control type. • **Exclude**: excludes the account/custom dimension/control type.
Account	Select an account or a node of accounts.
FST item	Select an FST item from the current FST.
Control type	Select a control type.
Custom dimension	Select a custom dimension.

Buttons and/or links on the page

Element	Description
Deployment	Runs the data processing to relate the accounts/custom dimensions/control types to the FST items.
Definition result	Opens a window showing details of the existing relationships.

Copy From window

Admin | <application database>

Dimensions tile > Account tile > ⋮ > FST & KPI > ⋮ > Copy From

Purpose of window

This window allows you to copy FST items from a source FST to the selected FST items.

Options in window

Element	Description
Target FST	Indicates the FST on which to copy the items.
Source FST	Indicates the FST from which to copy the items.
Copy accounts mapping also	Enables the copying of account/custom dimensions/control type relationships on the FST items of the source template.

Dashboard reports

Definition

Charts can be designed to visually represent the data included in a report. To do this, dashboard reports can be prepared.

In a dashboard report, each template can correspond to a dashboard and can, in turn, contain several matrices. The ability to generate charts can be enabled for all matrices.

Only users who have function 0003616 - Reporting .NET - Navigation - Edit dashboard" associated with their own role can configure Dashboard reports.

Filters on charts: slicers and shared slicers

The data shown in charts can be filtered both with filters applied to the form and with filters that can be modified by the user at runtime (see "Slicer" on page 176). However, while the filters applied to the module are applied to the whole report, slicer-type filters are applied to the individual chart.

Slicer filters are defined during the definition of the individual chart but the chosen values can be edited later to obtain a better result in the chart. However, editing a slicer does not run a new query on the database. Changes to the slicer therefore have no effect on the selection of data shown in the chart, but only affect the way in which they are displayed.

Slicers can be shared among matrices. If a slicer is applied to a specific dimension, all the matrices that share the slicer must contain the dimension in question.

Example

A dashboard report contains matrix1, matrix2 and matrix3. The Entity dimension is present on all the matrices. To define a shared slicer on the Entity dimension for every matrix, select **Link the dimensions** in the dashboard configuration window and enable **Share** on the Entity dimension. Then proceed as follows:

- For matrix1, select **matrix2**.
- For matrix2, select **matrix3**.
- For matrix3, select **matrix1**.

Available page layouts

Charts can distributed within pages according to the following predefined layouts:

- Full screen
- Two horizontal panes
- Two vertical panes

- Three horizontal panes (type 1 and type 2)
- Three vertical panes (type 1 and type 2)
- Four panes

***Note**: the system tries to optimise the position of charts. For example, if a template contains 5 matrices and a layout with 4 panes for every page has been chosen, the system will create two pages: the first will contain 4 charts and the second will contain the fifth in full-screen mode.*

Types of chart

A chart from among those contained in the following macro areas can be defined for every matrix in the report: column and bar, pie, line, combinations, maps.

Working with dashboard reports

Define the layout of a dashboard report

For more detailed instructions on how to create a form, see "Create a standard form" on page 99.

Excel > CCH® Tagetik > Design

1. When creating a form (or editing an existing form), activate the **enable dashboard** option.
2. Open the desired report, then click in the design toolbar: the **Define Dashboard** window will open.
3. In **Select a layout**, select the desired layout: a dedicated section will be shown for every template.

   ***Note**: if necessary, new pages will be created automatically to contain all the charts.*
4. In the specific section for each matrix, from **Select a chart**, choose the chart type and dimensions to be shown depending on the chosen type of chart.

   ***Note**: only dimensions defined on (matrix) row and column filters and tab filters can be selected.*

Change the order of charts in a dashboard report

Excel > CCH® Tagetik > Design

1. Open the desired dashboard report, then click in the design toolbar: the **Define Dashboard** window will open.
2. In **Select a layout**, select the desired layout: a dedicated section will be shown for every template.

   ***Note**: if necessary, new pages will be created automatically to contain all the charts.*
3. In **Position charts in the layout panes** it is possible to define which matrix will generate the chart for every pane of the layout.

Navigating dashboard reports

User | <application database>

Dashboard tile > click grouping > select the report

1. Set the required filters, then click **OK**: the charts prepared in the report will be filled in.
2. To view the charts of a specific sheet, select the corresponding tab.
3. To edit the value of the chart filters, click the button and edit the slicer values: only the filtered data will be shown in the chart.

4. To refresh the data in the charts, click .

   ***Note**: if the value of a non-shared slicer is edited, only the data for the current chart will be recalculated. If the value of a shared slicer is edited, the data will be recalculated and all the charts that share the slicer will be refreshed.*

5. To generate pivot tables based on the matrices used to generate charts, click to open a preview.


Define Dashboard window

Excel > CCH® Tagetik > Design > open dashboard form > Definition

Purpose of window

This window allows you to define the appearance of the dashboard report, or choose the types of chart to be displayed, their distribution within the template and the data shown. The default order of the charts within the pages mirrors the order of the matrices within the relative template.

What it looks like



Element	Description
A	List of sheets generated to contain all charts defined for the report
B	Layout section to set how charts are arranged on the page
C	Chart section to define a chart for every matrix

Slicer

Definition

In CCH Tagetik, the *Slicer* functionality allows you to change, directly in navigation mode or data entry mode, the parameters defined on the form without having to rerun the same form or open the form in design mode to edit it.

This functionality allows you to create, in a cell of the form, a slicer that displays a parametric element selection menu. It also allows you to change the slicer directly at runtime.

Working with slicers

Define a slicer

Excel > CCH® Tagetik > Design > select form >

See Come accedere alle finestre for alternative paths.

***IMPORTANT**: before inserting a slicer in the cell, to improve the visibility of the slicer when the form is run, it may be necessary to change the size of the cell in which it will be inserted, or merge it with other cells.*

1. Select the desired cell.
2. Click : the **New slicer** window will open.
3. Select the parameter on which to define the slicer.

   ***Note**: the user can select both parameters defined in the (standard or ad hoc) form, and parameters that are not used in the form but are defined in the system. Unused parameters can be shown by activating the **Show unused parameters** option.*

4. Click **OK**.

The inserted slicer is shown in the cell in the work desktop and in the **Open items** tree, with a description of the selected parameter.

Select a parameter in a slicer

Excel > CCH® Tagetik > Data Entry > open form

Excel > CCH® Tagetik > Navigation > select form >

1. Select the cell with the slicer and click .
2. Select the desired parameter, or click ... to open the selection window and choose the parameter. In this window, the user can define advanced options (e.g. reference FX rates for the selected values).
3. Click **OK**.
4. In the toolbar, click to refresh the form.

New Slicer window

Excel > CCH® Tagetik > Design > open form > select cell > Slicer

Purpose of window

This window allows you to select a parameter on which to create a slicer in the current form.

Columns in window

Element	Description
Used	Indicates whether the parameter is used in the form.
Ad Hoc	Indicates whether the parameter is an ad hoc parameter, i.e. only available in the current form.
Code	Parameter code
Description	Parameter description

Options in window

Element	Description
Show unused parameters	Shows the parameters that exist in the system but are not used in the form.

Design: matrices

Contents

This section covers the following topics:

Form matrices ... 178
The Origin dimension ... 180
Sign class ... 180
Headers ... 181
Setting headers ... 182
Headers tab ... 183
Overrides ... 185
The Override content on cells function ... 186
Overriding cell content ... 186
Setting overrides ... 187
Overrides tab ... 187
Matrix Wizard - Window structure ... 187
Dimensions tree in the Matrix Wizard ... 188
Working in the properties table ... 190
Table of row/column filter properties ... 190
Matrix filter properties table ... 197
Details of FX rate properties ... 199
Details of Reference FX rate properties ... 200
Details of Periodic value calculation properties ... 201
Tagetik style property details ... 201
Specific features of scenario and period parameter properties ... 202
Search window ... 206
Choose the dataset window ... 206
Matrix options tab ... 206
Transactional form editor tab ... 209
Preview window ... 210
Structure and definition of an advanced selection script ... 210
Dynamic matrices ... 211
Creating matrices ... 213
Managing matrices ... 214

Form matrices

What is a matrix?

A form's matrix is the tool with which the user defines the data managed by that form, the ways in which the data are managed, and the ways in which the data are displayed when the form is run. Creating a matrix therefore means deciding how to filter the data of the CCH Tagetik dimensions on the basis of the form's objectives.

When the form is run, the matrix appears as a normal data table in Excel, the row/column structure of which depends on the data managed, but its appearance can be customised using Tagetik styles (see "Tagetik styles " on page 118).

Matrix elements

Matrix configuration involves configuring the following elements via the Matrix Wizard ("Matrix Wizard - Window structure" on page 187).

- "Row/column filters" on page 229 (necessary)
- "Matrix filters" on page 226
- "Headers" on page 181
- "Overrides" on page 185
- Additional management options (see "Matrix options tab" on page 206)

Example matrix

This example describes the creation of a matrix which shows a comparison, for entity 001, of the budget data and the actual data for 2010 relative to the month of December, including the following revenues and costs:

- sales revenue of cost centre "Software sales", product "Antivirus"
- sales revenue of cost centre "Hardware sales", product "Memory cards"
- costs of cost centre "IT", product "Databases"

To do this, the following filters must be set:

- the account, cost centre, product dimensions on rows
- the scenario/period dimension on columns
- entity A01 and the amount type (mandatory dimension specific to Reporting) on the matrix (i.e. on both rows and columns).

The created matrix appears as below.

Entity A01	2010BDG December	2010ACT December
Product Revenues – Sales SW - Antivirus	- 1000	- 980
Product Revenues – Sales HW – Memory cards	- 900	- 950
Product Costs – IT – Databases	2000	2500
TOTAL	**100**	**570**

Transactional matrices

Transactional matrices only manage data on columns. When a transactional matrix is set in the form, the form is called a transactional form. Transactional matrices can manage both Financial Workspace data and Analytical Workspace data.

For more details, see Introduction to transactional forms.

Multidimensional matrices

Multidimensional matrices manage data on both rows and columns.
In particular, multidimensional matrices can be used to manage data from Analytical Workspace datasets. When creating the matrix, the user can select a dataset, a datasource or a virtual dataset for every Analytical Workspace.

The creation of matrices with Analytical Workspace data is subject to the following limitations:

- Multidimensional matrices cannot be designed on datasets with the "Show user data only" property enabled.
- "Comments and Attachments" fields cannot be added to multidimensional matrices, even if the associated dataset contains an equivalent field.
- Matrices cannot be defined on datasources that retrieve data via a different connection from the one used by the user.

Sorting of data in matrix trees

The display mode and order of elements in the dimensions tree and in the local row/column filter and matrix filter trees is defined in CCH Tagetik's general settings (see Settings window).

Display rules can also be set directly from the Excel interface, via the  **Display mode** icon in the design toolbar (see Tool bar).

Sorting entity, category and custom dimensions data

The order of elements related to the entity, category and custom dimensions is defined in the **Sorting** tab in the general settings for each dimension. For more details, see How to work with dimensions.

***Note**: whatever the configuration, the order is always ascending.*

The Origin dimension

What is it for

The *Origin* dimension allows you to obtain information on the origin of data. It can be used as a row/column filter, a matrix filter, a tab filter or a form filter, statically by selecting a lowest level element, or dynamically by using a system parameter (see "System parameter details" on page 137).

Specific features for use in parametric forms

Both during the design and during the running of parametric forms, the origin dimension defines the comparison condition with which to filter the data based on their origin. The comparison is on textual data via comparison operators:

- the operator "=" specified a single origin to be displayed
- the operator "<>" excludes the specific origin from the comparison

For example, by specifying "=" as the comparison operator, and *INPUT_DEFORM* as the comparison value on an origin filter, you can obtain the sum of all the figures with origin *INPUT_DEFORM*.

For more details on the possible values for the origin dimension, see Provenienza dei dati.

Sign class

Introduction

The sign with which amounts are shown in forms depends on general settings made in the system and on any specific overrides made at the individual account or FST item level, therefore in the report and/or template definition.

Depending on the needs of the project, it is possible to show the amounts with their original sign inverted in relation to the sign they have in the database, or as an absolute value (all amounts shown as positive).

In particular, setting the *Debit* sign determines the relative sign for the *Credit* sign (which will have the opposite sign). The sign setting for *Asset/Liability* and *Asset/Liability Increase* and *Asset/Liability Decrease* balance sheet amounts is valid in reporting for all the related amounts.

Both in data entry and navigation, if a value with a different sign has been inserted on the individual account or FST item, the system inverts the sign based on the accounting classes associated with the account/FST item in question.

***Note**: the following accounting classes are available in CCH Tagetik: Revenue, Cost, Asset, Liability, Asset increase, Asset decrease, Liability increase, Liability decrease.*

Details of signs

The sign attributed to the various accounting classes determines the sign with which the amount, if inserted from a data entry form, is saved on the database. When, at the account or FST item level, the sign inserted is the opposite of the sign defined on the accounting class in general settings, to save on the database the system recalculates the amount to obtain the sign indicated in the class settings.

A positive or negative value can be attributed to the Debit sign. The behaviour of the accounting classes, depending on the sign, is described below.

Debit sign	Description
Positive	On the application database, revenue and liability values are saved with a negative sign, while cost and asset values are saved with a positive sign. Therefore, if the signs of the values entered on this type of account are consistent with the signs specified above, the system will not change the sign.
Negative	On the application database, revenue and liability values are saved with a positive sign, while cost and asset values are saved with a negative sign. Therefore, if the signs of the values entered on this type of account are consistent with the signs specified above, the system will not change the sign.

Example: to create a balance sheet FST in which every line needs to have a positive sign, the signs of the accounting classes Liability and Liability (Decrease) must be set to positive in general settings. At the specific FST item level, it is then necessary to set the liability sign class for all liability accounting items.

Override the sign class on the account from FST item

When it is not necessary to change the sign on the individual accounts, or when a single logic is used for the FST items and the accounts related to them, the *Override Sign for class on the Account by FST item* option in the FST settings allows the accounts related to an FST item to inherit the sign class set on the same item (see "Financial statement templates" on page 161).

> ***Note**: In the case of dynamic matrices, in the presence of an account with a sign class inherited from an FST item and a dimension with "Insert children" selection type, the system will also apply the sign change to the generated subtotals.*

***IMPORTANT**: If the FST item contains a Formula, it does not inherit the sign from a hierarchical parent; the sign is derived from:

- the **Class**, if set on the FST item containing the formula;
- the **calculation expression**, i.e. the way in which the operators (+, -, ×, ÷) combine members that already have their own sign, including any reverse sign (sign inversion by convention) and aggregation signs (the sign contribution in hierarchical totals), according to the **basic rules of arithmetic**.
- any **overridden rules at the report level**

Override the sign in the Matrix Wizard

In reporting, the class settings given on the tables are visible in the dimensions tree in the matrix creation step, both for FSTs and for accounts.

In the matrix definition step it is possible to manually insert change sign settings for the sign that the system proposes as the result of attributing a certain sign class.

Based on the sign changes, the system shows the filter with specific colours.

If...	Then...
the class-sign combination present in configuration on the *debit* account entails a sign change	the filter is shown in orange.
the sign changes due to a manual override	the filter is shown in red.
due to the overridden sign change, the filter returns back to the sign that it had before the class was applied	the filter is shown in black.

For more details, see "Sign change" on page 192.

Headers

What they are for

By default, when the form is run, in the matrix table the row/column filters are identified by the table description of the dimension to which the dimensional elements of the filters refer.

***Note**: if the additional information Segment, FX rate, Reference FX rate, Weight is defined for dimensions on which a header is defined, then the system shows those properties at the end of the header (see "Layout options details" on page 134).*

For example, for the scenario filter *2021 Actuals*, in the Matrix Wizard the predefined header is *Description ($Scenario.desc)*, which recovers the description in the scenario table.

To facilitate the reading of tables and/or supplement the row/column descriptions, customised headers can be set for every filter. In particular, the predefined description can be replaced or supplemented with one or more descriptions, linked in a chain, from those available for the dimension.
Alternatively, it is possible to replace the description with a dictionary item which, once created on the row or column, is available among the headers.

When multiple descriptions are set, it is possible to choose whether to display the information in a single cell, separated by the "|" sign, or on several different cells on the same row, see "Setting headers" below.

Advanced Headers

In some cases, it is necessary to compose more complex headers, the definition of which depends not only on the dimensions used as filters, but also on all other dimensions available in the system. In this case, it is possible to use an advanced editor, the Cell Fields Wizard, which allows you to set how the text of attributes not related to the dimension is displayed in the cells (see "Cell fields" on page 105).

Descriptive information regarding the entire matrix cannot be inserted as headers, but only using cell fields.

Header structure

Headers show information as follows.

Element	Description
Segment	• *(SEGM.)* for *Per Segment* • *(PARENT SEGM.)* for *Per Segment Parent* • *(INTERSEGM.)* for *Per Intersegment* • *(PARENT INTERSEGM.)* for *Per Intersegment Parent* For more details, see "Tab filter properties" on page 222.
FX rate type	• *(Average FX rate)* • *(Final FX rate)* • *(Based on account)*
Dividing factor	• *(Periods)* in case of period factor • *(Days)* in case of daily factor
Reference FX rate	The FX rate's time reference with the relative FX rate type. For example, for a reference FX rate on the May period with average FX rate, it shows (REF.CH. 05 - May(Average FX rate)).

No additional information is shown if a dictionary item is set on the row/column.

Setting headers

Excel > CCH® Tagetik > Design > select form > Matrix > Headers

Edit an individual header of a dimension

1. In the list of predefined headers, expand the **Predefined functions**, then expand the desired nodes of headers, then select the desired header.
2. Click .
3. (Optional) In the list of defined headers, remove the header initially set by the system (the description of the dimension).

Create multiple headers to be shown on several rows/columns.

1. In the list of predefined headers, click **Predefined functions**, then click the desired hierarchy nodes, then select one or more desired headers.
2. Click .

Create multiple headers to be shown in a single cell.

1. In the list of predefined headers, click **Predefined functions**, then click the desired hierarchy nodes, then select one or more desired headers.
2. Click .

Headers inserted in this way will appear in a single cell, separated by a comma.

Edit the order of multiple headers

1. In the list of defined headers, select the desired header then click . The multiple header editor will open.
2. Change the header order.
3. Click **OK**.

Create advanced headers

1. In the list of defined headers, select the desired header then click . The **Cell Fields Wizard** will open (see).
2. Set the desired header (see "Cell fields" on page 105).
3. Click **OK**.


Headers tab

Excel > CCH® Tagetik > Design > select form > Matrix > Headers

Purpose of the tab

This tab allows you to customise the row and column headers of the matrix using predefined headers in order to make it easier to read the data in the table.

What it looks like



Element	Description
A	Action buttons in all tabs. See Struttura finestre di configurazione.
B	Row headers section
C	Column headers section
D	List of available headers
E	Buttons specific to the tab
F	List of defined headers

Areas of row/column header sections

Element	Description
List of predefined headers	Displays the list of predefined headers, indicated by $\$\square$.
List of defined headers	Displays the list of defined headers. Every defined header presents the following information: • matrix row/column number on which the header is defined • text shown in the matrix headers

Buttons in tab

Element	Description
	Adds one or more selected predefined headers to the list of defined headers.
	Adds, through concatenation, one or more selected predefined headers to a header that has already been defined. In the matrix, such headers are shown as a concatenation.
	Only with headers already defined. Removes one or more selected headers from the list of defined headers.
	Only with headers already defined. Moves the selected header up one position.
	Only with headers already defined. Moves the selected header down one position.
	Only with headers already defined with a OR logical function. Allows you to remove or reorganise one or several headers of a group of concatenated headers with the OR logical function.
	Opens the Cell Fields Wizard. See "Cell Fields Wizard" on page 105.

Overrides

Introduction

The Matrix Wizard's *Override* tab allows you to create, at the matrix level, overrides on the dimensions included in the form by form filters and tab filters. In fact, restrictions defined by form filters and tab filters on certain dimensions can be *excluded* from the matrix, or elements of dimensions originally excluded by the form filters and tab filters can be *included* in the matrix (see "Structure of the data in the forms and filters" on page 96).

***Note**: for the override to include functions, the elements selected in the matrix's override tab must belong to the same hierarchy used to insert the elements overridden in the matrix.*

Example

This example describes a form containing a sheet with filters on entities *A00*, *B00* and *A01* and two matrices respectively showing:

- data for a given scenario selected by the user when the form was run
- data for the previous scenario

To compare the data for one scenario on entities A00, B00 and A01 with data for the previous scenario related to the entities node *EU-Europe* (parent node of entities A00, B00 and A01), overrides for the tab filters must be applied on the second matrix, so as to define the EU node as a matrix filter for the second matrix. To do this:

1. In the **Matrix Filters** tab, in hierarchy *X00 - Geographical area*, select the filter *EU-Europe*.
2. In the **Override** tab in the Matrix Wizard, select entity hierarchy *X00 - Geographical area* which contains all the entities grouped geographically.

   ***Note**: for the override to take effect, the hierarchy selected in the **Overrides** tab must be the same as the one in the initial matrix filter.*

Overrides on Analytical Information Hub matrices

As regards matrices based on both multidimensional and Line by Line transactional Analytical Information Hub datasets, the override system is simplified. It is not possible to define an override on individual hierarchies of a dimension, but only on the dimension itself.

The Override content on cells function

Overrides on formulas

In CCH Tagetik, it is possible to insert formulas into form cells, via the Matrix Wizard (see "Matrix Wizard - Window structure" on the facing page).

The *formula* filters are filters on matrix rows or columns which, while the form is being run, function like Excel formulas and make it possible to process data based on the data handled by the matrix itself.

For more details, see "Formula filters" on page 237.

In the Matrix Wizard, the formula is set on the entire row/column of the matrix. However, in some contexts, it is necessary to define specific formulas for specific cells. Some examples are provided below:

- It is necessary to refer to cells that belong to other matrices or other cells of the form.
- Formulas must have different behaviour for certain cells of the matrix (whereas standard formulas are defined on the matrix rows and/or columns).
- Different constant values must be assigned for every cell of the matrix.

To create formulas at the cell level, it is possible to use the *Override content* function, which allows you to insert an Excel formula directly into a cell in the area occupied by a matrix.

It is important to consider the following behaviours:

- Inserting ordinary Excel formulas means that, when the matrix is generated as the form is run, the formula will be overwritten with what is present in the matrix.
- The content of cells can only be overridden in static matrices.
- If the data resulting from the formulas needs to be saved in the database, the cells containing the formulas in the matrix must have editability set to **Editability protected**

To remove an override, right click on the cell to which the override is applied and select Tagetik > Remove "Override content"

Override Headers

The *Override content* functionality also allows you to override header-type content in a cell. This override can be run in the following ways:

- by using a dictionary item on the row/column of the Matrix Wizard
- by setting the override on the matrix headers

Setting up an override on matrix headers is useful, for example, for inserting content in the matrix's starting cell, or the first cell at the top-left, at the intersection between the first row and the first column of the matrix. In order for the text content inserted directly into this cell in Excel not to be removed as the matrix is regenerated when the form is run, it can be added via overrides.

Overriding cell content

Excel > CCH® Tagetik > Design > select form >

See Come accedere alle finestre for alternative paths.

Set a content override

1. In the work desktop, select the cell in the area of the matrix on which to override content
2. Insert the desired formula or value in the cell.
3. In the toolbar, click Σ **Override content**.

The system will change the format of the cell and show its value in red. In the **Open items** panel, the presence in the form of cells with overridden content is indicated by the element **Cells with overridden content**.

Remove a content override

In the work desktop, right click on the cell and select *Tagetik > Remove "Override content"*.

Setting overrides

Excel > CCH® Tagetik > Design > select form > Matrix > Overrides

See Come accedere alle finestre for alternative paths.

Exclude restrictions of form/tab filter on dimensions from the matrix

In the dimensions tree, select the filters on one or several dimensions known to be originally defined at the form/tab level. This allows you not to apply the restrictions set by the filters at the form/tab level to the matrix.

***Note**: to add elements of the dimension to the row/column filters and matrix filters, see "Set row/column filters" on page 230 and "Setting matrix filters" on page 226.*

Overrides tab

Excel > CCH® Tagetik > Design > select form > Matrix > Overrides

See Come accedere alle finestre for alternative paths.

Purpose of the tab

This tab shows the tree of dimensions included in the form and allows you to override the exclusion of the matrix from the form filters and tab filters action on one or several dimensions.

***Note**: once the matrix has been excluded from the restrictions on the dimensions set by the form filters and tab filters, it is possible to include dimensional elements of those dimensions in the row/column filters and matrix filters. For this to work, the form filter and selected overrides must belong to the same dimensions hierarchy.*

Matrix Wizard - Window structure

Excel > CCH® Tagetik > Design > select form > Matrix

Excel > CCH® Tagetik > Design > select form > right click the cell on the work desktop > Tagetik > New Matrix or Modify matrix

Excel > CCH® Tagetik > Design > select form > double click the cell of the matrix in the work desktop

Excel > CCH® Tagetik > Open items > right click the left-hand panel > Matrices > New Matrix

Purpose of window

The Matrix Wizard allows you to create, edit and manage matrices in forms.

What it looks like

The structure of the Matrix Wizard tabs mirrors the general structure of the Excel add-in windows. For more information, see Struttura finestre di configurazione.

Window tabs

Element	Description
Row/column filters	Allows you to define CCH Tagetik dimensions as filters in the matrix rows and columns. See "Row/column filters tab" on page 234.
Matrix Filters	Allows you to define filters on dimension data at the matrix level. See "Matrix Filters tab" on page 227.
Headers	Allows you to define a description for the matrix rows and columns to make them easier to read. See "Headers tab" on page 183.
Matrix options	Allows you to manage the following: • form formatting • how cells without values are saved in the database • how to dynamically open rows/columns • Break back options See "Matrix options tab" on page 206.
Overrides	Allows you to define overrides in the matrix. See "Overrides tab" on the previous page.
Transactional form editor	For transactional forms only. Allows you to define the layout of the form. See "Transactional form editor tab" on page 209.
Custom filters	Only for transactional forms based on Analytical Workspace datasets. Allows you to create custom filters on the measures of the dataset associated with the form.

Buttons in the window

Element	Description
	Undo the last action.
	Repeat the last action.
	Shows a list of the filters used.
	If the class attribute has been changed, it realigns the signs of the accounts on the class of which it has been applied.
	Allows the user to select the display mode for forms on the panel: with description only, with code only or with both description and code.
	Refresh the dimensions tree.

Display options

Element	Description
Double click the top border	Displays the window full screen/resizes the window if already being displayed full screen.

Dimensions tree in the Matrix Wizard

Introduction

In the Matrix Wizard, the **Row/column filters**, **Matrix filters**, **Overrides** and **Forms** tabs allow you to set filters on reporting data based on a dimensions tree.

Elements of the dimensions tree

Depending on the selected tab, the dimensions tree shows the following dimensions:

Tab	Description
Row/column filters	• system dimensions (scenario, period, account, control groups, entity, etc.) • custom dimensions (e.g. : products, cost centres, etc.) • specific reporting dimensions (e.g. period length), see "Specific dimensions for reporting" on page 93. • specific dimensions of some reporting functionalities (e.g. Column form and Counter, used in the management of transactional data entry forms) • predefined filters, see "Parameters" on page 136. • Wizard > Control groups, see I gruppi di controllo: concetti di base.
Matrix filters	• system dimensions (scenario, period, account, entity...) • custom dimensions (e.g. : products, cost centres, etc.) • specific reporting dimensions (e.g. period length), see "Parameters" on page 136.
Overrides	• system dimensions (scenario, period, account, entity...) • custom dimensions (e.g. : products, cost centres, etc.) • specific reporting dimensions (e.g. period length), see "Parameters" on page 136. • predefined filters, see "Parameters" on page 136. • Wizard > Control groups, see I gruppi di controllo: concetti di base.

Account dimension utility nodes

In the dimensions tree, the account hierarchy and following utility nodes, which allow you to quickly select several accounts at the same time, are shown by default for the account dimension.

Node	Description
Financial statement templates	Aggregation structure of the accounts or accounts/custom dimensions generally used to create financial statements (IAS profit and loss statements and balance sheets, management reports, direct/indirect financial reports), KPIs and other indices necessary for reporting. See "Financial statement templates" on page 161.
Control groups	Groups of accounts organised on the basis of balancing rules between accounts, variations that document how they change over time, or elements that allow the user to detail an account. See I gruppi di controllo: concetti di base.
$ - All Accounts	Default node that allows you to select one or several elements or nodes from the group of accounts
$-All Control Groups	Node that allows you to select one or several elements or nodes from the group of control groups.

Parameter-type elements

In the dimensions tree, for each dimension and hierarchy there is a *parameter* shown in blue in the dimensions tree, the name of which always starts with $ (e.g. $AZI_P for entity elements, $PER_P for period elements, etc.). This allows you to select the desired dimension by choosing from among the available elements deriving from the context and compatible with the relative user restrictions.

In addition to dimensional parameters, when defined, *system parameters* and *custom parameters* can be used as row/column filters or matrix filters.

For more details on parameters, see "Parameters" on page 136.

Display rules

The data displayed in the dimensions tree vary based on the following criteria:

- user rights on dimensions
- **Exclude from reporting** option active on some hierarchies or nodes of a group because they are only useful for configuration, otherwise they are obsolete

Click to refresh the dimensions tree immediately after the deployment of changes in the dimensions table.

Working in the properties table

Procedures for setting the values of properties

Depending on the property, it is possible to apply one of the following methods.

- Click and select the desired element from the drop-down menu (e.g. sign change definition).
- Click on the desired field and insert the value in the dedicated window (e.g. formula insertion).
- Click the row containing the property and then on to open the editor the guides the insertion of values (e.g. reference FX rates definition).

Table of row/column filter properties

Introduction

The properties table allows the user to manage the filter properties to customise the matrix. When several filters are selected, only the shared properties are shown and the values set on them will be applied to all the selected filters.

Reference FX rates

This property manages the FX rate when a different FX rate from the one specified in the table is needed, or if it must be read from a different scenario or period from those of the data to be converted.

The possible values are provided below:

Element	Description
average	Average FX rate of the period in which it is calculated. These are the FX rates generally used for P&L accounts.
period average	Applies a different FX rate for every period into which the year is divided. Allows the user to perform more accurate conversions than the average FX rate.
final	Period-end FX rates. These are used for the balance sheet accounts, with the exception of the equity accounts, which are typically converted at the historical FX rate.
based on account	FX rate used for conversions and defined in the accounts table

FX rate

Currency dimension properties.

Element	Description
For matrices on the financial layer	
From Configuration	Value, displayed in brackets next to the active property, previously configured in **Default FX rate** for the new filters on the currency in the **Forms** section of CCH Tagetik 's general settings. See Valuta..
None	The Currency dimension is used as a dimension filter: only records whose currency is the selected currency will be read by the database.
Final FX rate	The records read by the database are converted into the selected currency using the final FX rate, as defined in the FX rate table.
Average FX rate	The records read by the database are converted into the selected currency using the average FX rate, as defined in the FX rate table.

Element	Description
Period average FX rate	The records read by the database are converted into the selected currency using the period average FX rate, as defined in the FX rate table. The **FX rate** property of the Currency dimension, as well as the equivalent property in **Reference FX rates**, does not support the **Period average FX rate** option if the form uses the standard reporting engine. Where this configuration is used, at the run form step, this option is automatically set to **Based on account**. A warning is sent and the user must correct the form configuration.
Based on account	In the accounts table, it is possible to define the FX rate to be used in the various data processing to covert the relevant amounts (**Conversion** property, with the following possible values: **None**, **Final**, **Average** or **Period average**). With this setting, the form converts records read from the database into the selected currency, using the relative FX rate, as defined in the table, for each of them.
For matrices on the analytics layer	
None	The Currency dimension is used as a dimension filter: only records whose currency is the selected currency will be read by the database.
Based on the measure	The option to be applied is read from the numerical measure configuration in which it is possible to define the desired FX rate for that measure from the web interface. (See Dataset fields).
Based on account	With this setting, the form converts records read from the database into the selected currency, using the relative FX rate, as defined in the table, for each of them. If the account dimension is not present in the dataset, the **Based on the measure** FX rate is applied.

Particular features of conversion based on account

Conversion based on account is only applicable when the dataset has the account dimension. If the “based on account” conversion type is specified and the matrix does not have the account dimension, the form is not run. If the account has a conversion type that is not supported by the analytical matrices, i.e. it is not the average FX rate, period average FX rate or final FX rate, the **Based on the measure** FX rate type is applied.

Forms in which global filters (form filters or sheet filters) on the currency are used will have the following behaviours:

When...	Then...
the dataset does not contain the account dimension	if the matrix has no overrides on the currency dimension, the system considers the currency indicated in the global filter: • if the conversion type is **final**, **average**, or **period average**, the system applies the **Based on the measure** conversion type. • if the conversion type is **None**, then no filter is applied and only the values in the selected currency are read.
	of the matrix specifies an override on the Currency dimension, then the global filters are not applied.
the dataset contains the Account dimension	the **Based on Account** conversion type is applied, regardless of what is specified at the matrix level, save for matrix overrides.

Periodic value calculation

Period length dimension properties.

Element	Description
Automatic	The properties' behaviour varies based on the engine used for reporting. Default value. See Motori di reporting. ***Note**: option used when the Period length is not specified in any of the form's filters.*
Aggregation of periodic values	Calculates the cumulated data as the sum of periodic figures. For example, the quarterly figure for the second quarter is calculated as the sum of the monthly figures read from periods 4, 5 and 6.
Net Year-to-date values	Calculates the cumulated data as the net year-to-date values. For example, the quarterly figure for the second quarter is calculated as the difference between the *year to date* figure for period 6 and the *year to date* figure for period 3.

Sign change

This account dimension property allows you to change the sign with which the account is displayed. When active, this inverts the sign of the data.

***Note**: the elements for which the sign change is active are shown in red in the Matrix Wizard.*

Line by Line matrices do not support the native sign change relative to the account dimension unless additional filters on the account dimension are present (Form/Sheet/Matrix filters).

For multidimensional AIH matrices related to an AW dataset configured with data refresh mode set to **Refresh existing record**, the sign change is not present for text-based measures.

Complementary

This property allows you to exclude a specific filter or node from a node of filters in a hierarchy. Thus, the system displays the entire hierarchy of the filter's parent node or excluded node, except for the specific filter or node. This type of filter is recognisable from the **<NOT>** prefix.

***Note**: the additional filter works on the hierarchies but not groupings.*

Data Validation

This property allows the user to associated a validation query with the selected filter to limit their choice to a restricted set of elements.

Size

This property is not editable and indicates the dimension to which the selected element belongs.

Advanced selection

Element	Description
Allow new rows/columns wizard in data entry	Only for transactional forms with **Pruning** set to **To zero**. When active, in data entry it allows you to view and edit rows/columns that are open but not shown because they are empty. ***Note**: the effects of the changes are shown in the form automatically (e.g. changes on amounts).*
Additional rows to open	With the Counter dimension, it is possible to set the number of additional rows to be opened in transactional forms. Set this value in the **Additional rows to open** field in the **Advanced selection** attribute included in the counter properties in the matrix. (See Details of the Counter element). Can only be set if **Allow new rows/columns wizard in data entry** is set to "false".
Detail subtotal	Displays the subtotal for every dimension nested in the filter node. *In the presence of three or more nested dimensions, activate the option to prevent potential style application errors.*

Element	Description
Generate subtotals up to	Allows the user to define the starting node for calculating subtotals. • **Root**: generates subtotals based on the hierarchy root (default value). • **Starting node**: generates subtotals based on the selected intermediate node. ***Note**: this has no effect if the elements returned as the result of the Advanced Selection script do not belong to the starting node's sub-tree. See "Details of advanced selection scripts for calculating the default value" on page 141.*
Restrictions	The system allows you to insert in the table restrictions on dimensions of the row/column, primarily between entity/custom dimensions, in order to allow, in data entry, data to be read/written only on the relative custom dimensions specified in the table, to improve performance. This option allows you to override these restrictions on dynamic elements, in order to see the data without the restrictions set in the table. **Hierarchy Node Intersection**: by default, if a single dimension of the matrix has several hierarchies, the system presents the intersection of the two hierarchies, i.e. the data related to elements belonging to both hierarchies. By activating this option, the system shows all combinations of elements of both hierarchies. See Entity elements.
Pruning	Hides empty rows/columns. • **Not valued**: hides from the table rows/columns which are found to have no data in the database during the run form phase. The value zero is considered as data. • **To zero**: hides from the table rows/columns which are found to have no data in the database during the run form phase or have the value 0 entered. • **None**: shows all rows/columns.
Ranking	Defines the criteria for sorting data within the table. • **No rule**: sorts the row data based on the values of a reference column. • **Top elements**: brings the elements with the highest values to the top. • **Bottom elements** brings the elements with the lowest values to the top. • **Pareto analysis 80/20**: selects the minimum set of rows/columns with the highest value in the reference column and which make up a defined % of the column/rows total. By default, the **threshold** is 80%, but it can be changed. • **Only elements that are not zero**: removes from the display rows/columns with no value entered or with the value 0 in the reference column/row. • **Reference column/row**: selects the matrix column/row (depending on where the ranking property is being set) on which basis the data is to be sorted. • **Number of elements to display**: sets the maximum number of rows to display. • **Accept more elements than requested**: if there are several rows with the same value, all rows will be displayed. If disabled, the system chooses the rows at random, so that it displays the best rows while respecting the limit indicated in **Number of elements to display**. • **Sorting rule**: defines the row sorting criteria (**increasing**, **decreasing**, **none**).
Script	Allows the user to set a query on CCH Tagetik 's application database in the cell using a TGKML syntax, see Advanced selection script.

Element	Description
Subtotals	Only with dynamic filters. When the form is run, at every hierarchy level interruption, it displays the subtotal calculated on the lowest level elements. The subtotal therefore takes the name of the parent node of the lowest level elements on which the subtotal is calculated (for example: Europe is the name, and therefore the parent node, of the subtotal calculated on the lowest level elements Italy, France, Spain etc.). For more details on the general settings for subtotals, see "Matrix options tab" on page 206.
Selection type	Define which hierarchy levels to display. • **None** • **Insert all children**: only displays the child nodes of the selected filter. • **Insert lowest level elements**: displays all the lowest level elements present below the selected node, to the last level. • **Insert Parent**: displays the parent node of the selected filter. • **Advanced selection**: activates the "Script " on the previous page property. Allows the user to insert dynamic elements that cannot be inserted via standard selection. • **Insert analytical FST** : (with Account type elements inserted via items of an FST) allows the user to define an analytical FST in which both the FST items and the related accounts are displayed. For more details, see "Financial statement templates" on page 161. • **Insert synthetic FST**: (with Account type elements inserted via items of an FST) allows the user to define a synthetic FST in which only the FST items are displayed. For more details, see "Financial statement templates" on page 161. • **Control group**: (with Account type elements entered via control groups) allows the user to define the accounts with reference to a group.

Dictionary

Element	Description
	Allows the user to select an existing dictionary item. See "Dictionary Items window" on page 114.

Editability

Element	Description
Editable	Makes the filter editable.
Not editable	Makes the filter non-editable.
Protected	Makes the filter editable using the formula, the result of which is not directly editable by is saved in the database when the form is saved.
Unspecified	Default value.

Transactional form editor

Only for transactional forms with "**Use Transactional form editor** active.

Element	Description
Tab	Defines the editor tab in which to view the selected column filter. • **Excluded from the editor**: does not show the filter in any tab • **<tab>**: shows the filter in the selected tab
Column	Defines the column of the tab on which the column filter is shown (2 = second column of the tab).
Row	Defines the row of the tab on which the column filter is shown (2 = second row of the tab).
Filled columns	Defines the number of columns occupied by the filter.
Label space	Defines the dimension in percentage terms with which to show the column label in the editor.

Validation

Only for data entry forms. Allows you to set checks on the correctness of the data entered. See "Validations" on page 106.

Conditional editability expression

Only on editable parameters or parameters with protected editability. Allows you to subject the editability of the current filter to conditions and logical expressions in relation to other filters. See "Validations" on page 106.

Dividing factor

Account dimension properties. Not supported for matrices designed on the Analytical Workspace.

Element	Description
Day	Calculates the average of the amounts based on the number of days that have passed from the start of the year to the specific month, e.g. 180 days from January to June.
Period	Calculates the average of the amounts based on the number of days in the specific month, e.g. 30 days for the month of June.

Tagetik style

Only available if a Tagetik style is defined for the matrix.

Element	Description
	Opens the style selection window for the matrix elements. See "Tagetik styles " on page 118.

Formula

Element	Description
	Opens a window to write the calculation formula.
Prevailing	Makes the formula the prevailing formula in case of intersection with others.
Calculation logic type	• **Client**: the formula refers to dimensional elements contained in the matrix and is solved in the local client. • **Server**: the formula refers to elements of the dimensions present in other matrices or other elements of the form, the formula is solved on the server and the client receives the resulting value.

Hyperlink

Element	Description
Action list	Opens the **Action List Wizard** window to define the actions to be run when a hyperlink is selected. See "Action List Wizard window" on page 303.
Prevailing	Makes the link defined for the row/column prevail over any other hyperlinks on intersection rows/columns on the same matrix which, at runtime, could create more than one value on the same cell.
Values or Headers	Allows you to specify the part of the matrix on which the hyperlink can be inserted. • **Values and headers**: the link is available both on headers and on row/column values. • **Values**: the link is only available on row/column values. • **Headers**: the link is only available on row/column headers.

Multi-selection

Property only available from the web interface on row/column filters with counter dimension in transactional matrices of the Analytical Workspaces.

When active, this shows tick boxes for selecting multiple rows/columns when the form is run.

Hide

Element	Description
Do not hide in the presence of editable cells	Shows the hidden row/column in the presence of editable cells.
Hide row or column	
Always	Synthetically hides the row/column. In contrast to Excel's native functionality, this option also remains anchored to the element when the form is dynamic and the position can change.
Not defined	Hides the row/column without data.
To zero	Hides the row/column the amounts of which are zero.
chained to	Hides the row/column when this is subject to the display of another row/column that can in turn be hidden.
Ignore the cells that contain formulas	Only with **Undefined**/**To zero**. In the presence of cells containing formulas, the value of the cells resulting from the formula is not considered when the system assesses of whether or not to hide the row/column.
Ignore the matrix headers	Only with **Undefined**/**To zero**. Does not consider the content of the values in the matrix header areas in the decision of whether or not to hide the row/column. Enabled by default.
Do not consider cells that contain text	Only with **Undefined**/**To zero**. In the presence of cells containing non-numeric values (amount type, description, etc.), these are not considered when the system assesses whether or not to hide the row/column. ***Note**: when this option is disabled, the cells containing non-numeric values are considered non-empty cells with values other than 0.*
Also evaluate other matrices on the same row/column	Only with **Undefined**/**To zero**. In the presence of several matrices containing cells on the same row/column, this only hides the row/column if all the matrices allow it to be hidden. The outcome of this check is therefore applied to all matrices. Cells outside of the matrix are ignored.
Reference row	Only with **Chained to**. Allows you to select the row/column to which to subordinate the current row/column.

Segment

Properties of the entity and accounts dimension

Allows you to view intercompany data related to the entities of an entity node called a *segment*. This property's default value is defined in advanced form settings and used on all the tab filters set on entity dimensions, custom dimension 2 or the counterparty entity. This value can be overridden when designing the matrix.

Element	Description
from configuration	Reads and applies the values indicated in the application's general settings to the Default section of the Form tab. SeeSettings window.
none	Does not apply any filters to journals
Parent segment	The value shown includes all consolidation journals (IC eliminations, financial investment eliminations, other corrections) between legal entities belonging to the same "parent" node.
Segment	The value shown includes all consolidation journals (IC eliminations, financial investment eliminations, other corrections) between legal entities belonging to the same node.
Intersegment	Identifies the values relative to all journals referring to legal entities belonging to different segments. This function is activated ONLY if the selected node has at least TWO levels below it. Data can be read according to this method both when creating "Tab filters" and when selecting "Prompt Filter", respecting all the restrictions on the depth of the levels for the choice of "Intersegment".
Parent intersegment	Identifies the values relative to all journals referring to legal entities belonging to different segments and, starting from a level below, takes all the journals that start from the node on which the function is activated.

Data type

Element	Description
Date	Applies the date format to the row/column.
Number	Applies the number format to the row/column.
Body	Applies the text format to the row/column.
Default	Applies the data type defined in the cell properties.

Prevailing data type

When active, this makes the data type set on the cell predominant over the data type defined for the entire row/column.

Navigation

Only for parametric filters on the scenario dimension. See "Navigating scenario parameters" on page 151.

Element	Description
Previous	Selects the scenario indicated in the scenarios list as the *previous scenario* to the selected scenario. See "Navigating scenario parameters" on page 151.
Next	Selects the scenario indicated in the scenarios list as the *next scenario* following the selected scenario. See "Navigating scenario parameters" on page 151.
Reference	Selects the scenario indicated in the scenarios list as the selected scenario's *reference scenario*. See "Navigating scenario parameters" on page 151.

Period Difference

Only for parametric filters on the period dimension.

Allows the user to navigate periods, shifting forwards or backwards from the period selected when the form is run.

See "Navigating period parameters" on page 152.

Matrix filter properties table

Introduction

The properties table allows the user to manage the filter properties to customise the matrix. When several filters are selected, only the shared properties are shown and the values set on them will be applied to all the selected filters.

Reference FX rates

Element	Description
average	Average FX rate of the period in which it is calculated. These are the FX rates generally used for P&L accounts.
period average	Applies a different FX rate for every period into which the year is divided. Allows the user to perform more accurate conversions than the average FX rate.
final	Period-end FX rates. These are used for the balance sheet accounts, with the exception of the equity accounts, which are typically converted at the historical FX rate.
based on account	FX rate used for conversions and defined in the accounts table

FX rate

Currency dimension properties.

Element	Description
For matrices on the financial layer	
From Configuration	Value, displayed in brackets next to the active property, previously configured in **Default FX rate** for the new filters on the currency in the **Forms** section of CCH Tagetik 's general settings. See Valuta..
None	The Currency dimension is used as a dimension filter: only records whose currency is the selected currency will be read by the database.
Final FX rate	The records read by the database are converted into the selected currency using the final FX rate, as defined in the FX rate table.
Average FX rate	The records read by the database are converted into the selected currency using the average FX rate, as defined in the FX rate table.
Period average FX rate	The records read by the database are converted into the selected currency using the period average FX rate, as defined in the FX rate table. The **FX rate** property of the Currency dimension, as well as the equivalent property in **Reference FX rates**, does not support the **Period average FX rate** option if the form uses the standard reporting engine. Where this configuration is used, at the run form step, this option is automatically set to **Based on account**. A warning is sent and the user must correct the form configuration.
Based on account	In the accounts table, it is possible to define the FX rate to be used in the various data processing to covert the relevant amounts (**Conversion** property, with the following possible values: **None**, **Final**, **Average** or **Period average**). With this setting, the form converts records read from the database into the selected currency, using the relative FX rate, as defined in the table, for each of them.
For matrices on the analytics layer	
None	The Currency dimension is used as a dimension filter: only records whose currency is the selected currency will be read by the database.
Based on the measure	The option to be applied is read from the numerical measure configuration in which it is possible to define the desired FX rate for that measure from the web interface. (See Dataset fields).
Based on account	With this setting, the form converts records read from the database into the selected currency, using the relative FX rate, as defined in the table, for each of them. If the account dimension is not present in the dataset, the **Based on the measure** FX rate is applied.

Particular features of conversion based on account

Conversion based on account is only applicable when the dataset has the account dimension. If the "based on account" conversion type is specified and the matrix does not have the account dimension, the form is not run. If the account has a conversion type that is not supported by the analytical matrices, i.e. it is not the average FX rate, period average FX rate or final FX rate, the **Based on the measure** FX rate type is applied.

Forms in which global filters (form filters or sheet filters) on the currency are used will have the following behaviours:

When...	Then...
the dataset does not contain the account dimension	if the matrix has no overrides on the currency dimension, the system considers the currency indicated in the global filter: • if the conversion type is **final**, **average**, or **period average**, the system applies the **Based on the measure** conversion type. • if the conversion type is **None**, then no filter is applied and only the values in the selected currency are read.
	of the matrix specifies an override on the Currency dimension, then the global filters are not applied.
the dataset contains the Account dimension	the **Based on Account** conversion type is applied, regardless of what is specified at the matrix level, save for matrix overrides.

Periodic value calculation

Period length dimension properties.

Element	Description
Automatic	The properties' behaviour varies based on the engine used for reporting. Default value. See Motori di reporting. ***Note**: option used when the Period length is not specified in any of the form's filters.*
Aggregation of periodic values	Calculates the cumulated data as the sum of periodic figures. For example, the quarterly figure for the second quarter is calculated as the sum of the monthly figures read from periods 4, 5 and 6.
Net Year-to-date values	Calculates the cumulated data as the net year-to-date values. For example, the quarterly figure for the second quarter is calculated as the difference between the *year to date* figure for period 6 and the *year to date* figure for period 3.

Size

Specifies the dimension and group/hierarchy from which the filter has been taken. Not editable.

Navigation

Only for parametric filters on the scenario dimension. See "Navigating scenario parameters" on page 151.

Element	Description
Previous	Selects the scenario indicated in the scenarios list as the *previous scenario* to the selected scenario. See "Navigating scenario parameters" on page 151.
Next	Selects the scenario indicated in the scenarios list as the *next scenario* following the selected scenario. See "Navigating scenario parameters" on page 151.
Reference	Selects the scenario indicated in the scenarios list as the selected scenario's *reference scenario*. See "Navigating scenario parameters" on page 151.

Period Difference

Only for parametric filters on the period dimension.

Allows the user to navigate periods, shifting forwards or backwards from the period selected when the form is run.

See "Navigating period parameters" on page 152.

Details of FX rate properties

Description

This property allows you to convert the currency (of the entity or transaction) of every figure in the matrix into the selected currency, using the FX rate defined for the scenario/period in use. To do this, it is necessary to define an element of the Currency dimension (row/column filter, matrix filter, tab filter or form filter) and set its FX rate property with the FX rate to be used. This operation may be useful for comparing the turnover of entities with different currencies, for example.

Property details

Depending on the type of matrix, the FX rate property has several available options:

Matrix type	Options
Financial layer	• **From configuration**: default value, which appears between brackets. The FX rate is determined by the **Default FX rate for the new filters on the currency** parameter in the general form settings in CCH Tagetik*Setup & Admin > Settings > Forms tab > Default section). Navbar > Settings > Forms tab > Default section)* See Settings window. • **None**: only reads records with the selected currency from the database. • **Final FX rate**: the records read by the database are converted into the selected currency using the final FX rate, as defined in the FX rate table. • **Average FX rate**: the records read by the database are converted into the selected currency using the average FX rate, as defined in the FX rate table. • **Period average FX rate**: the records read by the database are converted into the selected currency using the period average FX rate, as defined in the FX rate table. **Based on account**: in the accounts table, it is possible to define the FX rate to be used in the various types of data processing to covert the amounts (see Anagrafica conto). With this setting, the form converts records read from the database into the selected currency, using the relative FX rate, as defined in the table, for each of them. ***Note**: The FX rate property of the Currency dimension (as well as the equivalent property in Reference FX rates) does not support the **Period average FX rate** option if the form uses the standard reporting engine. In this case, when the form is run, the system changes this option, setting it to **Based on account**. The user receives a message inviting them to correct the form's configuration.*
Analytical layer	**None**: the Currency dimension is used as a dimension filter. Only records whose currency is the selected currency will be read by the database.
	Based on the measure: the option to be applied is read from the numeric measure. The desired FX rate for measures can be defined from the web interface. See Dataset fields
	Based on account: with this setting, the form converts records read from the database into the selected currency, using the relative FX rate, as defined in the table, for each of them. If the account dimension is not present on the dataset, the **Based on the measure** behaviour will be applied.

Matrices on multiple workspaces

If a sheet contains both a matrix on a financial workspace and a matrix on an analytical workspace, when a currency filter is applied to several matrices, such as a tab filter or form filter, the available options are the same as for the financial workspace. In order for the filter options to be also applied to the multidimensional matrix of the analytical workspace, the global filter options are converted as follows:

- none -> none
- final FX rate, average FX rate, period average FX rate, based on account -> based on measure

For more details on the logics that regulate these conversions, see Algoritmo di conversione valutaria.

Details of Reference FX rate properties

Description

By default, the system converts the amounts in the form using the FX rate defined in the table for the scenario/period applied to the cell containing the data (the FX rate type is defined on the row/column filter properties, or on the matrix filter, tab filter or form filter).

To define a different FX rate from the one in the table, it is possible to edit the reference FX rate property and set FX rate type of the scenario/period in use or another scenario/period. Data for a scenario/period can be used after being converted with different FX rates, for a "what if" type analysis.

> ### Example
>
> To carry out a comparison of the data of an account on the scenarios *2011 Actual* and *2012 Actual*, it is possible to calculate the value of the *2012 Actual* data "as if" it were subject to the *2011 Actual* FX rate. To do this, when managing the *2012 Actual* properties, *2011 Actual* and the FX rate type to be applied are selected as the reference FX rate.

For details on FX rate types, see "Reference FX rates" on page 190.

Details of Periodic value calculation properties

Description

This property allows you to specify the calculation method according to which CCH Tagetik transforms periodic figures into cumulated progressive figures.

Calculation options

The available calculation options are described in detail in "Periodic value calculation" on page 191.

Calculation options syntax: standard or in-memory reporting engine

Details of the calculation syntax of the periodic value in relation to the various reporting engines:

<table>
<tr><th>Element</th><th>Description</th></tr>
<tr><td>Standard reporting engine</td><td>The system identifies the process from the scenario/period pair of the figure to be converted and, based on the FX rate specified on the process, defines the calculation method for the periodic value and the relative algorithm.

<table>
<tr><th>If...</th><th>Then the periodic value is calculated as...</th></tr>
<tr><td>the process is set to Average FX rate</td><td rowspan="2">Net Year-to-date values</td></tr>
<tr><td>the scenario/period is not related to any process</td></tr>
<tr><td>the process is set to Period average FX rate</td><td>Aggregation of periodic values</td></tr>
</table>

IMPORTANT: if a single scenario includes periods belonging to processes with different FX rate configurations, in the presence of cumulated period lengths, the standard reporting engine may return incorrect results.

For more details on the FX rate calculation algorithm, see Algoritmo di conversione valutaria.</td></tr>
<tr><td>In-memory engine</td><td>The system identifies the FX rate to be applied to the individual cell and defines the periodic figure calculation method, regardless of where this has been derived overridden in the form, from the account or the process.

<table>
<tr><th>If...</th><th>Then the periodic value is calculated using the method:</th></tr>
<tr><td>the process is set to Final FX rate or Average FX rate</td><td>Net Year-to-date values</td></tr>
<tr><td>the process is set to Period average FX rate</td><td rowspan="4">Aggregation of periodic values</td></tr>
<tr><td>the process is set to Based on account</td></tr>
<tr><td>non conversion is applied and Periodic value calculation is set to Automatic</td></tr>
<tr><td>the period length is indicated as a form filter or tab filter, and the multidimensional matrix on the Analytical Workspace is influenced by this filter</td></tr>
</table>
</td></tr>
</table>

***Note**: the **Automatic** option is applied when the period length is not specified in the form.*

Tagetik style property details

Description

This property allows you to define a style on the selected row/column filter. When a style is set, the way in which it is applied to the filters will depend on the level of the tree of the sections of the matrix in which it is set. In fact, the style will be applied starting with the highest level of the tree. In other words, the sections

belonging to a given level of the tree inherit those of the higher levels, unless another style has explicitly been defined for them.

This property is only visible in the presence of a Tagetik style defined for the matrix.

By default, when the form is run, the style set on the last level of filters, or the style set on an intermediate filter that is then propagated on the last level, is applied.


In the presence of subtotals generated at runtime, these only inherit the style if they are subtotals of the last level and no style has been set on that level.

Specific features of scenario and period parameter properties

Using parameters

All parameters present in Tagetik (both system parameters and custom parameters) can be used within the Matrix Wizard to make the matrices dynamic.

In Tagetik, there is a parameter for every dimension and hierarchy. Parameters can be selected from the dimensions tree and are distinguished from the other elements by the colour blue. Both shared parameters and ad-hoc parameters can be chosen in the dimensions tree.



Once a parameter from the dimensions tree has been chosen, it can be inserted into the matrix as a row filter, a column filter or a matrix filter. Once inserted into a matrix, a parameter behaves the same way as a fixed value. They can also be nested into other elements and the properties that can be modified in the properties table are the same as for a fixed value (non-parametric) element.

For dynamic scenario and period parameter elements, there are additional properties that are activated in the properties table when inserted in the matrix as row filters or column filters. We will look at these properties in the next sections.

The dimensions tree used to define the Form, Tab and Matrix filters does not show Process-type parameters or dimensional parameters on the period that allow 'OR' operations, as these are not supported by the forms.


Navigating scenario parameters

Navigating scenarios allows the user to create dynamic forms for comparing data saved in the system in different scenarios. When scenarios are defined in Tagetik, temporal links and comparative links can be created between them.

For example, if I defined a scenario called 2012ACTUAL, which collects actual data for the year 2012, I could create a "Previous" type link to scenario 2011ACTUAL and in turn create a "Next" type link between scenario 2011ACT and 2012ACT.

In addition to temporal relationships, comparative relationships between different scenarios can also be defined. For example, a scenario called 2012BDG, which is a forecast for the year 2012, must be compared with the actual data for that year, e.g. 2012ACT. In Tagetik, up to 5 reference-type relationships between scenarios can be defined.

These chains of scenarios can be used within the Tagetik reporting client when scenario-type parameters are selected. When a scenario-type parameter is inserted in a row or column filter, the "Navigation" property is activated in the properties table.




In this window, we need to define the navigation chain for our scenario. Navigation starts from the element chosen by the user when the form is run. For example, if a user chooses scenario 2012ACT and a "Previous" navigation has been defined, scenario 2011ACT will be used.


Scenarios are navigated by choosing an element from the list and clicking the button. The element can be removed using the button. The order of the various scenarios can be changed using the and buttons. Several elements can be inserted to create navigation chains, e.g. the Previous --> Previous scenario or the Previous --> Reference #1 scenario.

The order in which the elements are added to the list is very important as the system navigates the scenarios according to the order in which they are added.


Let's look at an example in which a dynamic matrix is created to compare two actual data scenarios. First, we need to insert a parametric scenario within our matrix. This element will be the element chosen by the user, so we will not set any navigation for the element.



At this point, we must insert the second scenario, which will be the comparison scenario. In this column, we want to see the data for the scenario before the one selected by the user. So let's insert a parameter with the same code as the one inserted previously and set the navigation for the element.



Once navigation has been set for a parameter, the text in the filter window is changed to indicate which chain has been set.



At this point, the dynamic matrix is ready and can be used. Navigation chains between scenarios can be changed within the web interface without having to change the structure of the created form.

Navigating period parameters

The mechanism for navigating between period-type parameters is similar to navigating between scenarios. Offsets related to the parameter chosen as the filter can be defined between dynamic periods.


For example, I want to define a column which, depending on the chosen period, shows me data relative to 6 months earlier. If i choose period 12, the column will be defined with period 6, if I choose period 11, it will be defined with period 5, and so on.

A parameter of this type can be set using the "**Period Difference**" property present in the attributes table when we insert a period-type parametric element in a row or column filter. When we set a period difference, we must set the number of periods back or forward that we want to shift in relation to the chosen period. If the difference is greater than the number of periods in a scenario, the system obtains the periods from the scenario set as the previous or next scenario.

La navigazione del periodo non è totalmente supportata nell'AW, in particolare il sistema non ricava correttamente il valore della dimensione Scenario se, a causa dello scostamento maggiore del numero di periodi, è necessario usare lo scenario impostato come precedente o successivo. Questo si riscontra:

- nell'editabilità delle matrici multidimensionali
- nell'editabilità delle matrici LBL (Line By Line)
- nei dati estratti dalle matrici LBL (Line By Line)

Differences can be inserted directly within properties or using the scroll bar shown when properties are opened. The chosen difference is shown in the title of the edited parameter within the row or column filter.



Search window

Excel > CCH® Tagetik > Open items > double click matrix > Row/column filters or Matrix filters >

Purpose of window

This window allows you to search for elements using textual criteria, in the table of the dimensions of the environment that can be used in forms.

Options in window

Element	Description
Search bar	Allows you to insert the text to search for among the filter codes and/or descriptions. ***Note**: the text can contain the special characters "?" and "*".*
Type	Limits the search • **Code** • **Description** • **Code and description**
Regular Expression	Enables the search for regular expressions.
Case sensitive	Enables distinction between uppercase/lowercase.
Results display area	Displays the search results and allows you to select them to identify them in the dimensions tree.

Choose the dataset window

***IMPORTANT**: this window is only shown if the system used Analytical Workspaces and if at least one dataset has been set on them.*

Purpose of window

This window allows you to choose the dataset on which to define the matrix. The system shows the default Financial Workspace dataset and the list of all the available datasets for Analytical Workspaces. Once the dataset has been selected, the Matrix Wizard will open, showing the data of the dataset in the filter setting tabs (see "Matrix Wizard - Window structure" on page 187).

Options in window

Element	Description
Line item management	This makes the matrix transactional and allows you to create a Line by Line transactional form. See "Form matrices" on page 178.

Matrix options tab

Excel > CCH® Tagetik > Design > select form > Matrix > Matrix options

See Come accedere alle finestre for alternative paths.

Purpose of the tab

This tab allows you to manage the following:

- form formatting in areas of the matrix
- how empty matrix cells are saved in the database
- how to dynamically open rows/columns
- Break back options

Sub-tabs

Element	Description
Layout options	Allows you to do the following: • matrix formatting • matrix subtotal display mode • dynamic matrix display mode • how matrix row and column data are saved in the database
Calculation options	Allows you to manage elements related to optimisations and how matrix data are saved in the database.
Edit amounts	Allows you to manage the opening of new rows in data entry mode, for transactional forms.
Form - Break Back	Allows you to manage break back mode at the matrix level.

Note: *Calculation options, Edit Amounts, Form - Break Back are not support on transactional forms or multidimensional Analytical Workspaces.*

Options in the Layout options tab

Element	Description
Code	Allows you to edit the matrix code.
Formatting type	Allows you to enable/disable the use of Tagetik styles. See "Tagetik styles " on page 118. • **None**: the matrix is formatted using Excel's formatting functionalities. • **Apply Tagetik style**: the matrix is formatted using the Tagetik style associated with the form.
Subtotals	Allows you to manage the subtotal display mode in dynamic matrices. • **Subtotal before the detail**: shows the subtotal value after the total and before the lowest level elements. • **Deploy the lowest elements then the nodes of the same level**: in the presence of nodes to which both child nodes and elements of a dimension are related, this allows you to manage the order in which the form rows are generated. • **Group subtotals**: groups subtotals using Excel's group functionality. When enabled, every node and their children are grouped into an Excel level. ***Note****: transactional forms do not support the management of subtotals.*
Matrix	Allows you to change the matrix display mode in navigation and data entry. • **Do not repeat duplicate information on every row/column**: in the presence of dimensions nested on rows/columns, this allows you to prevent the description of those dimensions from being repeated in every row/column header, so it is only shown on rows where one of the nested dimensions changes. • **Show zero values if the cells aren't defined**: manages how empty cells are displayed. ◦ **Not defined**: items for which no value exists in the database are shown as empty cells in the form, ◦ **To zero**: items not defined are saved in the database and shown in the form with value 0. ***Note****: When this second option is used in combination with the form option "**Enable Save zero values**", the system saves a 0 in the database for every cell left empty when the form is submitted.* • **Allow matrix splitting**: no longer in use but present for compatibility with the client's previous versions. • **Show Documentation link**: allows you to create hyperlinks to web pages, to insert additional information on elements of dimensions. The links can only be configured in the web interface. The inserted link is shown in navigation and data entry modes inside the row/column header. ***Note****: transactional forms do not support the management of links.*

Element	Description
Rows and columns	This allows you to configure the way in which the dynamic matrix expands when the form is opened in navigation or data entry mode. • (Not enabled for transactional forms and Multidimensional Analytical Workspaces)**Maximum Number of Rows/Columns**: defines the maximum number of rows and columns that the system creates when it generates a dynamic matrix (**0**: unlimited). • **Row/column expansion mode**: allows you to configure way in which the rows or columns of a dynamic matrix can be generated ◦ **Shift cells down/right**: creates cells by moving existing cells for rows down and moving existing cells for columns to the right. ◦ **Entire row/column**: adds a row/column to the sheet. ◦ **Don't expand**: disables row/column expansion. • **Autofit columns**: allows you to set the column width. ◦ **None**: the column width is not adapted to the content. ◦ **From template**: the column width corresponds to the width set in the form design. ◦ **By value**: the column width adjusts to its content.
Row/column behaviour preview area	Shows the row/column expansion mode.

Options in the Calculation options tab

Element	Description
Enable overriding	• No longer in use but present for compatibility with the client's previous versions.
Save the original data and currency data separately	Allows you to save the original data and the currency data separately. By default, the system converts original currency data according to the scenario/period FX rate, then saves the result over the original data in the entity currency.
Exclude from evaluation of zero value sheets	Allows you to exclude a matrix from pruning (see "Pruning" on page 193). By default, with form filters with *pruning* set to *not defined/to zero* and matrices in the template with values of the same filters to zero/not defined, the system hides the sheet when the form is run.
Keep the IC amount in synch with the Gross amount	
Active	Automatically updates the gross figure every time the intercompany data are edited (e.g., if the gross figure is 100 and the intercompany figure is changed from 70 to 80, increasing it by 10, the system saves the gross figure as 110).
Not active	Does not update the gross figure every time the intercompany data are edited (e.g., if the gross figure is 100 and the intercompany figure is changed from 70 to 80, the system leaves the gross figure as 100).
Unspecified	The save mode is determined by the value of **Copy intercompany to gross amounts** in the advanced settings of the data entry rules configuration (*Setup & Administration > Data Entry & Submission Rules* > Amount & Intercompany rules) (*Navigation Panel > Processes & Workflows* > Amount & Intercompany rules). See "Data entry rules" on page 3.
Hints database	
Enable	Enables the use of database hints in queries run when the form is run.
Enable calculation on data	Enables the use of database hints in queries run when the form is run based on the content of the data tables.
Disable	Disables the use of database hints in queries run when the form is run.
Automatically	The system automatically activates/deactivates the use of database hints in queries run when the form is run.
Use optimization in report data entry	
Yes	When set to Yes, the matrix loading is optimized for calculating editability in the financial workspace, allowing for more efficient handling of high cardinality of accounts (or account/category combinations), and improving performance when dealing with thousands of accounts.
No	When set to No, the matrix loading is not optimized for calculating editability.
From configuration	When set to 'From configuration', the optimisation options are determined by the value "Use optimization in report data entry" in the System Settings window, under the Form -> Data Entry tab.

Options in the Edit amounts tab

Element	Description
"Instead of asking the user for a filter, automatically open the first one available"	(Only valid in forms that contain dynamic nodes with the advanced selection option **Allow new rows/columns wizard in data entry** enabled) When the user clicks on +, a new row/column opens on the first available element of the filter.
In the case of transactional forms, ask how many rows or columns to open	In a transactional form in which the **Allow new rows/columns wizard in data entry** option is enabled on the advanced selection options of the Counter dimension, it allows the following behaviour: • If active, and the form is run in data entry mode, when the user clicks +, it allows new rows to be opened manually. • If not active, when the form is run in data entry mode, the system opens a fixed number of rows specified on the attribute of the **Additional rows to open** matrix counter.
Enable Editability On Demand	(Only visible with transactional matrices) When the form is run in data entry mode, the cell editability calculation is not performed at the start, but afterwards, when the cell is clicked. See Editabilità onDemand.

Options in the Form - Break Back tab

Allows you to override break back mode on the matrix.

Element	Description
Break back dimensions	• **Default**: applies the break back mode specified in the data entry rules related to the process. • **break back deactivated**: deactivates break back, so the form's cells which correspond to a node are not editable. • **targets**: enables break back on custom dimensions only.
Save on the reference element	With the break back functionality active, indicates whether, in the data entry step from a form, the values inserted on the nodes must always be attributed to the reference lowest element. • **Default**: applies the break back mode specified in the data entry rules related to the process. • **Yes**: the values inserted on the nodes are attributed to the reference lowest element. • **No**: when the values that are inserted on the node can be distributed over lowest level elements related to the same node in proportion to the old value, they are automatically attributed to the nodes' reference lowest element.

Transactional form editor tab

Excel > CCH® Tagetik > Design > open form > Matrix > Transactional form editor

See Come accedere alle finestre for alternative paths.

***IMPORTANT**: this tab is only shown for transactional forms, when at least one element has been added to the local column filters tree in the Row/column filters tab.*

Purpose of the tab

This window allows you to define the characteristics of the detailed data entry window of transactional forms. In particular, it allows you to manage the following:

- Define the window's tabs, give them labels and set the number of rows and columns.
- Enable buttons to manage the form's rows in the data entry phase.
- Define the dimensions in terms of details window pixels.

The data entry window thus defined allows you to run data entry much more flexibly.

Once the characteristics of the details window have been defined from this tab, the user must define the tab of the window in which every column filter should be shown, and the column and row by setting the **Transactional form editor** column property (see "Table of row/column filter properties" on page 190).

Layout management options

Element	Description
Use Transactional form editor	Enable data entry management via the detail window.
Show buttons	
Add	In the data entry step, this shows the button on the row, allowing you to add a row below the selected row.
Edit	In the data entry step, this shows the button on the row, which opens a detail window to edit the data on the row. See Finestra di dettaglio data entry transazionale.
Delete	In the data entry step, this shows the button on the row, allowing you to delete the selected row.
Editor dimensions	
Width	Allows you to define the width in pixels of the detailed data entry window.
Height	Allows you to define the height in pixels of the detailed data entry window.

Layout management buttons

Element	Description
Add tab	Allows you to create a new tab in the window, define its label and number of rows/columns.
Remove tab	Removes the selected tab.
Rename tab	Renames the selected tab.
Preview	Shows a preview of the detail window. See "Preview window" below.

Tab management tabs

Element	Description
Rows	Defines the number of rows of the detail window.
Columns	Defines the number of columns of the detail window.

Preview window

Excel > CCH® Tagetik > Design > open form > Matrix > Transactional form editor > Preview

See Come accedere alle finestre for alternative paths.

Purpose of window

This window allows you to view a preview of the final layout of the detailed data entry window of transactional forms (see "Transactional form editor tab" on the previous page).

Structure and definition of an advanced selection script

An advanced selection script:

- starts with the key word "**TGKML 1.0**";
- can contain one or more instructions. Each instruction ends with the character "**;**" and assigns a given content to a variance. This content can be:
  - a string of text;
  - a number;
  - one or more logic functions or operations. This instructions can contain any previously defined classifier;
  - the element of a dimension or node;
  - a set of values (text, numeric or dimension elements)

The syntax of an instruction is:

variable_name := content;

The number of instructions that can be defined in a script is unlimited. All the classifiers are "local" and therefore they can be referred only within the same script. The name of a classifier cannot correspond to the name of the objects belonging to the script language (for example, the dimensions name, the functions name, ...).

The script syntax is not sensitive to the upper-case letters, therefore it is not possible to define two classifiers whose names differ only for one upper-case or lower-case letter.

- it can contain one or more comments identified by the symbol **//** at the beginning of the row. The characters that follow the symbol // up to the end of the row are ignored. The possible comments can be inserted in any point of the script
- only one classifier is used by the system to get the result of the script. This classifier is predefined in the script and is named **result**. This classifier is mandatory and no other classifier can be defined below. The content of this classifier must be of dimensional type.

Dynamic matrices

What they are

In matrices, it is always possible to change certain properties of filter nodes to make them dynamic. Thus, it is possible to take account of how the composition of the nodes changes over time without having to edit them in the matrix. These matrices have a variable row and column structure, which is calculated at runtime when the form is run. The system recovers the indicated node, considering all elements contained within it when the form is run.
For example, in a matrix with an account of the sales of products over the month, creating a dynamic matrix allows you to retrieve, when the form is run, dimensional data on the desired products and period without having to define them manually as filters in the matrix.

It is also possible to set only some of a matrix's elements as dynamic, even if they belong to the same dimension.


***IMPORTANT**: in dynamic matrices, elements inserted as dynamic row/column filters have Insert lowest level elements as their default selection type on creation. This setting can be changed.*

Selection type

This property allows you to define the dynamic element that must be shown depending on the various levels of the selected hierarchy.

Example

This example shows a hierarchy on the entity dimension that groups entities by geographical area, where the subsidiaries are lowest level elements (leaf elements) while regions are aggregations of elements (node elements).



Dynamic forms can be constructed to see several entities based on the selected node. If the node inserted as a row filter is *Europe*, the following results are obtained based on the selected selection type:

Advanced selection	Outcome
Insert Parent	At runtime, the parent node of the element indicated as the filter is inserted, so the matrix only shows the row corresponding to the node of the *WORLD* hierarchy containing the total of all nodes below it. 2012 Budget Dec Budget View - All Entities 3.306.274.160
Insert children	At runtime, all the rows corresponding to the child nodes of the node indicated as the filter are inserted, so the matrix only shows the rows corresponding to the *South Europe and North Europe* nodes, containing the relative subtotals. 2012 Budget Dec South Europe 75.976.479 Central Europe 59.611.203

Advanced selection	Outcome
Insert lowest level elements	At runtime, all the lowest level elements of the node indicated as the filter are inserted, so the matrix shows the rows corresponding to the lowest level elements, and therefore *Distribution Rome, Distribution Milan, Distribution Barcelona, Distribution Madrid, Distribution Berlin, Distribution Paris and Distribution Munich.* 

***IMPORTANT**: If advanced selection is applied to a hierarchy of time-dependent elements, the scenario and period must be determined unambiguously. The scenario and period elements must therefore be inserted either in the matrix, in the filters themselves (row or column) but above the dynamic elements, or in the form filters.*

Creating matrices

Introduction

Setting up matrices means creating a structure in which to define the data managed by the form. Once that structure has been created, it is necessary to define the database data that must be managed by the matrix. To do this, it is therefore necessary to set *filters* on the database data at several configuration levels. Matrix filters define which data are shown in a specific matrix. Form filters and tab filters are applied to all matrices present in the individual form or sheet, respectively. This module shows how to create matrix elements. For more details, see "Matrix filters" on page 226.

Define the matrix starting cell

Before creating a matrix, it is necessary to select a cell in the work desktop of the spreadsheet that will become the first cell at the top-left of the matrix table.

***IMPORTANT**: Do not select cell A1 of the work desktop to allow any information on the form to be displayed at runtime. Choose the starting cell in such a way that the created matrix never overlaps with other matrices, especially in the presence of dynamic matrices: overlapping could cause errors and lead to data being incorrectly displayed.*

The matrix can always be moved inside the template.

Create/modify a matrix with Financial Workspace data

Excel > CCH® Tagetik > Design > select form > Matrix

See Come accedere alle finestre for alternative paths.

1. In the **Choose the dataset** window, click **$CPM-Financial Workspace**.
2. Click **OK**.

Once the matrix has been created, the system assigns a default name (e.g. Matrix00, Matrix01...), which can be edited in the matrix wizard by the **Matrix options** tab in the **Code** field.

Create/modify a matrix with Analytical Workspace data

***IMPORTANT**: only with the Analytical workspaces module active and at least one workspace configured and online. Offline linked Analytical Workspace forms will not be accessible in either data entry or navigation mode.*

Excel > CCH® Tagetik > Design > select form > Matrix

See Come accedere alle finestre for alternative paths.

1. In the **Choose the dataset** window, click the desired dataset.
2. (Only if an Analytical Workspaces dataset is selected) To create a transactional matrix, click **Transactional**.
3. Click **OK**.

Once the matrix has been created, the system assigns a default name (e.g. Matrix00, Matrix01...), which can be edited in the matrix wizard by the **Matrix options** tab in the **Code** field.

Create a data entry matrix for the user

Excel > CCH® Tagetik > Design > open form > open or create matrix > Row/column filters

For a matrix to be a data entry matrix, some of its cells must be made available for data entry for the user, i.e. they must be made editable. To do this, once the desired matrix has been created, do the following:

1. In the **Row/column filters** tab, set the desired row/column filters (see "Set a filter on rows/columns" on page 230).
2. Select the row/column filter to be made editable and, in the filter properties table, set the filter's editability property to **Editability**.

***IMPORTANT**: matrices whose fields, with **Protected** editability, are fed by formulas or queries that calculate an overall figure based on the reading of data existing in the database, are not considered data entry matrices. For more details, see "Formula filters" on page 237 and Query.*

Managing matrices

Open a matrix to edit it

Excel > CCH® Tagetik > Design > select form > double click the cell of the matrix in the work desktop

See Come accedere alle finestre for alternative paths.

To edit a matrix recalled via a link, edit the source matrix directly. See "Create a link to a matrix" on the facing page.

Create a copy of a matrix

Excel > CCH® Tagetik > Open items

See Come accedere alle finestre for alternative paths.

This procedure describes how to create a matrix with attributes similar to those of an existing matrix, by creating a copy of the existing matrix. A matrix can also be copied to several templates or forms. After a matrix has been created, it can be edited.

1. In the left-hand panel, select the matrix to be copied, then click .
2. In the work desktop, select the development cell of the new matrix and click .
3. Enter the name of the new matrix.
4. Click **OK**.

Create a link to a matrix

Excel > CCH® Tagetik > Open items > select matrix

See Come accedere alle finestre for alternative paths.

In Excel, it is possible to create links to existing matrices in other forms or another template of the same form.

1. Click .
2. In the work desktop, select the development cell of the new matrix.
3. Click .
4. Enter the name of the matrix called up.

   ***Note**: the matrix recalled via the link cannot be opened in design mode or edited. To edit that matrix, the source matrix must be edited.*

Change the position of a matrix

Excel > CCH® Tagetik > Open items

See Come accedere alle finestre for alternative paths.

1. Select the desired matrix. In the work desktop, the system shows the matrix in a box.
2. Position the cursor on one of the box borders and, when it becomes , drag the matrix to the desired position.

Delete a matrix

There are several ways to delete matrices.

Excel > CCH® Tagetik > Design > select form > right click a cell of a matrix on the work desktop > Tagetik > Delete matrix

Excel > CCH® Tagetik > Open items > select matrix > right click > Matrices > Delete matrix

Excel > CCH® Tagetik > Open items > select matrix >

***Note**: deleting a matrix recalled via a link will not delete the source matrix. However, when the source matrix is deleted, the recalled matrix will also be deleted and marked as . The form containing it becomes invalid.*

Design: filters

Contents

This section covers the following topics:

Form filters ... 216
Form filters window ... 217
Form filter properties ... 218
Setting form filters ... 218
Tab filters ... 219
Setting tab filters ... 219
Tab filters window ... 220
Tab filter properties ... 222
Tab filter properties table ... 223
Matrix filters ... 226
Setting matrix filters ... 226
Matrix filter properties ... 227
Matrix Filters tab ... 227
Row/column filters ... 229
Set row/column filters ... 230
Row/column filter properties ... 231
Row/column filters tab ... 234
Examples of row/column filter settings ... 236
Formula filters ... 237
Managing formulas ... 240
Predefined filters ... 240
Working with predefined filters ... 241
Examples of predefined filter settings ... 242
Custom filters ... 243
Custom filters tab ... 244
The Print Filters function ... 245
Print Filters Wizard ... 245
Print Filters examples ... 246
Generate a filters printout ... 248
List of filters used window ... 249

Form filters

What they are for

Form filters define the data displayed for all form template matrices. It is therefore useful to define a form filter when there are several matrices and the data to be shown in the form refer to a specific element of a dimension. For example, if the form only displays data related to the *Original* amount type, it is useful to define the *Original* amount type as a form filter.


Form filters window

Excel > CCH® Tagetik > Design > select form/create new form > Form filters

Purpose of window

This window allows you to set filters on forms. These filters are elements and/or nodes of the dimensions tree that are added and modified in the form filters definition area and determine the data managed in the form.

What it looks like



Element	Description
A	Action buttons in all windows. See Struttura finestre di configurazione.
B	Dimensions tree
C	Buttons specific to the window
D	Form filters definition area
E	Table of properties of the selected element in the definition area

Window sections

Element	Description
Dimensions tree	Show the list of available dimensions. • system dimensions (scenario, period, account, entity...) • custom dimensions (customisable, up to a maximum of 5. E.g. products, cost centres...) • specific reporting dimensions (e.g. period length)
Form filters definition area	Show the list of filters currently set on the form.
Properties table	Allows you to manage the editable attributes of the selected dimension or filter.

Buttons in window

Element	Description
	Adds one or several elements or nodes selected in the dimensions tree to the form filters definition area.
	Only with filters with the OR function already defined. Allows you to remove one or more elements from filters defined as OR.
	Removes the selected filter.

Properties table

Element	Description
	Expands a set of details which change a filter property.
	Expands the list of possible values for the property.
	Opens the property configuration window.

For details of the possible options in relation to properties, see "Form filter properties" below.

Form filter properties

List of form filter properties

***Note**: the list of properties displayed varies depending on the type of dimension used as the filter.*

Element	Description
FX rate	For details on this property, see "Details of FX rate properties" on page 199.
Reference FX rates	Allows you to indicate a different FX rate from the one defined in the table, for the entity for the scenario/period in use, to be used in the form navigation step.
Complementary	This allows the user to exclude a specific filter or node from a node of filters in a hierarchy. Thus, the system displays the entire hierarchy of the filter's parent node or excluded node, except for the specific filter or node. ***Note**: the additional filter is identified by the prefix <NOT> and works on hierarchies but not groupings.*
Size	Indicates the dimension to which the selected element belongs. Non-editable property.
Dimension (node/lowest level element)	Indicates whether the filter is a node or a lowest level element.
Dividing factor	Allows you to set the factor for the calculation of the average amount for a defined number of days or by period.
Periodic value calculation	Allows you to define the calculation of cumulated data as the sum of period figures (e.g. the quarterly figure for the second quarter is calculated as the sum of the monthly figures read from periods 4, 5 and 6), or as the net year-to-date values (e.g. if the *period length* is *monthly*, the quarterly figure for the second quarter is calculated as the difference between the values for period 6 and the values for period 3).
Comparison condition	It allows the user to define a condition for comparison, or an operator and a value with which to compare the filter value.

Setting form filters

Excel > CCH® Tagetik > Design > select form/create new form > Form filters

Set a form filter

1. In the dimensions tree, select one or more elements of the desired dimension to be used as filters, then click next to the definition area, or drag them into the area: details of the reference dimension and the dimension elements will appear in the definition area.
2. Set the filter properties as desired.
3. Repeat the previous step to add other elements to the dimension or create filters related to other dimensions.

Tab filters

What they are for

Tab filters have an effect on all matrices included in the template. It is useful to define a tab filter when you want to manage several dimension elements of the same type and view one sheet per element in the form. For example, to view data for entities *A00*, *A01*, *A02*, if these entities are set as tab filters, the form will display one sheet for each entity.

The generated sheets are named as defined in the *Generate sheet names according to* setting in the general form options (see "Generate sheet names according to" on page 135).

Tab filters on forms with several templates

In forms with several templates, several tab filters can be set for each template. When the form is run, the system creates a copy of the template for every tab filter set. For example, in a form with the templates *PL - Profit & Loss* and *BS - Balance Sheet*, applying the tab filters on entities *A00*, *A01*, *B00* for *PL - Profit & Loss* and applying the tab filters on nodes *X04*, *X05* and *X06* (of hierarchy *X00-Departments* defined on the cost centre custom dimension) to *BS - Balance Sheet*, will mean that the system generates a form with 6 sheets.

Tab filters with formulas

It is possible to create tab filters containing formulas. The system creates a sheet containing the result of the formula.
As is the case for any other formula, it is possible to define a dictionary item to show a description for the sheet containing the values. When several sheets are shown in one template, it may be useful to create a sheet containing totals or statistics on data managed in the other sheets. To do this, a formula can be set as a tab filter argument.

> **Example**
>
> In a form with tab filters on entities A00, A01 and B00, by creating a fourth filter with the formula {1} + {2} + {3}, when the form is run the system will display the three sheets with entity filters and a fourth sheet containing the total of the amounts of the three entity sheets.

Setting tab filters

Excel > CCH® Tagetik > Design > select form/create new form > Tab filters

Set a tab filter

1. In the dimensions tree, select one or more of the dimension's elements to be used as tab filters, then click next to the definition area, or drag them into the area: details of the reference dimension and the dimension elements will appear below the node.
2. Set the filter properties as desired.

3. Repeat the previous step to add dimension elements or nodes from other dimensions.

   ***Note**: when the form is run, the system assigns a name to each sheet, following the rules established in the form options; see "Form options window" on page 133.*


Tab filters window

Excel > CCH® Tagetik > Design > select form/create new form > Tab filters

Purpose of window

This window allows you to set filters applied to the form to subdivide data into separate sheets. These filters are elements and/or nodes of the dimensions tree that are added and modified in the local filters tree and determine the number of sheets in the report and the data shown in each of them.

What it looks like



Element	Description
A	Action buttons in all windows. See Configuration window structure.
B	Dimensions tree
C	Buttons specific to the window
D	Tab filters definition area
E	Table of properties of the selected element in the definition area

Window sections

Element	Description
Dimensions tree	Show the list of available dimensions. • system dimensions (scenario, period, account, entity...) • custom dimensions (products, cost centres...) • specific reporting dimensions (e.g. period length)
Tab filters definition area	Show the list of filters currently set.
Properties table	Allows you to manage the editable attributes of the selected dimension or filter.

Buttons in the window

Element	Description
	Adds one or several elements or nodes selected in the dimensions tree under the selected node in the filters tree.
	Only with filters already defined, adds one or several elements or nodes selected in the dimensions tree to all filters already defined. ***Note**: if there are no pre-defined filters in the column, it functions like the*  *button.*
	Adds one or several filters selected in the dimensions tree to a selected filter, creating a OR type logical relationship. OR type logical relationships can only be created with elements or nodes belonging to the same dimension as the filters already defined. The added filter is labelled with the concatenation of the individual element codes separated by ",". The value displayed is equal to the sum of the elements entered.
	Adds one or several elements selected in the dimensions tree belonging to the same filter dimension to a node of filters linked by an OR logical relationship. The added filter is labelled with the concatenation of the individual element codes separated by ",". The value displayed is equal to the sum of the elements entered.
	(Only for control groups) Adds the control group selected in the dimensions tree to the filter. See I gruppi di controllo: concetti di base.
	(Only for control groups) Adds the control group selected in the dimensions tree to all filters already defined. See I gruppi di controllo: concetti di base.
	(Only for FST items) Analytically adds, under the selected filter, the FST selected in the dimensions tree. See "Financial statement templates" on page 161.
	(Only for FST items) Analytically adds, under all filters, the FST selected in the dimensions tree. See "Financial statement templates" on page 161.
	(Only for FST items) Synthetically enters the FST under the currently selected filter. See "Financial statement templates" on page 161.
	(Only for FST items) Synthetically adds, under all filters, the FST selected in the dimensions tree. See "Financial statement templates" on page 161.
	Adds a sheet on which a logical formula can be inserted. See "Formula filters" on page 237.
	Allows you to create a new template.
	Pastes the copied filters under the selected filter.
	Pastes the copied filters under every filter.
	Allows you to copy the structure of a filter.
	Only with filters already defined. Moves the selected element up one position.
	Only with filters already defined. Moves the selected element down one position.
	Only with filters already defined on several levels. Moves the selected level up one level.

Element	Description
	Only with filters already defined. Replaces en bloc the selected elements of a filter with elements selected in the dimensions tree. Useful for reusing a filter by replacing its elements, but not its properties.
	Only with filters already defined in the rows/columns with an OR logical relationship. Deletes one or several elements from the filter containing the OR logical relationship.
	Only with filters already defined. Deletes the selected element or node.
	Only with filters already defined. Deletes the entire level of the selected filter.

Properties table

Element	Description
	Expands a set of details which change a filter property.
	Expands the list of possible values for the property.
	Opens the property configuration window.

For details of the possible options in relation to properties, see "Row/column filter properties" on page 231.

Filter colour legend

Only for account dimensions.

Element	Description
	• Green: the sign is the same as the dimension class sign. • Orange: the sign has been changed automatically based on its class. See "Sign class" on page 180. • Red: the sign has been changed in the filter properties. See "Sign change" on page 192.

Tab filter properties

List of tab filter properties

***Note**: the list of properties displayed varies depending on the type of dimension used as the filter.*

Element	Description
Reference FX rates	Allows you to indicate a different FX rate from the one defined in the table, for the entity for the scenario/period in use, to be used in the form navigation step.
Sign change	This allows the user to change the sign in which the account is displayed. If the sign of a filter included in a formula changes, the formula will automatically account for the sign change.
Complementary	This allows the user to exclude a specific filter or node from a node of filters in a hierarchy. Thus, the system displays the entire hierarchy of the filter's parent node or excluded node, except for the specific filter or node. ***Note**: the additional filter is identified by the prefix <NOT> and works on hierarchies but not groupings.*
Size	Indicates the dimension to which the selected element belongs. Non-editable property.
Dividing factor	Allows you to set the factor for the calculation of the average amount for a defined number of days or by period.
Dictionary	Allows the user to associate dictionary items in the languages enabled in the environment with rows. When the form is run, instead of the description, the sheet name shows the dictionary item translated into the user's language. For more details, see "Dictionaries" on page 112.

Element	Description
Advanced selection	This allows the user to define a set of elements that the system must dynamically recover when running the form. For more details, see "Dynamic matrices" on page 211.
Navigation	Only visible if a parametric filter on the Scenario dimension has been selected. Allows the user to set criteria for navigating between scenarios (previous, next and reference). For more details, see "Navigating scenario parameters" on page 151.
Period Difference	Only visible if a parametric filter on the Period dimension has been selected. Allows the user to set criteria for navigating between periods. For more details, see "Navigating period parameters" on page 152.
Formula	Allows you to define elements calculated as formulas within the sheet. For more details, see "Formula filters" on page 237.
Hide	Allows you to hide sheets when the form is run.
Segment	Allows you to view intercompany data related to the entities of an entity node called a *segment*. This property's default value is defined in advanced form settings (see Settings window) and used on all the tab filters set on entity dimensions, custom dimension 2 or the counterparty entity. This value can be overridden when designing the form.

Tab filter properties table

Description

This table shows certain properties, the number and type of which depend on the selected filter or filters. The name and value are shown for every property. The properties needed for standard tab filter functionality are defined with a default value. Properties which refer to the same aspect of the setup and represent the details thereof are grouped below a main item identified with the icon.

If several filters are selected at the same time, the table will only show the shared properties and it will be possible to define the same property for all the selected filters with a single action.

Reference FX rates

Element	Description
average	Average FX rate of the period in which it is calculated. These are the FX rates generally used for P&L accounts.
period average	Applies a different FX rate for every period into which the year is divided. Allows the user to perform more accurate conversions than the average FX rate.
final	Period-end FX rates. These are used for the balance sheet accounts, with the exception of the equity accounts, which are typically converted at the historical FX rate.
based on account	FX rate used for conversions and defined in the accounts table

Sign change

Account dimension properties. When active, this inverts the sign of the data.

Complementary

When active, this excludes a filter or node from the node of filters containing it. The value shown is the total value of the parent node excluding the filter or node on which the property is active

Size

Not editable. Indicates the dimension to which the selected element belongs.

Advanced selection

Element	Description
Detail subtotal	Displays the subtotal for every dimension nested in the filter node.  *In the presence of three or more nested dimensions, activate the option to prevent potential style application errors.*
Generate subtotals up to	Allows the user to define the starting node for calculating subtotals. • **Root**: generates subtotals based on the hierarchy root (default value). • **Starting node**: generates subtotals based on the selected intermediate node. ***Note**: this has no effect if the elements returned as the result of the Advanced Selection script do not belong to the starting node's sub-tree. See "Details of advanced selection scripts for calculating the default value" on page 141.*
Restrictions	The system allows you to insert in the table restrictions on dimensions of the sheet, primarily between entity/custom dimensions, in order to allow, in data entry, data to be read/written only on the relative custom dimensions specified in the table, to improve performance. This option allows you to override these restrictions on dynamic elements, in order to see the data without the restrictions set in the table. **Hierarchy Node Intersection**: by default, if a single dimension of the matrix has several hierarchies, the system presents the intersection of the two hierarchies, i.e. the data related to elements belonging to both hierarchies. By activating this option, the system shows all combinations of elements of both hierarchies. See Entity elements.
Pruning	Hides empty rows/columns. • **Not valued**: hides from the table rows/columns which are found to have no data in the database during the run form phase. The value zero is considered as data. • **To zero**: hides from the table rows/columns which are found to have no data in the database during the run form phase or have the value 0 entered. • **None**: shows all rows/columns.
Script	Allows the user to set a query on CCH Tagetik 's application database in the cell using a TGKML syntax, see Advanced selection script.
Subtotals	Only with dynamic filters. When the form is run, at every hierarchy level interruption, it displays the subtotal calculated on the lowest level elements. The subtotal therefore takes the name of the parent node of the lowest level elements on which the subtotal is calculated (for example: Europe is the name, and therefore the parent node, of the subtotal calculated on the lowest level elements Italy, France, Spain etc.). For more details on the general settings for subtotals, see "Matrix options tab" on page 206.
Selection type	Define which hierarchy levels to display. • **None** • **Insert all children**: only displays the child nodes of the selected filter. • **Insert lowest level elements**: displays all the lowest level elements present below the selected node, to the last level. • **Insert Parent**: displays the parent node of the selected filter. • **Advanced selection**: activates the "Script " above property. Allows the user to insert dynamic elements that cannot be inserted via standard selection. • **Insert analytical FST** : (with Account type elements inserted via items of an FST) allows the user to define an analytical FST in which both the FST items and the related accounts are displayed. For more details, see "Financial statement templates" on page 161. • **Insert synthetic FST**: (with Account type elements inserted via items of an FST) allows the user to define a synthetic FST in which only the FST items are displayed. For more details, see "Financial statement templates" on page 161. • **Control group**: (with Account type elements entered via control groups) allows the user to define the accounts with reference to a group.

Dictionary

Element	Description
	Allows the user to select an existing dictionary item. See "Dictionary Items window" on page 114.

Formula

Element	Description
	Opens a window to write the calculation formula.
Prevailing	Makes the formula the prevailing formula in case of intersection with others.
Calculation logic type	• **Client**: the formula refers to dimension elements contained in the tab filter and is solved in the local client. • **Server**: the formula refers to elements of the dimensions present in other sheets or other elements of the form, the formula is solved on the server and the client receives the resulting value.

Hide

Element	Description
Never	In this case, the sheet is displayed when the form is run.
Always	In this case, the sheet is hidden when the form is run.

Segment

Properties of the entity and accounts dimension

Element	Description
(from configuration)	Reads and applies the values indicated in the application's general settings to the Default section of the Form tab. See Settings window.
None	Does not apply any filters to journals
Per Segment parent	The value shown includes all consolidation journals (IC eliminations, financial investment eliminations, other corrections) for all nodes or legal entities belonging to the same "parent" node.
By segment	The value shown includes all consolidation journals (IC eliminations, financial investment eliminations, other corrections) between legal entities belonging to the same node.
Intersegment	Identifies the values relative to all journals referring to legal entities belonging to different segments. This function is activated ONLY if the selected node has at least TWO levels below it. Data can be read according to this method both when creating "Tab filters" and when selecting "Prompt Filter", respecting all the restrictions on the depth of the levels for the choice of "Intersegment".
Per Intersegment Parent	Identifies the values relative to all journals referring to legal entities belonging to different segments and, starting from a level below, takes all the journals that start from the node on which the function is activated.

Navigation

Only for parametric filters on the scenario dimension. See "Navigating scenario parameters" on page 151.

Element	Description
Previous	Selects the scenario indicated in the scenarios list as the *previous scenario* to the selected scenario. See "Navigating scenario parameters" on page 151.
Next	Selects the scenario indicated in the scenarios list as the *next scenario* following the selected scenario. See "Navigating scenario parameters" on page 151.
Reference	Selects the scenario indicated in the scenarios list as the selected scenario's *reference scenario*. See "Navigating scenario parameters" on page 151.

Period Difference

Only for parametric filters on the period dimension.

Allows the user to navigate periods, shifting forwards or backwards from the period selected when the form is run.

See "Navigating period parameters" on page 152.

Matrix filters

What they are for

The data that the matrix manages are defined using row/column filters. When a logic that groups the data to be set on row/column filters can be identified, then the data can be filtered at the global level on the matrix, by defining *matrix filters*. For example, if the matrix needs to manage data of a single entity only, it is useful to set the entity filter on the entire matrix. Thus, without the need to apply the filter to every row/column in the matrix, when the form is run it shows, for the entire matrix, only data related to the entity indicated in the matrix filter.

Setting matrix filters

Excel > CCH® Tagetik > Design > select form/create new form > Matrix > Matrix Filters

Introduction

Setting matrix filters means managing filters that have an effect on the whole matrix, not just on certain rows/columns. It is possible to define filters made up of individual dimensions and filters with more complex structures.

Set a filter

1. In the dimensions tree, select one or more elements to be used as a filter, then click next to the matrix filters definition area, or drag them into the area. Details of the reference dimension and the selected dimension elements will appear in the definition area.
2. Set the filter properties as desired (see "Matrix filter properties" on the facing page).
3. Repeat the previous step to add elements of the same dimension or create filters related to other dimensions.

Add a dimension element to a filter

1. In the dimensions tree, select the desired dimension element and click : the element will be added to the elements node relative to the dimension to which it belongs.
2. Set the filter properties as desired.

Customise a filter

In the filters definition area, click on the desired filter and change its properties in the properties table (see "Matrix filter properties table" on page 197).

Matrix filter properties

List of matrix filters

Element	Description
Complementary	This allows the user to exclude a specific filter or node from a node of filters in a hierarchy. Thus, the system displays the entire hierarchy of the filter's parent node or excluded node, except for the specific filter or node. ***Note**: the additional filter is identified by the prefix <NOT> and works on hierarchies but not groupings.*
Comparison condition	It allows the user to define a condition for comparison, or an operator and a value with which to compare the filter value. *To specify an individual element of the filter to be compared, use the operator "=". To exclude one of them, use the operator "<>".* *For example: with operator "=" and value "INPUT_DEFORM" on an Origin type filter, the user can obtain the sum of all the figures with origin "INPUT_DEFORM".*
Reference FX rates	This allows the user to define a different FX rate from that which is specified in the table, i.e. whether it needs to be read from a scenario or period other than those of the data to be converted. See "Details of Reference FX rate properties" on page 200.
FX rate	Allows the user to view the entity or transaction amounts in a different currency. See "Details of FX rate properties" on page 199.
Periodic value calculation	Allows the user to specify the calculation method for the periodic value. The calculation methods vary depending on the reporting engine used (see "Form options window" on page 133).
Size	Indicates the dimension to which the selected element belongs. Non-editable property.
Navigation	Only visible if a parametric filter on the Scenario dimension has been selected. Allows the user to set criteria for navigating between scenarios (previous, next and reference). For more details, see "Navigating scenario parameters" on page 151.
Period Difference	Only visible if a parametric filter on the Period dimension has been selected. Allows the user to set criteria for navigating between periods. For more details, see "Navigating period parameters" on page 152.


Matrix Filters tab

Excel > CCH® Tagetik > Design > select form/create new form > Matrix > Matrix Filters

Purpose of the tab

This tab allows you to define filters on dimensions that are valid over the entire matrix.

What it looks like



Element	Description
A	Action buttons in all tabs. See Struttura finestre di configurazione.
B	Dimensions tree
C	Buttons specific to the tab
D	Matrix filters definition area
E	Table of properties of the selected element in the definition area

Tab sections

Element	Description
Dimensions tree	Show the list of available dimensions. • system dimensions (scenario, period, account, entity...) • custom dimensions (custom dimensions: e.g. products, cost centres...) • specific reporting dimensions (e.g. period length)
Matrix filters definition area	Show the list of filters set on the matrix.
Properties table	Allows you to manage the editable attributes of the selected dimension or filter.

Buttons in tab

Element	Description
	Adds one or several elements or nodes selected in the dimensions tree to the matrix filters definition area.
	Only with filters with the OR function already defined. Removes one or more elements from filters defined as OR clauses. This button is only activated when matrix filters with the OR logical relationship have already been defined.
	Removes the selected filter.

Properties table

Element	Description
	Expands a set of details which change a filter property.
	Expands the list of possible values for the property.
	Opens the property configuration window.

For details of the possible options in relation to properties, see "Matrix filter properties" on page 227.

Row/column filters

Introduction

To define the content of the matrix, filters must be set on the rows, columns and potentially the entire matrix. In particular, in order to define a filter, select elements of the dimensions, said dimension elements and any aggregation structures the user wants to view or process the data of.

Specific features of filters on account dimensions

For the account dimension, the definition of filters can be simplified using *financial statement templates* or *control groups* (see "Financial statement templates" on page 161 and I gruppi di controllo: concetti di base).

A financial statement template (FST) is a structure used to aggregate accounts or custom accounts/dimensions that can represent financial statements (IAS profit and loss statements and balance sheets, management reports, direct/indirect financial reports), KPIs and other indices for reporting. A financial statement template can be added to a matrix in its entirety or in part as a filter to be able to design its structure more quickly and efficiently.

Similarly, when the structure of a control group conforms to the specifics of the form, it can be added as a filter so all the accounts contained in it are added to the form.

For more information, see "Financial statement templates" on page 161 and I gruppi di controllo: concetti di base.

Row/column filter properties

When a filter is selected, the properties table displays all the properties of the filter with the relative values. Mandatory properties are set automatically to the default value. The user can edit filter properties to adapt the matrix configuration to their own business needs.

Depending on the type of property, the user can choose an option from among pre-set values, or enter formulas, dictionary items and so on.

When a row/column filter is added to an account dimension, the system changes the sign depending on the class assigned to the account (see "Sign class" on page 180).

For details of filter/column properties, see "Table of row/column filter properties" on page 190.

Placeholder elements

To add empty rows/columns to the matrix, elements called *placeholders* can be added between row/column filters. The purpose of these elements is to add empty rows/columns directly into the matrix structure and regulate the layout of the form. In fact, any empty rows/columns added manually in Excel are overwritten when the form structure is changed.

Formulas

To add formulas to cells of the matrix, *formula*-type elements can be added between row/column filters. The purpose of these elements is to add formulas directly into the matrix structure. Any formulas added manually in Excel are overwritten when the form structure is changed.

Formulas can be used to insert a row total or a variance between two columns. For example, in a matrix with costs on the rows and two scenarios on the columns, it is possible to view in runtime an additional row containing the total costs for the two scenarios and the annual variance, calculated as the difference

between the totals for the two scenarios. To obtain this result, a dedicated formula between the column filters must be prepared.

Set row/column filters

Excel > CCH® Tagetik > Design > open form > open or create matrix > Row/column filters

Introduction

Setting row/column filters means defining what data will be shown in the matrix's rows/columns. It is possible to define filters made up of individual dimensions and filters with more complex structures.

Set a filter on rows/columns

This procedure explains how to define filters on rows. Proceed in the same way to define column filters.

1. In the dimensions tree, select an element or node of the desired dimension to be used as a filter for the rows, then click next to the local filters on the rows, or drag it directly into the rows section. The filter will appear below the **Rows** node.
2. Set the filter properties as desired (see "Row/column filter properties" on the facing page).
3. Repeat the previous steps to add dimension elements or nodes from other dimensions.

Customise a filter

In the local row/column filters tree, click on the desired filter and edit its properties in the properties table (see "Matrix filter properties table" on page 197).

Create OR filters in the local row/column filters tree

This procedure explains how to create a filter containing several elements of a hierarchy of dimension elements directly in the row/column filters tree, by linking them to a cumulative relationship. To create such a filter, the OR function must be used ( ). At runtime, that hierarchy is run in the matrix just like any other node. The procedure to be followed is:

1. In the desired local filters tree, select the Rows (or columns) parent node.
2. In the dimensions tree, select the desired dimension elements and click . The elements are added on the same level.

Add OR values to an existing filter

1. In the filters tree, select the desired filter.
2. In the dimensions tree, select the desired dimension elements and click . The elements are added on the same level.

Add a placeholder

Click the row/column filter that will precede the placeholder, then click . The placeholder will appear below the selected filter.

Add a formula

1. Click on the row/column filter or on the placeholder that will precede the formula, then click . The formula placeholder will appear below the selected filter and the formula editor will open.
2. Select the desired options for the formula and enter the text of the formula. For instructions on how to write formulas, see "Formula filters" on page 237.

To view a list of the pre-existing filters on rows/columns and select the desired ones, position the cursor in the formula writing area and right click.

3. Click **OK**.

Row/column filter properties

List of row/column filters

The row/column filters are listed below.

Element	Description
Reference FX rates	This allows the user to define a different FX rate from that which is specified in the table, i.e. whether it needs to be read from a scenario or period other than those of the data to be converted. See "Details of Reference FX rate properties" on page 200.
FX rate	Allows the user to view the entity or transaction amounts in a different currency. See "Details of FX rate properties" on page 199.
Sign change	This allows the user to change the sign in which the account is displayed. If the sign of a filter included in a formula changes, the formula will automatically account for the sign change.
Periodic value calculation	Allows the user to specify the calculation method for the periodic value. The calculation method varies depending on the reporting engine used (see "Form options window" on page 133).
Complementary	This allows the user to exclude a specific filter or node from a node of filters in a hierarchy. Thus, the system displays the entire hierarchy of the filter's parent node or excluded node, except for the specific filter or node. ***Note**: the additional filter is identified by the prefix <NOT> and works on hierarchies but not groupings.*
Comparison condition	It allows the user to define a condition for comparison, or an operator and a value with which to compare the filter value. *To specify an individual element of the filter to be compared, use the operator "=". To exclude one of them, use the operator "<>".* *For example: with operator "=" and value "INPUT_DEFORM" on an Origin type filter, the user can obtain the sum of all the figures with origin "INPUT_DEFORM".*

Element	Description
Data Validation	Only with validation queries set in the form. Associates a validation query with the selected element to limit the user's choice to a restricted set of elements. ***Note:*** in the presence of Dictionary and Validation Query insisting on the same textual measure, the drop-down shows all values in the validation query as a suggestion; if data validation is active, only those values belonging to the Dictionary are saved. An exception is made if the 'Out of dictionary values allowed' flag has been enabled on the measure.
Size	Indicates the dimension to which the selected element belongs. Non-editable property.
Advanced selection	This allows the user to define a set of elements that the system must dynamically recover when running the form. For more details, see "Dynamic matrices" on page 211.
Dictionary	Allows the user to associate dictionary items in the languages enabled in the environment with rows. When the form is run, instead of the description, the sheet name shows the dictionary item translated into the user's language. For more details, see "Dictionaries" on page 112.
Editability	Allows you to define row/column editability. For more details, see "Cell editability" on page 156.
Validation check	Allows you to define accuracy checks on data entered via the Validation Checks Wizard. For more details, see "Validations" on page 106.
Conditional editability expression	Allows you to subject the editability set on the row/column to one or several conditions that depend on the content of other rows/columns of the current matrix. For more details, see "Validations" on page 106.
Division factor	Allows you to calculate the average of a value at a certain date, according to the following calculation methods. • *day*: the average is calculated on the basis of the number of days from the start of the year to the specific month, e.g. 180 days from January to June. • *period*: the average is calculated on the basis of the number of days in the specific month, e.g. 30 days for June. ***Note****: this functionality is not supported for matrices designed on Analytical Workspace.*
Tagetik style	Allows you to define a style for the selected row/column filter. See "Tagetik style property details" on page 201.

Element	Description
Formula	Allows you to define elements calculated as formulas on the row/column. For more details, see "Formula filters" on page 237.
Hyperlink	Allows you to define links between forms. For more details, see "Hyperlinks" on page 298.
Multi-selection	Property only available from the web interface on row/column filters with counter dimension in transactional matrices of the Analytical Workspaces. Allows you to see check boxes for multiple selection, in Navigation and Data Entry and for every row/column.
Less	Allows you to hide rows/columns when the form is run. In particular, it allows you to: • create specific layouts for each output sheet • create useful rows/columns linked to matrix formulas • hide superfluous rows/columns in specific contexts in which the form is used ***Note**: in data entry, rows/columns cannot be hidden if they contain at least one editable cell.*
Segment	Allows you to view intercompany data of the entities of a chosen node of entities, called a *segment*. This property's default value is defined in advanced form settings (see Finestra Impostazioni) and is used on all the row/column filters on which the segment is set on entity dimensions, custom dimension 2 or the counterparty entity. This value can be overridden during design or when editing the matrix from the properties table. ***Note**: matrices designed on Analytical Workspace do not support this property.*
Data type	Allows the user to define the row/column data type (string, date, numerical, etc.) to optimise how it is displayed in the run form phase.
Prevailing data type	Allows the user to choose, for an individual cell, a different data type from the one defined for the row/column.
Navigation	Only visible if a parametric filter on the Scenario dimension has been selected. Allows the user to set criteria for navigating between scenarios (previous, next and reference). For more details, see "Navigating scenario parameters" on page 151.
Period Difference	Only visible if a parametric filter on the Period dimension has been selected. Allows the user to set criteria for navigating between periods. For more details, see "Navigating period parameters" on page 152.


Row/column filters tab

Excel > CCH® Tagetik > Design > open form > open or create matrix > Row/column filters

Purpose of the tab

This tab allows you to set filters on the rows and columns of the matrix. These filters are elements and/or nodes of the dimensions tree that are added and modified in the local row/column filters tree and determine the selection of data managed in the rows and columns.

What it looks like



Element	Description
A	Action buttons in all tabs. See Struttura finestre di configurazione.
B	Dimensions tree
C	Buttons specific to the tab
D	Local row filters tree
E	Local column filters tree
F	Table of properties of the selected element in the definition area

Tab sections

Element	Description
Dimensions tree	Show the list of available dimensions. • system dimensions (scenario, period, account, entity...) • custom dimensions (e.g. "Products", "Cost centres" ...) • specific reporting dimensions (e.g. period length) • specific dimensions of some reporting functionalities (e.g. Column form, Counter and Status, used in the management of transactional data entry forms)
Local row filters tree	Shows the list of filters set on rows.
Local column filters tree	Shows the list of filters set on columns.
Properties table	Allows you to manage the editable attributes of the selected dimension or filter.

Buttons in the tab

Element	Description
	Adds one or several elements or nodes selected in the dimensions tree under the selected node in the filters tree.
	Only with filters already defined, adds one or several elements or nodes selected in the dimensions tree to all filters already defined. ***Note**: if there are no pre-defined filters in the column, it functions like the*  *button.*
	Adds one or several filters selected in the dimensions tree, creating a OR type logical relationship. OR logical relationships can only be created with elements or nodes belonging to the same dimension. The added filter is labelled with the concatenation of the individual element codes separated by ",". The value displayed is equal to the sum of the elements entered.
	Adds one or several filters selected in the dimensions tree to a selected existing filter, creating a OR type logical relationship. The added filter is labelled with the concatenation of the codes of the individual existing and added elements, separated by ",". The value displayed is equal to the sum of the elements entered.
	Adds the control group selected in the dimensions tree to a filter in the rows/columns.
	Adds the control group selected in the dimensions tree to all filters already defined.
	Analytically adds, under the selected filter, the FST selected in the dimensions tree. See .
	Analytically adds, under all filters, the FST selected in the dimensions tree.
	Synthetically enters the FST under the currently selected filter.
	Synthetically adds, under all filters, the FST selected in the dimensions tree.
	Save a filter as predefined. The new filter is then added to the dimensions tree. See "Predefined filters" on page 240.
	Update a predefined filter. The new filter is then added to the dimensions tree. See "Predefined filters" on page 240.
	Add an empty placeholder element.
	Adds a placeholder on which a logical formula can be inserted. See "Formula filters" on page 237.
	Pastes the copied filters under the selected filter.
	Pastes the copied filters under every filter.
	Allows you to copy the structure of a filter.
	Only with filters already defined. Moves the selected element up one position.

Element	Description
	Only with filters already defined. Moves the selected element down one position.
	Only with filters at several levels already defined in the row/column columns. Moves the selected level up one position.
	Only with filters already defined. Inverts the row filters and column filters.
	Only with filters already defined. Replaces en bloc the selected elements of a filter with elements selected in the dimensions tree. Useful for reusing a filter by replacing its elements, but not its properties.
	Only with filters already defined in the rows/columns with an OR logical relationship. Deletes one or several elements from the filter containing the OR logical relationship.
	Only with filters already defined. Deletes the selected element or node.
	Only with filters already defined. Deletes the entire level of the selected filter.

Properties table

Element	Description
	Expands a set of details which change a filter property.
	Expands the list of possible values for the property.
	Opens the property configuration window.

For details of the possible options in relation to properties, see "Row/column filter properties" on page 231.

Filter colour legend

Only for account dimensions.

Element	Description
	• Green: the sign is the same as the dimension class sign. • Orange: the sign has been changed automatically based on its class. See "Sign class" on page 180. • Red: the sign has been changed in the filter properties. See " Sign change" on page 231.

Examples of row/column filter settings

Example of simple filters

To create a data entry form to insert quantities of products managed, the following must be set:

- the product custom dimension on the rows
- the quantity account dimensions on the columns

Example of complex filters

To create a form for comparing data between the budget P&L and the actual P&L on periods June and December, the following must be defined:

- the P&L financial statement template for the row filters
- the scenario and the period for the column filters.

In the run step, the following elements will therefore be generated:

- one row for every type of data in the P&L financial statement template
- a total of four columns for the column filters, corresponding to the combinations of the periods with scenarios: 2019BDG/December, 2010ACT/December, 2019BDG/June, 2010ACT/June.

Entity A01	2010BDG December	2010ACT December
Product Revenues – Sales SW - Antivirus	- 1000	- 980
Product Revenues – Sales HW – Memory cards	- 900	- 950
Product Costs – IT – Databases	2000	2500
TOTAL	**100**	**570**

Formula filters

What they are

The *formula* filters are filters on matrix rows or columns which, while the form is being run, function like Excel formulas and make it possible to process data based on the data handled by the matrix itself.

There are advantages to inserting a formula during the design of a matrix, rather than into the matrix area directly. Formulas inserted in this way are also stored when the matrix is regenerated, or whenever the form's structure is changed. On the contrary, formulas inserted directly into the matrix area in Excel are overwritten every time the matrix is regenerated.

Formula format

The supported syntax for formulas is English with separator ",", regardless of the display language used for CCH Tagetik, the add-in or the Excel installation. In Matrix Wizard formulas, references are made to filters in rows/columns rather than cell coordinates like in Excel. The syntax to be followed is detailed below.

- {n}: Row formulas: nth row, current column
- {m}: Column formulas: mth column. current row
- {n,m}: Row/column formulas: nth row, mth column.

E.g. Excel function "=SUM(A1: A2)" is "SUM({1}:{2})" in the Matrix Wizard.

In the form run step, the system transforms the Matrix Wizard formula into an Excel formula for all the row/column filters to which the formula refers. It then automatically adds the "=" symbol in Excel when it generates the matrix.

***Note**: in the local filters tree, formulas do not have descriptions except for formula-type FST items. In any case, descriptions can be allocated to formulas using dictionary items. See "Dictionaries" on page 112.*

Server formulas

To add information on a filter within the matrix, *server formulas* can be inserted. These formulas allow you to add cell fields that refer to other elements of the matrix and form (relative to a dimension present on the rows if working on columns and vice versa, or other matrices or tab filters, form filters) to show the dimension properties (e.g. description, company name, etc.)

Prevailing formulas

When a row and a column containing formulas intersect, the system considers the row formula by default.

To tell the system your preference for a specific row or column in case of intersections, the **Prevailing formulas** option can be enabled in the desired row or column.

***Note**: if both intersecting formulas are set as prevailing formulas, the default behaviour will be applied. The default behaviour and the prevailing formula option do not apply to cells with subtotals.*

Example of a subtotal on a row/column

In the presence of a subtotal calculation formula on both rows and columns, if the prevailing formula option is set as active in both formulas, the subtotal will be calculated on all rows and columns.

	January	February	March	April	Σ
A00	1000	1000	1000	1000	4000
A01	1000	1000	1000	1000	4000
A02	1000	1000	1000	1000	4000
A03	1000	1000	1000	1000	4000
A04	1000	1000	1000	1000	4000
Σ	5000	5000	5000	5000	20000

Example of different subtotals on rows/columns

By activating the prevailing formula option, several subtotal calculation logics can be defined in the same matrix and a selective display of the desired subtotals can be set in the form run step.

For example, in the following matrix, you want to see:

- the total of the intersecting column data in the cells of the last row
- a ratio to the data of the last column in the last cell of the same column

If the sum formula is set on the row, the matrix reports an unsatisfactory-type datum for the last cell of the last column.

	2030 Actual	2031 Actual	Variation
	FY	FY	%
Antivirus	35,700	128,403	259.7%
SW Utilities	5,511,664	3,327,259	-39.6%
Office Automation	8,825,100	12,119,264	37.3%
Monitor	1,176,689	3,482,844	196.0%
Video Projectors	392,230	600,255	53.0%
Total	**15,941,383**	**19,658,024**	**506.4%**

If the sum formula is set on the row and a prevailing ratio formula on the last column, when the form is run that formula will prevail over the sum formula on the row and the cell in question will report the desired value.

	2030 Actual	2031 Actual	Variation
	FY	FY	%
Antivirus	35,700	128,403	259.7%
SW Utilities	5,511,664	3,327,259	-39.6%
Office Automation	8,825,100	12,119,264	37.3%
Monitor	1,176,689	3,482,844	196.0%
Video Projectors	392,230	600,255	53.0%
Total	**15,941,383**	**19,658,024**	**23.3%**

Quick actions for inserting formulas

Quick insert actions can be used to optimise the insertion of formulas in forms, e.g. to insert formulas on the entire row or matrix. For more details, see "Managing formulas" on the next page.

Create reference to specific cells

On standard non-dynamic forms, it is possible to create formulas with references to specific cells in the form.

Element	Description
Bidimensional reference	Absolute reference to a specific cell. Created by indicating the cell coordinates, constructed as follows: • first term = row number • second term = column number For example, *{2,5}* corresponds to an absolute reference to the intersection cell between the second row and the fifth column.
Offset	Relative reference to a cell. Created by indicating the cell's position relative to the row/column on which the reference is being defined. • first term = number of row positions above or below the formula row/column (e.g. *-3* = 3 rows *above*, *+3* = 3 rows *below*) • second term = number of column positions to the left or right of the formula column (e.g. *-3* = 3 columns *to the left*, +3 = 3 columns *to the right*) For example, *{+2, -3}* corresponds to a relative reference to the intersection cell between the second row below and the third column to the left of the row/column on which the formula is set.
Hybrid	Reference created by combining bidimensional and offset reference rules. For example, *{1,-3}* corresponds to a reference to the intersection cell between row *1* and the third column to the left of the row/column on which the formula is set.

Interrupting automatic ranges

When two or more of a formula's arguments include references to adjacent cells, on running the form the system transforms those references into a range. Where the syntax of specific functions does not accept ranges, the system generates error messages. In such cases, the adjacent cells need to be separated with a placeholder row or column, which can be hidden. An example is provided below:

Syntax with range	Syntax on running the form
NETWORKDAYS({1},{2}, Holidays_Dates)	NETWORKDAYS(A1:A2, Holidays_Dates) The syntax includes a range that is not permitted.

Syntax with placeholder between rows	Syntax on running the form
NETWORKDAYS({1},{3}, Holidays_Dates)	NETWORKDAYS(A1, A3, Holidays_Dates) The syntax does not include ranges.

Supported Excel formulas

The add-in supports the following Excel formulas:

Formula	Formula	Formula
Address	Hyperlink	Rank
Bin2Dec	If	Rate
Choose	Iferror	Replace
Code	ImReal	Rept
Column	Index	Roman
Columns	Indirect	Row
Complex	Intercept	Rows
Count	IPMT	Slope
Coounta	Irr	Substitute

Formula	Formula	Formula
Countbank	Lookup	Subtotal
Countif	Match	Sumif
Countifs	Mina	Sumifs
Days360	Maxa	Sumproduct
Dec2Bin	Mirr	Sumx2my2
Dec2Hex	Mode	Sumx2py2
Variance	Na	Sumxmy2
EDate	Now	T
Error.type	Npv	Text
Even	Oct2Dec	Time
Fact	Odd	Today
FactDouble	Offset	Value
Hex2Dec	PPMT	Vlookup
Hlookup	Quotient	Weekday

***Note**: to calculate the value of formulas before viewing them, e.g. when sorting the matrix elements based on the value of a formula, it is necessary to use Excel functions related to advanced selection scripts (see "Excel functions" on page 294).*

Managing formulas

Insert a formula on all cells in a row/column

This procedure shows you how to insert a formula on a whole row/column from a matrix cell.

1. To select the cell:

If you want to copy the formula...	Then...
on the row	select the cell of the first column relative to the row
on the column	select the cell of the first row relative to the column

2. Insert the desired formula in the cell in accordance with Excel syntax.
3. Press ENTER: the formula will be propagated over the whole row/column.

In the matrix, the system automatically converts Excel syntax into CCH Tagetik syntax.

When inserting elements in braces, make sure you edit them in or click on the {} button at the top-right, otherwise the number will be considered a pure number, not an element of the matrix.

To insert the elements involved in the formula, position the cursor in the Reporting Client Formula window and right click; a list will appear showing all the rows/columns of the matrix in which to select the desired element. This prevents errors and allows you to write the formula quicker.

Predefined filters

Description

To optimise the design of the form structure, the definition of sets of row/column filters and the property settings of the filters that they contain can be saved in a single *predefined filter*. The predefined filter is then shown in the matrix dimensions tree together with the dimensions (in the **Filters** folder) and can be used like a normal filter. Predefined filters can be modified or removed at any time. For example, this functionality is useful in the case of several forms with the same or similar structures; saving a set of filters as a single filter allows you to quickly replicate the structure for all forms, avoiding the need to design a new one for each of them.

The predefined filters functionality is only available to users for whom function "0002914 - Reporting .Net - Param - Predefined filters" is enabled in their role.

Predefined filters can be used as a parameters (see "Parameters" on page 136).

Static or dynamic use of predefined filters

Predefined filters can be used statically or dynamically.

Use	Description
Static	The filter is defined on the matrix in the row/column filters definition phase.
Dynamic	The filter is used as a form run parameter, so it is defined dynamically when the form is opened (see "Parameters" on page 136). All changes made to dynamic filters are automatically propagated to all forms in which the filter is used.

Particular cases in the use of predefined filters

The following particular cases may be encountered when using predefined filters:

- Several predefined filters can be inserted dynamically (when the form is run, the system checks that the various predefined filters on which the deployment is performed contain the same dimensions in the same order).
- Placeholders can be inserted between predefined filters.
- It is possible to add elements of other dimensions below predefined filters inserted dynamically (when the form is run, the system checks that the added dimensions do not include any of the dimensions already present in the predefined filter).
- Predefined filters can be inserted statically or dynamically below pre-existing elements of other dimensions (when the form is run, the system checks that the filter dimensions do not include any of the dimensions already present in the filters tree).

Working with predefined filters

Excel > CCH® Tagetik > Design > open form > open or create matrix > Row/column filters

Create a predefined filter in a matrix

This procedure shows you how to create a predefined filter based on a combination of filters set on rows of the matrix, but it is also valid if done on the basis of filters set on columns.

1. Click next to the local row filters tree: the **Predefined filters** window will open.
2. Insert a code for the new predefined filter and a description for every language supported by the system.
3. Click **OK**.

Saved predefined filters are visible in the **Filters** node of the Matrix Wizard dimensions tree.

***Note**: in local filter trees, the predefined filter is identified with the icon if it is dynamic or the icon if it is static.*

Update a predefined filter

Modify the structure of the filter as desired and click .

Edit the description of the predefined filter

1. In the dimensions tree, select **Filters**, right click the desired predefined filter and select **Edit header**.
2. Edit one or more descriptions as desired.
3. Click **OK**.

Delete a predefined filter

In the dimensions tree, select **Filters**, right click the desired predefined filter and select **Delete**.

***IMPORTANT**: when the predefined filter is deleted, the system does not check whether it is used in one or several forms.*

Insert a predefined filter dynamically

1. Open the matrix (see Come accedere alle finestre).
2. Select **Dynamic** at the top-left.
3. Insert the predefined filter as a row/column filter or a matrix filter.


***Note**: in filter trees, the predefined filter is identified with the icon.*

Examples of predefined filter settings


Using predefined filters

Suppose you have the following predefined filters available:


- Fixed_Var: allows you to compare scenarios 2012ACT and 2011ACT and to calculate the relative variance



- Fixed_Var_%: allows you to compare scenarios 2012ACT and 2011ACT, and calculate the relative variance and percentage variance




Tagetik allows the user to decide which predefined filter to use when the form is run, by inserting (in this case in the columns) the Predefined filter parameter "$FLT_P - Filters".



The Predefined filter parameter must be inserted as Dynamic, by activating the "Dynamic" option at the top-left of the Matrix Wizard.


When the form is run, the user selects the predefined filter to be used (in addition to the other available parameters).




Using predefined filters with parametric elements

In the previous example, the predefined filter did not contain any parametric elements. Now let's look at an example in which the predefined filter contains a parametric scenario "$SCE_P". Suppose you have the following predefined filters:


- Param_Var: allows you to compare the current and previous scenarios and calculate the relative variance



- Param_Var_%: allows you to compare the current and previous scenarios and calculate the relative variance and percentage variance



If the Predefined filter parameter "$FLT_P - Filters" is inserted in the columns, in the run step the system will ask the user to indicate which predefined filter to use, but will not require the scenario. This is because the form structure is only known after it has been run. It is therefore necessary to override the scenario parameter in the form. To do this, the user must click the **Manage parameters** button in the Design bar ribbon.



In the parameters configuration window, the user must

- click the **Edit** button;
- select parameter $SCE_P from the "Other parameters" folder and move it to the definition area using the button.

This means that the user will be asked for the scenario when the form is run.

Custom filters

What they are

In transactional Analytical Workspace matrices, custom filters can be defined on dataset measures.

When the form is run, custom filters are applied by running a query on the database.

***Note**: the filter semantics can be made conditional on the implementation of the specific vendor.*

***Note**: when an Analytical Workspace is duplicated, and reports are included in the duplication, any custom filters on measures will be cloned, but not filters on measures with which a Analytical Workspace dictionary type is associated.*

Custom filters are defined using the Matrix Wizard (see "Custom filters tab" below).

Custom filter restrictions

Custom filters are subject to the following restrictions:

- they only use the equals operator (=)
- they use AND as the logic operator to join filters. This allows the user to obtain the intersection of the results of filters applied in this way.

Application of filters when cloning workspaces

If the function is used to duplicate a workspace (see Clone window) that includes forms containing filters on measures, the cloned forms will have the same filters. However, filters on measures with which an AW dictionary-type parameter is associated will not be cloned.

Locking mechanism

The report locking mechanism also considers parametric custom filters. In fact, it blocks access in data entry mode if the set of data retrieved with the application of custom filters is the same.

Custom filters tab

Excel > CCH® Tagetik > Design > open form > Matrix > Custom Filters


See Come accedere alle finestre for alternative paths.

***IMPORTANT**: this tab is only shown when a transactional matrix refers to an Analytical Information Hub dataset.*

Purpose of the tab

This tab allows you to create a custom filter based on the measures data of the dataset associated with the form.

What it looks like



Page sections

Element	Description
Custom filter conditions definition area	Shows rows for defining the conditions of the filter on the dataset's measures.
Filter management buttons	Allows you to manage filters on measures.

Fields for defining custom filter conditions

Element	Description
Measure	Allows you to select a dataset measure.
Ask at runtime	Allows you to set, on the measure data, a filter on a fixed value or a value obtained from the definition of a custom parameter when the form is run (see "Parameters" on page 136).
Parameter	Only visible with **Ask at runtime** selected. Shows the list of non-dimensional parameters that are compatible with the selected measure and allows you to select one of them to filter the measure data. ***Note**: parameters are compatible when the data type is the same as the measure type (text, number, date), or, for dictionary-type parameters, when the parameter refers to a dictionary belonging to the same Analytical Workspace as the measure and the measure type is text.*
Operator	Allows you to select the operator to be applied to the filter.
Text box	Only visible with **Ask at runtime** not selected and when the measure type is text or numeric. Allows you to enter the value of the filter.
Date selection box	Only visible with **Ask at runtime** not selected and when the measure type is date. Allows you to select a date for the filter.

Filter management buttons

Element	Description
	Adds a filter.
	Removes a filter

The Print Filters function

What is it for

The *Print Filters* function allows you to see a version of the form in which the matrix cells show details of the filters to which the amount is subject, instead of the amount itself. This functionality is useful for the configurator user, because it allows you to consult, in the context of the work desktop, information on the origins of what is set in the form, or in the matrix, form filters or tab filters.

In particular, it makes it easier to consult the dimensions used in the matrix when, in the presence of complex configurations, they cannot be immediately inferred from the rows/columns of the form. For example, the dimensions present on the form run cannot be immediately inferred in a form that displays variations with control groups inserted on the columns and variation accounts inserted on the rows.

Print Filters Wizard

Excel > CCH® Tagetik > Design > open form > Run > Print Filters

Purpose of window

This window allows you to select the attributes of dimensions relative to the form filters to start printing the filters. Once the desired dimensions have been selected, the system generates the filters printout by overlaying on the matrix cell fields showing the requested attributes of the dimensions involved. For more details on cell fields, see "Cell fields" on page 105.

Page sections

Element	Description
Predefined functions tree	Shows the existing dimensions and the relative attributes.
Dimensions area to be printed	Shows a list of the chosen dimensions, which will populate the cell fields on the structure of the matrix in the print filters step.

Buttons on the page

Element	Description
	Adds the selected dimension to the dimensions area.
	Deletes the selected dimension from the dimensions area.
	Allows you to access an advanced editor for the cell field relative to the dimension selected in the dimensions area.
	Moves the selected dimension up/down in the dimensions area.


Print Filters examples

Example 1


Suppose you have a form in which a filter on a hierarchy of the entity dimension is used as a filter both on the rows and on the columns. The matrix present in the form is therefore of the type shown below

	A	B	C	D	E	F
1						
2						
3				Europe	Usa	
4			Subholding B	1,000	1,000	
5			Subholding North America	1,000	1,000	
6			Subholding Y	1,000	1,000	
7				3,000	3,000	
8						
9						
10						
11						

We insert the $Entity.code cell field in the print filters wizard window.




When the OK button is clicked, the system displays the following




Example 2

Suppose you have a form in which scenarios are on the rows and periods are on the columns, and a matrix filter has also been defined on the entity dimension. The matrix present in the form is therefore of the type shown below



We insert the relevant cell field in the print filters window as necessary to show the entity currency



When the OK button is clicked, the system displays the following

	A	B	C	D
1				
2			June	Dec
3		2011 Actual	Entity= 'EUR'	Entity= 'EUR'
4		2012 Actual	Entity= 'EUR'	Entity= 'EUR'
5		2013 Budget	Entity= 'EUR'	Entity= 'EUR'
6				
7				
8				

Generate a filters printout

Excel > CCH® Tagetik > Design > open form > Run > Print Filters

Select the dimensions for the cell fields of the filters printout

To find out the dimensions of the matrix's row/column filters, click : the List of filters used window will appear (see "List of filters used window" on the facing page).

1. Select the desired dimension or the attribute of the dimension and click to add it to the dimensions area.
2. Repeat step 1 for all desired dimensions.
3. (Optional) Click to run advanced configurations for the cell field relative to the dimension selected in the dimensions area to be printed (for more details on advanced cell field configuration, see "Cell fields" on page 105. Run the advanced configuration and click **OK**.
4. Click **OK**: in the work desktop, the matrix will show the cell fields of the filters printout.

List of filters used window

Excel > CCH® Tagetik > Design > open form > List of filters used

Excel > CCH® Tagetik > Design > open form > open the matrix wizard of one of the matrices > List of filters used

Purpose of window

This window shows a list of all the filters set on the current form.

Data in window

Element	Description
Code	Form code.
Description	Form description.
Form filters	List of filters applied to the form.
<template name> Template	List of filters contained in the template, grouped by filter type. • **Tab filters** • **Matrix Filters** • **Row filters** • **Column filters**
Used parameters	List of opening parameters set on the form.

Buttons on the page

Element	Description
	Copy of the information shown in the window.

Design: functions

Contents

This section covers the following topics:

Dimensional functions 250
Description of dimensional functions 251
Dimensional attributes 252
Description of the attributes shared by all dimensions 252
Description of attributes for the Entity dimension 256
Description of attributes for the Account dimension 262
Description of attributes for the Scenario dimension 265
Description of attributes for the Period dimension 270
Description of attributes for other dimensions 272
Non-dimensional functions 273
Description of non-dimensional functions 273
Non-dimensional attributes 279
Location functions 283
Description of location functions 283
Aggregation structure navigation functions 286
Description of aggregation structure navigation functions 286
Excel functions 294
Functions on sets 296
Hyperlinks 298
Managing hyperlinks 301
Action List Wizard window 303
The Open form window (Action List Wizard) 304
Properties Window: Filters cycle 306

Dimensional functions

Description

These functions return dimensional objects like nodes of aggregation structures or lowest level elements (leaves) if these form part of a filter (row/column, matrix, sheet, form) to which advanced selection is applied. They are grouped into nodes, one for every CCH Tagetik dimension.

The "**$**" symbol followed by the dimension name represents the function that returns the dimension object used.

Example

var := $Account; saves the used accounts in the "var" variable.

var := $Scenario; saves the used scenarios in the "var" variable.

Description of dimensional functions

The $ Function

Element	Description
Availability	From CCH Tagetik 3.0912
Applicability	To all dimensions
Syntax	*$<DimensionName>[(boolean)]*
Parameters	(optional) Boolean: • TRUE: allows you to obtain the lowest level elements of the indicated dimensional object. • FALSE: allows you to obtain the indicated dimensional object.
Value returned	Filter defined on the following dimensions: • **$Entity.**: entity dimension • **$Account.**: account dimension • **$Causal.**: causal dimension • **$Cust_Dim1...5.**: custom dimensions • **$Category.**: category dimension • **$AmountType.**: amount type dimension • **$Currency.**: currency dimension • **$Scenario.**: scenario dimension • **$Period.**: period dimension • **$PeriodLength.**: period length dimension • **$ICEntity.**: counterparty entity dimension • **$ICCust_Dim.**: counterparty custom dimension

Example

`$Entity`

Returns the entity on which it is possible to operate with attributes.

Example

`$Entity.code` or `$Entity(TRUE).code`

With a parameter on a hierarchy of the entity dimension.

If the following is selected when running the form...	The function will return...
a lowest level element of the hierarchy	the code of the selected lowest level element
a node of the hierarchy	a string resulting from the concatenation of the codes of all the lowest level elements related to the selected node.

Example

`$Entity(FALSE).code`

With a parameter on a hierarchy of the entity dimension, if the user selects a node of the hierarchy, the code of the selected node will be obtained when the form is run.

Particular features of dimensional functions

For every dimensional function, there is a corresponding function without the $ symbol. With the $, the function returns the current value associated with a dimension; without the $, it returns a description of the dimension.

Examples

`$Entity.desc`: returns the string "Tagetik srl".

`Entity.desc`: returns the string "Entity".

These functions are also useful for recalling elements in forms where the involved dimension is not used. Descriptions are always available and return information on all the system's dimensions, including those not linked to the current filters.

Example

The **$Entity.getLeaf("A1").desc** function can be used to print a cell field with the description of entity "A1". However, this only works if a starting filter is present on the entity dimension and it is therefore possible to identify the lowest level element with code "A1". If there are no filters on the entity dimension, or if the entity dimension is not included in the form, the $Entity expression will not return anything. In this case, the **Entity.getLeaf("A1").desc** function will return the desired information.

Functions without the $ are also applicable to hierarchies: **hierarchy("G1").Entity.getNode("N1").desc** or **Entity("G1").getNode("N1").desc**

Hierarchy

Element	Description
Availability	From CCH Tagetik 3.0912
Applicability	To all dimensions in which hierarchies can be defined
Syntax	*Hierarchy("heirarchy_code")*
Parameters	*"heirarchy_code."*
Value returned	Filter on the dimension hierarchy indicated in "heirarchy_code"

Example

`$Entity(Hierarchy("G1"))`: returns the filter on hierarchy G1 defined on the entity dimension.

Dimensional attributes

Description

The attributes of dimensional functions provide information on the dimensional object called up by the function. The most common attribute is **code**, available for almost all functions. This attribute returns a string of text containing the code of the dimensional object.

Dimensional functions and attributes are typically used to define matrix headers and cell fields. Attributes can be valid for all dimensions or specific for one dimension.

Example

var := $Account.code; saves the code of the used account in the "var" variable.

var := $Account.desc; saves the description of the used account in the "var" variable.

Description of the attributes shared by all dimensions

Attribute 1, ..., Attribute 5

Element	Description
Availability	From 3.0912
Applicability	All dimensions for which custom attributes can be managed (Entity, Account, Custom Dimensions)
Syntax	*Attribute1*
Value returned	String with the value of the custom attribute defined in the elements table of the dimension to which it is applied.

Example

`$Entity.Attribute1`

Returns the value of the entity's attribute 1.

Code

Element	Description
Availability	From 3.0912
Applicability	All objects, dimensional and otherwise
Syntax	*code*
Value returned	String with the dimensional object element code

Example

`$Entity.code`

Returns the entity code specified in the filter (row/column, matrix, sheet, form).

Desc

Element	Description
Availability	From 3.0912
Applicability	All objects, dimensional and otherwise
Syntax	*Desc([language])*
Parameters	• *language*: (Optional) Code of the table language indicated as a whole number.
Value returned	String with the description of the dimensional (or non-dimensional) object element. The optional parameter is only supported if there are multiple descriptions. If omitted, the user's table language is used.

Example

`$Entity.desc(2)`

Returns the description of the entity, specified in the filter (row/column, matrix, sheet, form), in table language 2.

DictionaryTerm

Element	Description
Availability	From 3.1012
Applicability	All dimensional objects (lowest level elements and nodes)
Syntax	*DictionaryTerm([language])*
Parameters	• *language*: (Optional) Code of the table language indicated as a whole number.
Value returned	Any dictionary items associated with the filter (row/column, matrix, sheet, form) or an empty string. The optional parameter is only supported if there are multiple descriptions. If omitted, the user's table language is used.

Examples

- `$Entity.dictionaryTerm`

Returns the description of the dictionary item in the user's table language related to the filter (row/column, matrix, sheet, form) on the entity.

- `$Entity.dictionaryTerm(2)`

Returns the description, in table language 2, of the dictionary item related to the filter (row/column, matrix, sheet, form) on the entity.

Dimension

Element	Description
Availability	From 3.0912
Applicability	All dimensional objects (lowest level elements and nodes)
Syntax	*Dimension*
Attributes	• *code* • *desc* • *hierarchyCode*
Value returned	Dimension or hierarchy to which the filter (row/column, matrix, sheet, form) belongs

Examples

- `$Entity.dimension.code`

Returns the string "AZI", which identifies the entity dimension.

- `$Entity.dimension.desc`

Returns the name assigned to the entity dimension in configuration, e.g. "Legal Entity".

- `$Entity.dimension.hierarchyCode`

Returns the code of the hierarchy to which the entity specified in the filter (row/column, matrix, sheet, form) belongs.

Link

Element	Description
Availability	From 3.1012
Applicability	All dimensional objects (lowest level elements and nodes)
Syntax	*link*
Value returned	Any link to the documentation related to the element of the dimensional object

Example

`$Entity.link`

Returns any link to the documentation related in the table to the entity specified in the filter (row/column, matrix, sheet, form).

LowestReference

Element	Description
Availability	From 3.0912
Applicability	All nodes of a hierarchy
Syntax	*lowestReference*
Value returned	Reference lowest element relative to the node

Example

`$Entity(Hierarchy("01")).lowestReference.desc`

Returns the description of the reference entity relative to the node used as a filter (row/column, matrix, sheet, form) on the entity's hierarchy 01.

Path

Element	Description
Availability	From 4.2.0
Applicability	All dimensions and forms
Syntax	*Path([level], [separator], [cellField])*

Element	Description
Parameters	• *level*. (Optional) The number of levels to go up in the hierarchy (1 = parent, 2 = grandparent, etc.). If omitted or zero, it will go down to the root of the hierarchy. • *separator*. (Optional) Separator to be used between each element in the returned string. If omitted, the backslash "\" will be used. • *cellField*. (Optional) Cell field-type expression to be defined on each node of the hierarchy belonging to the *path*. If omitted, the code will be used. If the *path* function is applied to the form object, this field is not supported and only the code of the group's nodes belonging to the *path* will be used.
Value returned	String obtained from the concatenation of expressions defined on the nodes of the current element's path.

Examples

The following examples look at a filter on the "AG - Geographical area" hierarchy of the entity dimension and presume that the city of Lucca (LU) is related to the Tuscany (TOS) node followed by the Italy (ITA) / Europe (EU) nodes:

- `$Entity.path`

Returns the string "AG\EUR\ITA\TOS\LU".

- `$Entity.path(0)`

Returns the string "AG\EUR\ITA\TOS\LU".

- `$Entity.path(2)`

Returns the string "TOS\LU".

- `$Entity.path(".")`

Returns the string "AG.EUR.ITA.TOS.LU".

- `$Entity.path(3,".")`

Returns the string "ITA.TOS.LU".

- `$Entity.path(3,".","$Entity.desc")`

Returns the string "Italy.Tuscany.Lucca".

With a form related to the "DE - Data Entry" \ "P&L - Profit And Loss" nodes of form group "$", the following behaviour is obtained:

- `Report.path`

Returns the string "$\DE\CE".

- `Report.path(2)`

Returns the string "DE\CE".

- `Report.path(".")`

Returns the string "$.DE.CE".

Segment Type

Element	Description
Availability	From 3.1012
Applicability	All hierarchy nodes
Syntax	*segmentType*
Value returned	Segment type applied to the filter (row/column, matrix, sheet, form)

Example

```
$Entity(Hierarchy("01")).segmentType.desc
```

Returns the description of the segment type relative to the node used as a filter (row/column, matrix, sheet, form) on the entity's hierarchy 01.

Description of attributes for the Entity dimension

The AdministrativeHQ attribute

Element	Description
Availability	From 3.0912
Syntax	*AdministrativeHQ*
Value returned	Name of the entity's administrative headquarters

Example

```
$Entity.administrativeHQ
```

Returns the entity's administrative headquarters.

The AdministrativeHQBranch attribute

Element	Description
Availability	From 3.0912
Syntax	*AdministrativeHQBranch*
Value returned	City of the entity's administrative HQ

Example

```
$Entity.administrativeHQBranch
```

Returns the city of the entity's administrative HQ.

The AlternativeCode attribute

Element	Description
Availability	From 4.2.1
Syntax	*AlternativeCode*
Value returned	Alternative entity code

Example

Entity with code A00 and alternative code A00_ITA.

```
$Entity.alternativeCode
```

Returns the string "A00_ITA".

The BusinessName attribute

Element	Description
Availability	From 3.0912
Syntax	*businessName*
Value returned	The entity's business name

Example

```
$Entity.businessName
```

Returns the entity's business name.

The CertificationDate attribute

Element	Description
Availability	From 3.0912
Syntax	*certificationDate*
Value returned	The entity's submission date

Example

```
$Entity.certificationDate
```

Returns the entity's submission date/phase containing the form for the process to which scenarios/periods present in the filter (row/column, matrix, sheet, form) are related.

The ConsolidationPerc attribute

Element	Description
Availability	From 3.0912
Syntax	*consolidationPerc*
Value returned	The entity's consolidation percentage

Example

```
$Entity.consolidationPerc
```

Returns the entity's consolidation percentage.

The ConsolidationType attribute

Element	Description
Availability	From 3.0912
Syntax	*consolidationType*
Value returned	The entity's consolidation type

Example

```
$Entity.consolidationType
```

Returns the entity's consolidation type.

The ConstitutionDate attribute

Element	Description
Availability	From 5.0
Syntax	*constitutionDate*
Value returned	The date on which the entity was established

Example

```
$Entity.constitutionDate
```

Returns the date on which the entity was established.

The Counterparties attribute

Element	Description
Availability	From 3.0912
Syntax	*counterparties*
Value returned	Counterparty entities related to the entity

Example

`$Entity.counterparties.code`

Returns the codes of the counterparty entities related to the entity.

The CounterpartiesByControlType attribute

Element	Description
Availability	From 3.0912
Syntax	*counterpartiesByControlType*
Attributes	• *code* • *desc*
Value returned	Counterparty entities related to the current entity by scenario/period (control chart). Requires a filter (row/column, matrix, sheet, form) on the scenario and period dimensions.

***IMPORTANT**: this attribute always returns elements belonging to the "Counterparty Entity" dimension. The elements obtained can then only be used directly within advanced selection scripts related to the "Counterparty Entity" dimension (see "Details of advanced selection scripts for calculating the default value" on page 141).*

Example

`$Entity.counterpartiesControlType.code`

Returns the codes of the counterparty entities related to the entity within the control chart.

The Currency attribute

Element	Description
Availability	From 3.0912
Syntax	*currency([scenario],[period])*
Attributes	• *code* • *desc*
Parameters	• *scenario* (optional) Scenario code • *period* (optional) Period code
Value returned	Entity currency specified in the filter (row/column, matrix, sheet, form) for the process to which scenarios/periods present in the filter are related.

Examples

- `$Entity.currency.code`

Returns the currency code associated with the entity specified in the filter for the process to which scenarios/periods present in the filter are related.

- `$Entity.currency.code.getLeaf()`

Returns the filter on the currency associated with the entity

- `$Entity.currency(column("MATRIX1",1).$Scenario,column ("MATRIX1",1).$Period.code`

Returns the currency code associated with the entity specified in the filter for the process to which scenarios/periods present on the first column of "MATRIX1" are related.

The Cust_dim1Default, Cust_dim2Default, ... Cust_dim5Default attribute

Element	Description
Availability	From 4.2.1
Syntax	*cust_dim1Default*
Attributes	• *code* • *desc*
Value returned	Default element of the custom dimension associated with the entity specified in the filter (row/column, matrix, sheet, form) extracted from the elements table

Example

```
$Entity.cust_dim1Default.code
```

Returns the code of the default element of custom dimension 1 associated with the entity specified in the filter.

The Email attribute

Element	Description
Availability	From 5.0
Syntax	*email*
Value returned	Entity email

Example

```
$Entity.email
```

Returns the entity's email.

The EquityRatioPerc attribute

Element	Description
Availability	From 3.0912
Syntax	*equityRatioPerc([scenario],[period])*
Parameters	• *scenario* (optional) Scenario code • *period* (optional) Period code
Value returned	The entity's equity ratio percentage

Examples

- `$Entity.equityRatioPerc`

Returns the equity ratio percentage.

- `$Entity.equityRatioPerc(column("MATRIX 1",1).$Scenario,column("MATRIX 1",1).$Period)`

Returns the equity ratio percentage for scenarios/periods indicated as parameters, not those specified in the filter (row/column, matrix, sheet, form).

The ExchangeRate attribute

Element	Description
Availability	From 3.0912
Syntax	*exchangeRate([scenario],[period],[entity])*
Applicability	Entity or currency
Parameters	• *scenario* (optional) Scenario code • *period* (optional) Period code • *entity* (optional) Entity code
Attributes	• *average* Average FX rate • *final* Final FX rate • *period*: Period average FX rate
Value returned	FX rate of the currency used as the filter (row/column, matrix, sheet, form) or of the entity indicated as the parameter

Examples

- `$Currency.exchangeRate.average`

Returns the average FX rate of the entity currency for the scenario/period/entity defined in the filter.

- `$Currency.exchangeRate.final`

Returns the final FX rate of the entity currency for the scenario/period/entity defined in the filter.

- `$Currency.exchangeRate.periodic`

Returns the period average FX rate of the entity currency for the scenario/period/entity defined in the filter.

- `$Currency.exchangeRate(matrix("MATRIX 1").$Scenario, matrix("MATRIX 1").$Period, matrix("MATRIX 1").$Entity).average`

Returns the average FX rate of the entity currency for the scenario/period/entity defined in "Matrix 1".

The LegalHQ attribute

Element	Description
Availability	From 3.0912
Syntax	*legalHQ*
Value returned	The entity's legal headquarters

Example

`$Entity.legalHQ`

Returns the entity's legal headquarters.

The LegalHQBranch attribute

Element	Description
Availability	From 3.0912
Syntax	*legalHQBranch*
Value returned	City of the entity's legal HQ

Example

`$Entity.legalHQBranch`

Returns the city of the entity's legal HQ.

The OwnershipPerc attribute

Element	Description
Availability	From 3.0912
Syntax	*ownershipPerc([scenario],[period])*
Parameters	• *scenario* (optional) Scenario code • *period* (optional) Period code
Value returned	The entity's ownership percentage

Examples

- `$Entity.ownershipPerc`

Returns the ownership percentage.

- `$Entity.ownershipPerc(column("MATRIX 1",1).$Scenario,column("MATRIX 1",1).$Period)`

Returns the ownership percentage relative to the scenario/period defined as a parameter of the function and not for the scenario/period specified in the filter.

The Phone attribute

Element	Description
Availability	From 5.0
Syntax	*phone*
Value returned	Entity telephone number

Example

```
$Entity.phone
```

Returns the entity's telephone number.

The ProcessStep attribute

Element	Description
Availability	From 3.0912
Syntax	*processStep*
Attributes	• *code* • *desc*
Value returned	Step related to the entity for the process to which the scenario/process present in the filter (row/column, matrix, sheet, form) is related

Example

```
$Entity.processStep.code
```

Returns the code of the step associated with the entity specified in the filter.

The ProportionalityPerc attribute

Element	Description
Availability	From 3.0912
Syntax	*proportionalityPerc*
Parameters	• *scenario* (optional) Scenario code • *period* (optional) Period code
Value returned	The entity's proportionality percentage

Examples

- `$Entity.proportionalityPerc`

Returns the entity's proportionality percentage.

- `$Entity.proportionalityPerc(column("MATRIX 1",1).$Scenario,column("MATRIX 1",1).$Period)`

Returns the entity's proportionality percentage for scenarios/periods processed as parameters of the function, not for those specified in the filter.

The Snapshot attribute

Element	Description
Availability	From 3.0912
Syntax	*snapshot*
Value returned	Information related to the entity/scenario/period triplet when a snapshot scenario is created

Examples

- `$Entity.snapshot.comment`

Returns the comment inserted when the snapshot scenario for entity/scenario/periods present in the filter was created.

- `$Entity.snapshot.desc`

Returns the description inserted when the snapshot scenario for the entity/scenario/period present in the filter was created.

The Variable attribute

Element	Description
Availability	From 3.0912
Syntax	*variable(code)*
Parameters	• *code* Classifier code
Attributes	• *code* • *desc*
Value returned	The Variable element associated with the entity specified in the filter

Example

`$Entity.variable("V01").desc`

Returns the description of variable "V01" associated with the entity specified in the filter.

Description of attributes for the Account dimension

The AccountsToDetail attribute

Element	Description
Availability	From 3.0912
Syntax	*accountsToDetail*
Value returned	Set of parent account of the control group to be detailed. In case of: • **filter on a control group**, it returns the group's parent account • **filter on the account** it returns the parent accounts of the control group to which the account belongs

Example

`$Account.accountsToDetail`

Returns all accounts to be detailed of the control group specified in the filter (row/column, matrix, sheet, form) or of the control group to which the account specified in the filter belongs.

The CausalsGroup attribute

Element	Description
Availability	From 3.0912
Syntax	*causalsGroup*
Attributes	• *code* • *desc*
Value returned	Any node of causals used to create the control group specified in the filter

Examples

- `$Account.causalsGroup.code`

Returns the node of causals used to create the control group specified in the filter.

- `$Account.causalsGroup.lowest`

Returns all individual causals of the node of causals used to create the control group specified in the filter.

The GroupType attribute

Element	Description
Availability	From 3.0912
Syntax	*groupType*
Attributes	• *code* • *desc*
Value returned	Type (code and description) of the control group specified in the filter. The following values are returned: • D - Details • F - Variation • Q - Balancing • C - Coherence In case of: • **filter on control group** returns the control group type • **filter on account** returns the type of the control group to which the account belongs

Example

With filters on a Variation-type control group:

`$Account.groupType.code`: returns string "F"

`$Account.groupType.desc`: returns the “Variation" string or equivalent string, depending on the application language set by the user

The OriginalAccounts attribute

Element	Description
Availability	From 3.0912
Syntax	*originalAccounts*
Value returned	Set of accounts related to a FST item. In case of: • **filter on account**, it returns the same account • **FST items** and **nodes of a hierarchy defined on the account dimension**, it is equivalent to the children() function and returns the related accounts • **formula-type FST items**, it progressively returns the accounts related to all FST items involved in the formula, including those involved indirectly, depending on the items to which other filters are related in a chain, up to the one to which the accounts are related. • **control group/causal intersection**, it returns the account present in the intersection

The OriginalControlGroup attribute

Element	Description
Availability	From 3.0912
Syntax	*originalControlGroup*
Value returned	Control group associated with a filter on an account. In case of: • **filter on a control group**, it returns the control group • **filter on account** taken from **within a control group**, it returns the control group to which the account belongs • **filter on account taken from elsewhere** (hierarchies, FSTs), it returns all control groups that detail the account

Examples

- `$Account.originalControlGroup.code`

Returns the control group to which the account specified in the filter belongs

- `$Account.originalControlGroup.controlGroup`

Deploys the control group to which the account specified in the filter belongs, like in the Matrix Wizard.

- `$Account.originalControlgroup.causalsGroup.code`

Returns, given a filter on an account, the code of the detail-type node related to the control group to which the account belongs.

The Schema attribute

Element	Description
Availability	From 3.0912
Syntax	*template*
Attributes	• code • desc • taxonomy
Value returned	Financial Statement Template to which the account specified in the filter belongs. If the account was chosen from a hierarchy defined on the account dimension, it returns an empty string

Examples

`$Account.schema.code`

Returns the code of the FST to which the account specified in the filter belongs.

`$Account.schema.desc`

Returns the description of the FST to which the account specified in the filter belongs.

The ShortDesc attribute

Element	Description
Availability	From 3.0912
Syntax	*shortDesc*
Value returned	Short description in the language of the user of the specified account

Example

`$Account.shortDesc`

Returns the description of the account specified in the filter.

The XBRLName attribute

Element	Description
Availability	From 3.1012
Syntax	*xbrlName*
Value returned	Value of the XBRL name field associated with a filter on the account. In particular, in case of: • **a filter on an FST item**, it returns the value of the XBRL name field associated with the item • **a filter on account** taken from **within an FST**, it returns the value of the XBRL name field associated with the FST item to which the account is related • in all other cases, it returns an error

Example

`$Account.xbrlName`

Returns the value of the XBRL name field associated with the account.

Description of attributes for the Scenario dimension

The CertificationDate attribute

Element	Description
Availability	From 3.0912
Syntax	*certificationDate*
Value returned	The entity's submission date

Example

```
$Entity.certificationDate
```

Returns the entity's submission date for the process to which scenario and period present in the filter are related.

The ConsolidationScenario attribute

Element	Description
Availability	From 3.0912
Syntax	*consolidationScenario*
Attributes	• *code* • *desc*
Value returned	If applied to an original scenario, it returns the associated consolidation scenario or set of consolidation scenarios. If applied to a consolidation scenario, it returns the same scenario.

Examples

- `$Scenario.consolidationScenario.code`

Returns the code of the consolidation scenario associated with the original scenario specified in the filter.

- `Scenario.consolidationScenario("true").code`

Returns the code of the consolidation scenario associated with the original scenario specified in the filter. In the event that the scenario is included in more than one group, it is shown below every group in which it has been inserted.

- `$Scenario.consolidationScenario("false").code`

Returns the code of the consolidation scenario associated with the original scenario specified in the filter

The CurrencyScenario attribute

Element	Description
Availability	From 3.1012
Syntax	*currencyScenario*
Attributes	• *code* • *desc*
Value returned	Currency of the consolidation scenario specified in the filter. If applied to an original scenario, it returns an empty string.

Example

```
$Scenario.currencyScenario.code
```

Returns the currency code of the consolidation scenario specified in the filter.

The ExchangeRate attribute

Element	Description
Availability	From 3.0912
Syntax	*exchangeRate([scenario],[period],[entity])*
Applicability	Entity or currency
Parameters	• *scenario* (Optional) Scenario code • *period* (Optional) Period code • *entity* (Optional) Entity code
Attributes	• *average* Average FX rate • *final* Final FX rate • *period*: Period average FX rate
Value returned	FX rate of the currency used as the filter or of the entity indicated as the parameter

Examples

- `$Currency.exchangeRate.average`

Returns the average FX rate of the entity currency for the scenario/period/entity defined in the filter.

- `$Currency.exchangeRate.final`

Returns the final FX rate of the entity currency for the scenario/period/entity defined in the filter.

- `$Currency.exchangeRate.periodic`

Returns the period average FX rate of the entity currency for the scenario/period/entity defined in the filter.

- `$Currency.exchangeRate(matrix("MATRIX 1").$Scenario, matrix("MATRIX 1").$Period, matrix("MATRIX 1").$Entity).average`

Returns the average FX rate of the entity currency for the scenario/period/entity defined in "Matrix 1".

The Holding attribute

Element	Description
Availability	From 3.0912
Syntax	*holding*
Attributes	• *code* • *desc*
Value returned	Holding of the consolidation scenario specified in the filter

Example

`$Scenario.holding.code`

Returns the code of the holding.

The Next/Prev/Ref1/Ref2/.../Ref5 attribute

Element	Description
Availability	From 3.0912
Syntax	*next, prev, ref1, ref2, ... ref5*
Attributes	• code • desc
Value returned	Value of the relative field for the scenario specified in the filter. In the scenarios table, the attributes and fields correspond as follows: • **next** - next scenario • **prev** - previous scenario • **ref1** - reference scenario 1 • **...** • **ref5** - reference scenario 5

Examples

- `$Scenario.next.code`

Returns the code of the scenario following the one specified in the filter.

- `$Scenario.prev.code`

Returns the code of the scenario prior to the one specified in the filter.

- `$Scenarioref1.code`

Returns the code of reference scenario 1 specified in the filter.

- `$Scenario.next.next.desc`

Returns the description of the scenario following the scenario following the scenario specified in the filter.

- `$Scenario.prev.ref1.desc`

Returns the description of reference scenario 1 of the scenario prior to the one specified in the filter.

The NumCopia attribute

Element	Description
Availability	From 3.1109
Syntax	*numCopia*
Attributes	• code • desc
Value returned	Version of the snapshot scenario

Example

With an original 2012ACT scenario for which three snapshot scenarios are defined:

- Version 01: 2012ACT_V1
- Version 02: 2012ACT_V2
- Version 03: 2012ACT_V3

If scenario 2012ACT_V2 is used in the filters, then the `$Scenario.numCopia` syntax returns string "2".

The Opening attribute

Element	Description
Availability	From 4.2.0
Syntax	*opening*
Attributes	• *CumulatedDays* • *endDate* • *MonthDays* • *startDate*
Value returned	Given a scenario, it returns the opening scenario/period.

Example

`$Scenario.opening.startdate`

Returns the start date of the opening period.

The OriginalScenario attribute

Element	Description
Availability	From 3.0912
Syntax	*originalScenario*
Parameters	("true/false")

Element	Description
Attributes	• *code* • *desc*
Value returned	If applied to a consolidation scenario, it returns the associated original scenario. If applied to an original scenario, it returns the same scenario.

Example

- `$Scenario.originalScenario.code`
  - Returns the code of the original scenario associated with the consolidation scenario specified in the filter.

    `Scenario.originalScenario("true").code`

Returns the code of the original scenario associated with the consolidation scenario specified in the filter. In the event that the scenario is included in more than one group, it is shown below every group in which it has been inserted.

- `$Scenario.originalScenario("false").code`

Returns the code the original scenario associated with the consolidation scenario specified in the filter.

The OriginalSnapshotScenario attribute

Element	Description
Availability	From 3.0903
Syntax	*originalSnapshotScenario*
Attributes	• *code* • *desc*
Value returned	Given a snapshot scenario, it returns the linked original scenario.

Example

`$Scenario.originalSnapshotScenario.code`

Returns the code of the original scenario linked to the snapshot scenario.

The ScenarioPeriod attribute

Element	Description
Availability	From 3.0912
Syntax	*scenarioPeriod*
Attributes	• *CumulatedDays* • *endDate* • *MonthDays* • *Quarter* • *startDate* ***Note**: the "quarter" attribute is used to refer to the current quarter. In the editor window, it is also possible to navigate between quarters using the offsetSP, firstSP and lastSP functions.*
Value returned	Scenario/period pair associated with the filters on the scenario and period dimensions. Can be applied to both the scenario and the period dimension.

Examples

- `$Scenario.ScenarioPeriod.endDate`

Returns the scenario/period end date associated with the scenario specified in the filter.

- `$Period.ScenarioPeriod.endDate`

Returns the scenario/period end date associated with the period specified in the filter.

- `$Period.ScenarioPeriod.(Period.getLeaf("04")).endDate`

Returns the period end date with code 04.

"Quarter" attribute examples

With scenario "2014" and period "02" as input filters, the following behaviours may take place:

- *quarter.firstSP.endDate*

Returns the date of the last day in the first period of the quarter containing the current period ("31/01/2014").

- *quarter.lastSP.endDate*

Returns the date of the last day in the last period of the quarter containing the current period ("31/03/2014").

- *quarter.offsetSP(1).firstSP.EndDate*

Returns the date of the last day in the first period of the quarter following the current quarter ("30/04/2014").

- *quarter.offsetSP(-1).firstSP.EndDate*

Returns the date of the last day in the first period of the quarter prior to the current quarter ("31/10/2013").

The ScenarioPeriod attribute

Element	Description
Availability	From 5.1.0
Syntax	*scenarioPeriod*
Attributes	• *desc*
Value returned	Description of the period of the scenario specified in the filter

Example

```
$Scenario.scenarioPeriod.Description
```

Returns the description of the period of the specified scenario.

The Periods attribute

Element	Description
Availability	From 5.3.SP14
Syntax	*Periods*
Attributes	• *code* • *desc*
Value returned	List of periods of the scenario specified in the filter

Example

```
$Scenario(@NOME_PARAMETRO).Periods
```

Returns the list of periods of the scenario specified in the filter.

The SnapshotScenarios attribute

Element	Description
Availability	From 3.0903
Syntax	*snapshotScenarios*
Attributes	• *code* • *desc*
Value returned	Set of all snapshot scenarios related to the scenario specified in the filter

Example

```
$Scenario.snapshotScenario.item(1).code
```

Returns the code of the first snapshot scenario related to the scenario specified in the filter.

The Version attribute

Element	Description
Availability	From 3.0912
Syntax	*version*
Value returned	Value of the "Version" field in the scenarios table for the scenario specified in the filter

Example

```
$Scenario.version
```

Returns the version of the scenario specified in the filter.

The Year attribute

Element	Description
Availability	From 3.0912
Syntax	*year*
Value returned	Value of the "Year" field in the scenarios table for the scenario specified in the filter

Example

```
$Scenario.year
```

Returns the year of the scenario specified in the filter.

Description of attributes for the Period dimension

The CertificationDate attribute

Element	Description
Availability	From 3.0912
Syntax	*certificationDate*
Value returned	The entity's submission date

Example

```
$Entity.certificationDate
```

Returns the entity's submission date for the process to which scenarios/periods present in the filter are related.

The DescNumPeriod attribute

Element	Description
Availability	From 3.1109
Syntax	*descNumPeriod*
Value returned	Value of the "Period number" field in the periods table for the specified period

Example

```
$Period.descNumPeriod
```

Returns the number of the period specified in the filter.

The ExchangeRate attribute

Element	Description
Availability	From 3.0912
Syntax	*exchangeRate([scenario],[period],[entity])*
Applicability	Entity or currency
Parameters	• *scenario* (Optional) Scenario code • *period* (Optional) Period code • *entity* (Optional) Entity code
Attributes	• *average* Average FX rate • *final* Final FX rate • *period*: Period average FX rate
Value returned	FX rate of the currency used as the filter or of the entity indicated as the parameter of the function

Examples

- `$Currency.exchangeRate.average`

Returns the average FX rate of the entity currency for the defined scenario/period/entity.

- `$Currency.exchangeRate.final`

Returns the final FX rate of the entity currency for the defined scenario/period/entity.

- `$Currency.exchangeRate.periodic`

Returns the period average FX rate of the entity currency for the defined scenario/period/entity.

- `$Currency.exchangeRate(matrix("MATRIX 1").$Scenario, matrix("MATRIX 1").$Period, matrix("MATRIX 1").$Entity).average`

Returns the average FX rate of the entity currency for the scenario/period/entity defined in "Matrix1".

Offset attribute

Element	Description
Availability	From 3.1109
Syntax	*offset*
Parameters	• *offset* Deviation from the starting period
Value returned	Period obtained based on the period indicated when applying the offset. If the shift is greater than the number of periods present in the scenario, prior or subsequent to the indicated period, the system creates a chain of periods, taking account of the previous and subsequent relationships of the scenarios.

Example

With filter on Period = April and Scenario = 2013ACT and 2012ACT = previous scenario. Scenarios are made up of 12 periods.

- `$Period.offset(-3).code`

Returns the code of the "January" period

- `$Period.offset(-5).code`

Returns the code of the "November" period

The ScenarioOffset attribute

Element	Description
Availability	From 3.1109
Syntax	*scenarioOffset*
Parameters	• *offset* Deviation from the starting period
Value returned	Scenario obtained from the "offset" of the periods indicated in the parameter. Returns the scenario indicated in the filter if the shift does not give rise to scenario offsets.

Example

With filter on Period = April and Scenario = 2013ACT and 2012ACT = previous scenario. Scenarios are made up of 12 periods.

- `$Period.scenarioOffset(-6).code`

Returns the code of the previous scenario (2012ACT)

- `$Period.scenarioOffset (-3).code`

Returns the code of the filter scenario (2013ACT)

The ScenarioPeriod attribute

Element	Description
Availability	From 3.0912
Syntax	*scenarioPeriod*
Attributes	• *CumulatedDays* • *endDate* • *MonthDays* • *startDate*
Value returned	Scenario/period pair associated with the filters on scenario and period dimensions. Can be applied to both the scenario and the period dimension.

Examples

- `$Scenario.ScenarioPeriod.endDate`

Returns the scenario/period end date associated with the scenario.

- `$Period.ScenarioPeriod.endDate`

Returns the scenario/period end date associated with the period.

- `$Period.ScenarioPeriod.(Period.getLeaf("04")).endDate`

Returns the period end date (overridden) with code 04.

Description of attributes for other dimensions

Attributes for the Column form dimension (of a transactional form)

The ColAttribute attribute

Element	Description
Availability	From 3.1109
Syntax	*colAttribute(codAttr)*
Parameters	*codAttr* Attribute code
Value returned	Value of the codAttr attribute associated with the column of a transactional form

Example

`$Formcolonna.colAttribute("XYZ")`

Returns the value of the attribute that has code "XYZ" associated with the current column.

Form attribute

Element	Description
Availability	From 3.1109
Syntax	*form*

Element	Description
Attributes	• *code* • *desc*
Value returned	Form to which the current column belongs

> **Example**
>
> `$Formcolumn.form.code`
>
> Returns the code of the form to which the current column belongs.

Attributes for Measure dimensions

The MeasureType attribute

Element	Description
Availability	From 5.3.4
Syntax	*measureType*
Value returned	Measure type (numeric, date, text)

> **Example**
>
> If the form uses a measure with dimension code "ME_001_000001":
>
> • `$ME_001_000001.measureType`
>
> It returns the measure type indicated in the filter.

Non-dimensional functions

Description

Non-dimensional functions return non-dimensional objects like processes, users or forms.
They present their attributes.

> **Examples**
>
> • `var := User.code;`
>
> Saves, in the "var" variable, the code of the user who ran the form.
>
> • `var := Form.desc;`
>
> Saves, in the "var" variable, the description of the form in use in the language set in the user table.

Description of non-dimensional functions

The Dataprocessing function

Element	Description
Availability	From 3.1106
Syntax	*dataprocessing*
Attributes	• *desc* • *dataprocessingcount*

> **Examples**
>
> • `dataprocessing.desc`

Returns the string "Data Processing in progress", in the user's application language, in the presence of data processing operating on the set of dimensions defined by the form filters, otherwise it returns an empty string.

- `dataprocessing.dataprocessingcount`

Returns the number of data processes in progress on the set of dimensions defined by the form filters.

The Datasource function

Element	Description
Availability	From 3.1103
Syntax	*datasource*
Attributes	• *code* • *desc*

Examples

- `Datasource.code`

Returns the code of the datasource in use.

- `Datasource.desc`

Returns the description of the datasource in use.

The Process function

Element	Description
Availability	From 3.0903
Syntax	*process*([scenario],[period])
Attributes	• *code* • *desc* • *BusinessCycle* • *Scenarios* • *Periods*
Parameters	• *(Optional) scenario: scenario code* • *(Optional) period: period code*

Examples

- `Process.code`

Returns the code of the process on which data entry is carried out. If the form is not run in data entry mode, an error is generated.

- `Process.desc`

Returns the description of the process on which data entry is carried out. If the form is not run in data entry mode, an error is generated.

- `Process($Scenario.code,$Period.code).code`

Returns the code of the process to which scenarios/periods present in the form/tab filter are related. If the scenario-period combination has no related process, this function will generated an error.

- `Process($Scenario.code,$Period.code).desc`

Returns the description of the process to which scenarios/periods present in the form/tab filter are related. If the scenario-period combination has no related process, this function will generated an error.

The BusinessCycle function

Only used as a *Process* attribute. Returns the process submission type.

Element	Description
Availability	From 5.3.11
Syntax	*process.BusinessCycle*
Attributes	• *code* • *desc*
Parameters	No parameter.

Examples

- `Process.BusinessCycle.code`

Returns the process submission type code. For single submission, it returns "U", for scenarios/periods, it returns "S".

- `Process.BusinessCycle.desc`

Returns the description of the process submission type. For single submission, it returns "Single", for scenarios/periods, it returns "Scenario/Period".

The Scenarios function

Only used as a *Process* attribute. Returns a list of the scenarios associated with the process.

Element	Description
Availability	From 5.3.11
Syntax	*process.Scenarios*
Attributes	• *code*
Parameters	No parameter.

Example

`Process.Scenarios.code`

Returns the codes of the scenarios associated with the current process.

Element	Description
Availability	From 5.3.14
Syntax	*process([processo]).Scenarios*
Attributes	• *code*
Parameters	(Optional) process: process code

Example

`Process(@PARAMETRO_PROCESSO).Scenarios`

Returns the codes of the original and consolidation scenarios, associated with the process specified via a dynamic parameter. This function can be inserted in a scenario-type parameter based either on the flat dimension or on a hierarchical dimension.

The Periods function

Only used as a *Process* attribute. Returns a list of the periods associated with the process regardless of the scenario to which they belong (can only be used within DTPs and Parametric Jobs).

Element	Description
Availability	From 5.3.SP14
Syntax	*process.Periods*
Attributes	*code*
Parameters	(Optional) process: process code

Examples

- `Process.Periods`

Returns the codes of the periods associated with the current process.

- `Process(@COD_PROCESSO).Periods`

Returns the codes of the periods associated with the process specified as the parameter.

The Item(n) function

Function only used as a *Scenarios* attribute.

Element	Description
Availability	From 5.3.11
Syntax	*process.Scenarios.Item(n)*
Parameters	*n*: scenario to be targeted, ordered by code from 0 in ascending alphabetical order.
Value returned	Scenario n from among those associated with the process

The ProcessScenarioPeriods function

Function that can be used in the DTP run or Parametric Jobs window.

Element	Description
Availability	From 5.3.SP14
Syntax	*ProcessScenarioPeriods(codProcesso,codScenario)*
Parameters	• *codProcesso*: process code • *codScenario*: scenario code
Value returned	Available (not locked) periods of a scenario belonging to the selected process

Examples

- `ProcessScenarioPeriods("ACT","2019BDG")`

If there is a process with code "ATC" containing a scenario with code "2019BDG", it returns the non-locked periods of the scenario associated with the process.

- `ProcessScenarioPeriods(@COD_PROCESSO,@COD_SCENARIO)`

If a parameter with code @COD_PROCESSO and a scenario-type parameter with code @COD_SCENARIO are selected, and the scenario belongs to the process, it returns the non-locked periods of that specific scenario associated with the process.

The Server function

Element	Description
Availability	From 4.2.1
Syntax	*server*
Attributes	*url*

Example

`Server.url`

Returns the string containing the url of the server to which the client is connected.

The User function

Element	Description
Availability	From 3.0903
Syntax	*user*

Element	Description
Value returned	User who performed the login (current user)
Attributes	• *code* • *desc* • *appLang* ◦ *code* ◦ *desc* ◦ *langIndex* • *tablesLang* ◦ *code* ◦ *desc* ◦ *langIndex*

Examples

- `User.code`

Returns the code of the current user.

- `User.desc`

Returns the description of user.

- `User.appLang.code`

Returns the code of the user's application language.

- `User.appLang.desc`

Returns the description of the user's application language.

- `User.appLang.langIndex`

Returns the whole number by which the user's application language is identified.

- `User.tablesLang.code`

Returns the code of the user's table language.

- `User.tablesLang.desc`

Returns the description of the user's table language.

- `User.tablesLang.langIndex`

Returns the whole number identifying the user's table language.

The Dict function

Element	Description
Availability	From 4.3.2
Syntax	*dict(codVoceDizionario, [language])*
Value returned	String containing the description of the dictionary item identified by *codVoceDizionario*.
Parameters	• *codVoceDizionario*: shared dictionary item code • [*language*] (optional): language in which the dictionary item description is returned (numbers from 0 to 4). If omitted, it returns the description in the language in which the form was run.

The Datasetpartition function

Element	Description
Availability	From 5.3.SP7
Syntax	*DATASETPARTITION(codWorkspace, codDataset, [codProcesso], [codScenario], [codPeriodo], [codAzienda], [codTipologia], [valoreSeMancante])*

Element	Description
Value returned	String containing the Dataset physical partition name identified by the codDataset code and belonging to the workspace with the codWorkspace code. Based on the partitioning type, the other additional parameters need to be specified.
Parameters	• *codWorkspace*. Workspace code • *codDataset*. Dataset code • *codProcesso*. Process code • *codScenario*. Scenario code • *codPeriodo*. Period code • *codAzienda*. Entity code • *codTipologia*. Type code • *valoreSeMancante*. (optional) String returned if the partition does not exist

Particular features for parameters

Parameters can be specified using fixed values (between double inverted commas) or using the dedicated syntax. See "Details of advanced selection scripts for calculating the default value" on page 141.

The values of the parameters, separated by commas, are interpreted based on the position in which they are specified (the first string is interpreted as the Workspace code, the second as the Dataset code, etc.). To omit an optional parameter, specify an empty string in the relative position, between double inverted commas or otherwise.

- With **Dataset not partitioned**: set the first two parameters only. If specified, the other parameters will be ignored by the system.
- With **Dataset partitioned by Business Cycle**: also specify the Process. If the Process is submission by Scenario/Period, the Scenario and Period will also need to be specified, otherwise the *codScenario* and *codPeriodo* parameters are optional and will be ignored by the system if specified. If the process is single submission, only the Process needs to be specified, in addition to the reference dataset and workspace.
- With **Dataset partitioned by Business Cycle and Entity**: specify the Process and Entity. If the chosen Process is submission by Scenario/Period, the Scenario and Period will also need to be specified, otherwise the *codScenario* and *codPeriodo* parameters will be ignored by the system. These parameters must in any case be set, but this can be done using an empty value.
  If the **dataset is partitioned by entity**, then the entity must be specified.
  If some parameters are not specified because they are not required by the partitioning type, then they will be ignored. When such parameters are not necessary, the user can avoid specifying them, using several consecutive commas (as many as there are parameters to ignore) or empty strings.

To access data of a different type from the Reporting Layer: also specify the type parameter, in addition to the various parameters for the partitioning type used.

In general, access to a calculation type requires the user to specify the Entity (or the node of Entities - hierarchy code *pipe*node code) that they want to access: to dynamically resolve the lowest level element or the Entity node of the context, the entity parameter can be specified with the following syntax:
`if($Entity.isleaf,$Entity.code,$Entity.Dimension.hierarchyCode +"|" + $Entity(False).code)`

For example, it is possible to obtain the partition with DatasetPARTITION("001", "000007", "ACT", "2019ACT", "05", , "TYPOL") of the dataset partitioned by business cycle with code "000007" in the workspace with code "001", given the process is submission by scenario/process, relative to the "ACT" process, period "05" of scenario "2019ACT", with type "TYPOL" but not partitioned by entity. The same behaviour is obtained using the following wording, with the inverted commas: DatasetPARTITION("001", "000007", "ACT", "2019ACT", "05", "", "TYPOL").

If the specified parameters do not identify any partition existing on the system, the cell field will not return an error but an empty string and if this is used in a query as an extraction table then a syntax error message will be returned on reading. If the partition is not present but a value to return in case the partition is missing (*valoreSeMancante* parameter) is specified as the last parameter, then the function will return the value inserted as the parameter.

Examples

- `DatasetPARTITION("001", "000006")`

With a non-partitioned dataset with code "000006" in the workspace with code "001", it returns the name of the single physical partition, if present.

- `DatasetPARTITION("001", "000007", "BUD")`

With a dataset partitioned by business cycle with code "000007" in the workspace with code "001", and given the "BUD" single submission process, it returns the name of the single physical partition related to the "BUD" process, if present.

- `DatasetPARTITION("001", "000007", "ACT", "2019ACT", "01")`

With a dataset partitioned by business cycle with code "000007" in the workspace with code "001", and given the "ACT" scenario/period submission process, it returns the name of the single physical partition, if present, related to the "ACT" process, period "01" of scenario "2019ACT".

- `DatasetPARTITION("001", "000007", process("2019ACT","01"), "2019ACT", "01")`

With a dataset partitioned by business cycle with code "000007" in the workspace with code "001", it returns the name of the single physical partition, if present, related to period "01" of scenario "2019ACT" and to the process to which the scenario-period combination is related. That process is returned by the "process("2019ACT","01")" function.

- `DatasetPARTITION("001", "000008", "BUD", "", "", "CORP")`

With a dataset partitioned by business cycle - entity with code "000008" in the workspace with code "001", and given the "BUD" single submission process, it returns the name of the single physical partition, if present, related to the "BUD" process, entity "CORP".

- `DatasetPARTITION("001", "000008", "ACT", "2019ACT", "01", "CORP")`

With a dataset partitioned by business cycle - entity with code "000008" in the workspace with code "001", and given the "ACT" scenario/period submission process, it returns the name of the single physical partition, if present, related to the "ACT" process, period "01" of scenario "2019ACT", entity "CORP".

- `DatasetPARTITION("001", "000008", process("2019ACT","01") , "2019ACT", "01", "CORP")`

With a dataset partitioned by business cycle with code "000007" in the workspace with code "001", it returns the name of the single physical partition, if present, related to entity "CORP", period "01" of scenario "2019ACT" and to the process to which the scenario-period combination is related. That process is returned by the "process("2019ACT","01")" function.

```
DatasetPARTITION("001", "000007", "ACT", "2019ACT", "05", , , "TGK_DUAL")
```

With a dataset partitioned by business cycle with code "000007" in the workspace with code "001", and given the "ACT" scenario/period submission process, related to the "ACT" process, period "05" of scenario "2019ACT", and no partition has been generated for that scenario/period pair, then it returns the text reported as the last "TGK_DUAL" parameter.

Non-dimensional attributes

Description

Non-dimensional functions related to forms and reports have attributes that make it possible to obtain information on those objects.

The non-dimensional attributes of forms and report lists are described below.

The Code attribute

Element	Description
Availability	From 3.0912
Applicability	Non-dimensional "form" object
Syntax	*code*
Value returned	String with the code of the current form

Example

```
report.code
```

Returns the current form code.

The Desc attribute

Element	Description
Availability	From 3.0912
Applicability	Non-dimensional "form" object
Syntax	*desc([language])*
Parameters	*language* (optional) Code of the table language indicated as a whole number
Value returned	String with the description of the current form. The optional parameter is only supported with multiple descriptions. If omitted, the user language is used.

Example

```
report.desc(2)
```

Returns the description of the current form in table language 2.

The Path attribute

Element	Description
Availability	From 4.2.0
Applicability	Non-dimensional "form" object
Syntax	*Path([level], [separator])*
Parameters	• *level* (optional) The number of levels to go up in the form group. If omitted or zero, it goes to the root of the group • *separator* (optional) Separator to be used between each element in the string. Of omitted, a backslash "\" is used
Value returned	String obtained from the concatenation of expressions defined on the nodes of the current element's path.

Example

With a form related to the "DE - Data Entry" \ "CE - Profit And Loss" nodes of form group "$":

- `Report.path`

Returns the string "$\DE\CE".

- `Report.path(2)`

Returns the string "DE\CE".

- `Report.path(".")`

Returns the string "$.DE.CE".

The ReportFile attribute

Element	Description
Availability	From 4.2.1 (SP20)
Syntax	*reportFile*
Attributes	• *filename* • *filepath* • *fullName*
Value returned	If the current form is an ad hoc form, it returns some information related to the file on disk containing the form structure. If the form is shared, it returns an empty string.

Example

To find out whether a form is ad hoc:

```
if(report.reportFile.filename="", "Form shared", "Form Ad hoc")
Report.reportfile.filename
```

Returns:

- the string "myReport.xlsx" for "myReport.xlsx" ad hoc forms,
- an empty string for shared forms,
- "book1" for ad hoc forms that have not yet been saved.

`Report.reportfile.filepath`

Returns:

- the string "C:\Users\Username\Documents" string for "myReport.xlsx" for "myReport.xlsx" ad hoc forms saved in the user's documents folder,
- empty string for shared forms,
- an empty string for ad hoc forms that have not yet been saved.

`Report.reportfile.fullFileName`

Returns:

- the string "C:\Users\Username\Documents\myReport.xlsx" for "myReport.xlsx" ad hoc forms saved in the user's documents folder,
- empty string for shared forms,
- "book1" for ad hoc forms that have not yet been saved.

The RunDate attribute

Element	Description
Availability	From 3.0903
Syntax	*runDate([dataFormat],[timeFormat])*
Parameters	• *dataFormat*: can take one of the following values: ◦ -1: no format. The date is not printed ◦ 0: the Full format is used ◦ 1: the Long format is used ◦ 2: the dd-mmm-yyyy format is used ◦ 3 (or omitted): the Short format is used • *timeFormat*: can take one of the following values: ◦ -1 (or omitted): no format. The date is not printed ◦ 1: the Full format is used ◦ 2: the Long format is used ◦ 3: the hh.mm format is used
Value returned	Date and time at which the form was run in the time zone of the application server. Poiché l'attributo RunDate è valorizzato in base al contesto di esecuzione del form, è possibile che data e ora risultino differenti quando il form viene eseguito dal Web rispetto all'esecuzione tramite Excel Add-in. Optionally, it is possible to specify one format type for the date and one for the time. Effective formatting also will depend on the user's local formatting.

Example

A form run on 15 March 2013 at 15:27 with format setting = "Italian".

- `report.runDate`

Returns 15/03/13.

- `report.runDate(0)`

Returns Friday 15 March 2013.

- `report.runDate(1)`

Returns 15 March 2013.

- `report.runDate(2)`

Returns 15-Mar-2013.

- `report.runDate(1,1)`

Returns 15 March 2013 15.27.59 GMT+01:00.

- `report.runDate(1,2)`

Returns 15 March 2013 15.27.59.

- `report.runDate(1,3)`

Returns 15 March 2013 15.27.

- `report.runDate(-1,2)`

Returns 15.27.59.

The Code attribute

Element	Description
Availability	From 3.0912
Applicability	Non-dimensional "ReportList" object
Syntax	*code*
Value returned	String containing the code of the form containing the Report list

Example

`ReportList.code`

Returns the form code of the current Report list.

The Desc attribute

Element	Description
Availability	From 3.0912
Applicability	Non-dimensional "ReportList" object
Syntax	*desc([language])*
Parameters	• *language* (optional) Code of the table language indicated as a whole number
Value returned	String containing the description of the form containing the Report list. The parameter is only supported with multiple descriptions. If omitted, the user language is used

Example

`ReportList.desc`

Returns the description of the report containing the current report list.

The ReportListFile attribute

Element	Description
Availability	From 4.2.1 (SP20)
Syntax	*ReportListFile*
Attributes	• *filename* • *filepath* • *fullName*
Value returned	Form containing the current Report list. In the absence of a containing form, with the report list therefore created "on the fly", an error will be generated. Can only be used with parametric expressions inserted in the Report list creation wizard.

Example

`${reportList.reportListFile.filePath}\myOutput.xlsx`

Defines a "myOutput.xlsx" file in the same folder as the Report list structure as the output file of a report list.

`ReportList.reportListfile.filename`

Returns:

- the string "myReportList.xlsx" for "myReportList.xlsx" report lists,
- an empty string for report lists saved in the table,
- the string "book 1" for ad hoc report lists that have not yet been saved.

```
ReportList.reportListFile.filePath
```

Returns:

- "C:\Users\Nomeutente\Documents" for "myReportList.xlsx" report lists saved in the user's documents folder,
- an empty string for reports run in the table,
- an empty string for ad hoc reports that have not yet been saved.

```
Report.reportfile.fullFileName
```

Returns:

- "C:\Users\Username\Documents\myReportList.xlsx" for "myReportList.xlsx" report lists saved in the documents folder,
- an empty string for reports lists saved in the table,
- "book 1" for ad hoc report lists that have not yet been saved

Location functions

Description

Location functions allow you to access specific positions in a form (e.g. a row, a column, a matrix). They are used in combination with dimensional functions.

Example

```
var := row("MATRIX 1", 10). $Entity.code
```

Saves, in the "var" variable, the entity code defined in row 10 of "MATRIX1".

Description of location functions

The Column function

Element	Description
Availability	From 3.0912
Syntax	*Column(MatrixCode, ColumnNumber)*
Parameters	• *MatrixCode* Matrix code written between inverted commas • *ColumnNumber* Column number of the matrix
Value returned	Column "ColumnNumber" of the matrix with code "MatrixCode"

Example

```
column("MATRIX 1", 10).$Entity.code
```

Returns the code of the entity present in column 10 of "MATRIX1"

The Matrix function

Element	Description
Availability	From 3.0912
Syntax	*Matrix(MatrixCode)*
Parameters	• *MatrixCode* Matrix code written between inverted commas
Value returned	Reference to the matrix filters of the matrix with code "MatrixCode"

Example

`matrix("MATRIX 2").$Entity.code`

Returns the code of the entity present in the matrix filters of the matrix with code "MATRIX 2".

The Parameter function

Element	Description
Availability	From 3.0912
Syntax	*Parameter(ParameterCode)*
Parameters	• *ParameterCode* Parameter code written between inverted commas
Value returned	Reference to the parametric filter with code "ParameterCode"

Example

`parameter("S01").$Scenario.code`

Returns the code of the scenario associated with the parametric filter with code "S01".

The ParameterValue function

Element	Description
Availability	From 3.1012
Syntax	*ParameterValue*
Value returned	The value of a parameter

Example

`parameter("PP").parameterValue`

Returns the value of parameter "PP".

The PositionIndex function

Element	Description
Availability	From 3.0912
Syntax	*PositionIndex*
Value returned	Current sheet for cell fields, queries, data processing or deployment. Current row or column for conditional formatting expressions

Example

`positionIndex.$Scenario.code`

Returns the code of the scenario associated with the sheet, e.g. when the scenario is inserted as a tab filter.

The PrintFilters function

Element	Description
Availability	From 4.2.1
Syntax	*printFilters([Position],[cellField 1],[cellField 2],...,[cellField N])*
Parameters	• *Position* (optional) Reference to a position via location function • *cellField1,...,cellField N* (optional) List of field attributes for every filter, must be written between inverted commas
Value returned	String obtained by concatenating the field attributes. The separator between two fields of a filter is "-" (dash between two spaces) and the separator between two filters is "," (comma followed by space)

Examples

- `Sheet(1).Printfilters`

Returns the concatenation between code and description of the filters of the first sheet.

- `PrintFilters(row("MATRIX1", "5"),"code", "attribute1")`

Returns the concatenation between code and attribute 1 of the filters on row 5 of MATRIX 1.

The Prompt function

Element	Description
Availability	From 3.0912
Syntax	*Prompt*
Value returned	Reference to dynamic global filters for the VBA client (also left compatible for the .NET client)

Example

```
prompt.$Scenario.code
```

Returns the code of the scenario associated with the dynamic global filters.

The ReportFilters function

Element	Description
Availability	From 3.1006
Syntax	*reportFilters*
Value returned	Reference to the form filters for .NET Client Reporting.

Example

```
reportFilters.$Scenario.code
```

Returns the code of the scenario associated with the form filters.

The Row function

Element	Description
Availability	From 3.0912
Syntax	*Row(MatrixCode, RowNumber)*
Parameters	• *MatrixCode* Matrix code between inverted commas • *RowNumber* Matrix row number
Value returned	Row "RowNumber" of the matrix with code "MatrixCode"

Example

```
row("MATRIX 1", 10).$Entity.code
```

Returns the entity code of row 10 of the matrix with code "MATRIX1".

The Sheet function

Element	Description
Availability	From 3.0912
Syntax	*Sheet*
Parameters	*sheet* Sheet number between inverted commas
Value returned	Reference to the "sheet" sheet

Example

```
Sheet("13").$Scenario.code
```

Returns the scenario code read from sheet 13.

Aggregation structure navigation functions

Description

Navigation functions allow you to move within an aggregation structure to obtain an object or set of objects.

Examples

- `var := this.lowest;`

Saves, in the "var" variable, the lowest level elements (leaves) of the node on which advanced selection has been defined. Has the same outcome as "Insert lowest level elements".

- `var := this.lowest.parent;`

Saves, in the "var" variable, the parent nodes of the lowest level elements (leaves) of the node on which advanced selection has been defined.

- `var := this.children.onlyLeafs;`

Saves, in the "var" variable, the elements related to the node on which advanced selection has been defined.

Description of aggregation structure navigation functions

The Parent function

Element	Description
Availability	From 3.0903
Syntax	*parent*
Value returned	Parent node of the element or node on which advanced selection has been defined

Example

`$Entity.parent.code`

Returns the code of the parent node of the entity specified in the filter.

The Children function

Element	Description
Availability	From 3.0903
Syntax	*children([scenario],[period])*
Scenario	• *scenario* (optional) Scenario code • *period* (optional) Period code
Value returned	Elements and/or child nodes of the node to which the function is applied. If the function is applied to an element and not a node, it returns the element.

Examples

- `$Entity.children`

Returns the child elements of the node of the specified entity hierarchy.

- `$Entity.children(2013ACT,03)`

Returns the child elements of the node of the time-dependent entity hierarchy specified for period 03 of scenario 2013ACT.

The Lowest function

Element	Description
Availability	From 3.0903
Syntax	lowest*[scenario],[period],[restrictions]*
Parameters	• *scenario* (optional) Scenario code • *period* (optional) Period code • *restrictions* (optional) These "partialise" the result of the deployment based on the filters in place. They can be activated or deactivated. The syntax for activating or deactivating them is the following: *"nomeLimitazione1:=TRUE|FALSE;nomeLimitazione2:=TRUE|FALSE;..."* Restrictions that are not specified are deactivated by default. The following restrictions are available: • *EntityAccountCustomNLim* (e.g. EntityAccountCustom1Lim, EntityAccountCustom2Lim, ...). Restrictions between Entity/Custom dimension N and between Account/Custom dimension N • *CounterpartyAccountCustom2Lim*. Restrictions between Counterparty Entity/Custom dimension 2 and between Account/Custom dimension 2 • *IntersectionLim*. Intersection of filters in place
Value returned	Lowest level elements of the node to which the function is applied. If it is applied to an element instead, it returns the element.

Examples

- `$Entity.lowest`

Returns the lowest level elements of the node of the entity hierarchy specified in the filter.

- `$Entity.lowest(2013ACT,03)`

Returns the lowest level elements of the node of the time-dependent entity hierarchy specified in the filter for period 03 of scenario 2013ACT.

- `$Entity.lowest(EntityAccountCustom1Lim := FALSE;IntersectionLim := FALSE)`

Returns the lowest level elements of the node of the entity hierarchy specified in the filter not considering the restrictions between entity and custom dimension 1. Ignores possible filters on the entity dimension originating from other hierarchies.

The Root function

Element	Description
Availability	From 3.0903
Syntax	*root*
Value returned	Root of the hierarchy to which the node or element belongs

Example

`$Entity.root.code`

Returns the code of the root node of the entity hierarchy specified in the filter.

The All function

Element	Description
Availability	From 3.0903
Syntax	*all*
Value returned	Nodes and lowest level elements of the dimension specified in the filter

Example

`$Entity.all.code`

Returns the codes of all lowest level elements and nodes of the entity hierarchy specified in the filter.

The Ancestor function

Element	Description
Availability	From 3.0903
Syntax	*Ancestor(ancestorLevel)*
Parameters	*ancestorLevel* Level of hierarchy
Value returned	Ancestor level *ancestorLevel*. If the parameter exceeds the hierarchy root, it returns an empty set.

Examples

- `$Entity.ancestor(1).code`

Returns the code of the parent node of the entity. Ancestor(1) is equivalent to the parent function.

- `$Entity.ancestor(2).code`

Returns the code of the grandparent node of the entity on which it is applied.

The AllAncestors function

Element	Description
Availability	From 3.0903
Syntax	*AllAncestors(ancestorLevel)*
Parameters	*ancestorLevel* Level of hierarchy
Value returned	All ancestors up to the *ancestorLevel*. If the parameter exceeds the hierarchy root, the system returns all ancestor nodes up to the root, inclusive

Example

`$Entity.allancestors(2).code`

Returns the code of the parent node and grandparent node of the entity on which it is applied.

The Descendants function

Element	Description
Availability	From 3.0903
Syntax	*Descendants(descLevel)*
Parameters	*descLevel* Level of hierarchy
Value returned	Descendent levels *descLevel*. If the parameter exceeds the level of the hierarchy's lowest level elements, the system returns an empty set

Examples

- `$Entity.descendants(1).code`

Returns the codes of the elements and/or child nodes of the node of entities on which it is applied. Descendants(1) is equivalent to the children function.

- `$Entity.descendants(2).code`

Returns the codes of the elements and/or grandchild nodes of the node of entities on which it is applied.

The AllDescendants function

Element	Description
Availability	From 3.0903
Syntax	*AllDescendants(descLevel)*

Element	Description
Parameters	*descLevel* Level of hierarchy
Value returned	All descendants up to the *descLevel* level. If the parameter exceeds the level of the hierarchy's lowest level elements, the system returns all the descendant nodes and leaves up to the lowest level elements, inclusive.

Example

```
$Entity.alldescendants(2).code
```

Returns the codes of the elements and/or child and grandchild nodes of the node of entities on which it is applied.

The Complementary function

Element	Description
Availability	From 3.0903
Syntax	*Complementary(ancestorLevel)*
Parameters	*ancestorLevel* Level of hierarchy
Value returned	Complementary elements of the element present in the filter, calculated in relation to the ancestor node specified by the *ancestorLevel* parameter.

Example

```
$Entity.complementary(1).code
```

Returns the codes of the entities belonging to the sub-tree of the parent node of the entity specified in the filter.

The Siblings function

Element	Description
Availability	From 3.0903
Syntax	*siblings*
Parameters	*ancestorLevel* Level of hierarchy
Value returned	The siblings of the element to which it is applied, including the element itself. If you want to exclude the starting element, you can remove it from the returned set using the difference operator between sets.

Examples

- `$Entity.siblings.code`

Returns the code of the siblings of the element to which it is applied, including the element itself.

- `$Entity.siblings.code - $Entity.code`

Returns the code of the siblings of the element to which it is applied, excluding the element itself.

The OnlyLeafs/OnlyNodes function

Element	Description
Availability	From 3.0903
Syntax	*onlyLeafs, onlyNodes*
Value returned	Only the leaves (lowest level elements) and nodes of the set

Examples

- `$Entity.children.onlyLeafs`

Returns only the leaves from among the children of the current entity node, excluding the nodes.

- `$Entity.children.onlyNodes`

Returns only the nodes from among the children of the current entity node, excluding the leaves.

The GetLeafs/GetNode function

Element	Description
Availability	From 3.0903
Syntax	*getLeaf(code), getNode(code)*
Parameters	• *code.* Code of the leaf and node to be retrieved
Value returned	Leaf or node, with the code indicated as parameter, in the same hierarchy as the node to which the functions are applied

Examples

- `$Entity.getLeaf("10")`

Returns only the leaf with code "10" from among the leaves of the hierarchy to which the current entity belongs.

- `$Entity.getNode("01").lowest`

Returns all the leaves of the node with code "01" of the hierarchy to which the current entity belongs.

- `$Category.getLeaf("C1")`

Returns category C1.

***IMPORTANT**: several nodes could be related in the groupings of a leaf. In such cases, the expression returns leaf duplicates for every node to which it is related. To take one of them, use the trimSet function.*

- `$Category.getLeaf("C1").trimSet(1).code`

Returns only the first occurrence of the leaf with code C1

The IsLeaf function

Element	Description
Availability	From 3.0903
Syntax	*isLeaf*
Value returned	1 if it is a leaf, otherwise 0. If the function is applied to a set with more than one element, the system returns an error

Example

`$Entity.isLeaf`

Returns 1 if the entity dimension is a leaf.

The Level function

Element	Description
Availability	From 3.0903
Syntax	*Level*
Value returned	Whole number indicating the level of nesting within the hierarchy. The root of a hierarchy is level 1, its children are level 2, etc. This function is useful for applying different formatting to the levels of a hierarchy with conditional expressions via a style sheet. From version 1109P, the function returns the value 0 if applied to: • row or column placeholders • "+" rows/columns created automatically when the possibility of inserting new elements in data entry is enabled

Example

`$Entity.level`

Returns 3 if the entity dimension is a leaf of a child node of the hierarchy root.

The This function

Element	Description
Availability	From 3.0903
Syntax	*this*
Value returned	Node specified in the row/column filters tree to which advanced selection has been applied

Example

`this.lowest`

Returns the leaves of the node used as the row/column filter on which advanced selection has been defined.

The Select function

Element	Description
Availability	From 3.0903
Syntax	• *select* (field, operator, value) • *select* (condition)
Parameters	• *field* Dimensional attribute (can be managed using string manipulation functions) to be compared with *value* • *operator* Comparison logic operator • *value* String or variable to be compared with *field* • *condition* Logical expression that returns a true/false result for every element of the set to which the formula is applied. If it is necessary to use inverted commas within the string expression, use the constant QT.
Value returned	Elements of the set that satisfy the condition defined via the three parameters (field, operator, value) or a single parameter (condition)

Examples

- `$Entity.lowest.select("$Entity.attribute1", "=", "A")`

Returns the leaves of the starting node that have "A" as the value of attribute 1.

- `$Entity.children.select("$Entity.lowest.size > 3")`

Returns the children of the starting node that have more than 3 leaves related.

- `$Entity.children.select("LEFT($Entity.code,3)=" + QT + "000" +QT)`

Returns the children of the starting node with a code starting with "000".

The Sort function

Element	Description
Availability	From 3.0903
Syntax	*sort(expression, ["DESC"])*
Parameters	• *expression* Expression on the basis of which to run sorting • *"DESC"* (optional) The predefined sorting is ascending; it becomes descending if "DESC" is specified
Value returned	List of the elements of the set sorted according to the *expression* parameter

Examples

- `$Entity.children.sort("$Entity.attribute1"`

Sorts the children of the entity filter in ascending order based on the custom 1 attribute.

- `$Entity.children.sort("$Entity.attribute1", "DESC")`

Sorts the children of the entity filter in descending order based on the custom 1 attribute.

- `$Entity.children.sort("$Entity.children.size" , "DESC").sort( "$Entity.attribute1")`

Sorts the children of the entity filter in ascending order based on the custom 1 attribute. If the value of attribute 1 remains the same, it sorts the number of children of the involved elements in descending order.

The SetEditability function

Element	Description
Availability	From 3.0903
Syntax	• *setEditability(editMode, field, operator, value)* • *setEditability(editMode, condition)*
Parameters	• *editMode* Editability type to be assigned to elements. It can be set to "editable" or "e", "protected" or "p" and "readonly" or "ro" • *field* Dimensional attribute (can be managed using string manipulation functions) to be compared with *value* • *operator* Comparison logic operator • *value* String or variable to be compared with *field* • *condition* Logical expression that returns a true/false result for every element of the set to which the formula is applied. If inverted commas need to be used in the string, use the constant QT
Value returned	Assigns the specified editability type to the elements of the set that satisfy the condition defined via the three parameters (field, operator, value) or a single parameter (condition). Editability can only be overridden in accordance with the following rules: • If the starting node has been indicated as "not specified" or "editable" in the Matrix Wizard, it can be overridden with any editability type • If the starting node is indicated as "protected", it can only be made non-editable • If the starting node has been indicated as "not editable", its editability cannot be changed using this function.

Examples

- `myAccountsSet.setEditability("readonly", "LEFT($Account.code,3)", "<=", "000")`

Makes the accounts of the set whose codes starts with "000" non-editable.

- `myAccountsSet.setEditability("readonly", "$Account.code.length <= 5")`

Makes the accounts of the set whose code has less than 5 characters non-editable.

The OrFilter function

Element	Description
Availability	From 3.0903
Syntax	*orFilter(element1, element2, ... elementN)*
Parameters	• *element1* Will form part of the final filter. Can be defined as a string between inverted commas or dimensional function • *element2* As above
Value returned	A single filter obtained by combining, with OR relationships, elements processed as parameters. If one of the parameters is a set, OR relationships are established among all elements of the set.

Examples

- `OrFilter($Entity.getLeaf("01"), $Entity.getLeaf("02"))`

Establishes an OR relationship between entities 01 and 02.

- `OrFilter($Entity.children)`

Establishes an OR relationship among the children of the node of the entity hierarchy to which it is applied.

Can also be written as: $Entity.children.orFilter().

The ContainedFilter function

Element	Description
Availability	From 3.0903
Syntax	*containedFilters(orFilter)*
Parameters	*orFilter* Filter made up of a set of filters combined using OR relationships
Value returned	The inverse orFilter function. Returns the set of OR filters in the filter processed as a parameter

Example

```
$Dest1.containedFilters.lowest.code
```

Takes the OR clauses and obtains the originally involved lowest level elements from them.

The SyntheticSchema function

Element	Description
Availability	From 3.0903
Syntax	*syntheticSchema(FSTCode)*
Parameters	*FSTCode* Schema or FST item code
Value returned	Schema or FST item shown in synthetic mode

***IMPORTANT**: prevent 'partialising' the result of this script with the select functions and similar functions. If the script only returns some of the elements, some formulas present in certain FST items may be targeting elements that are not returned and this could be generating an error in the run step.*

Example

```
SyntheticSchema(@SP)
```

Generates the synthetic schema specified as the value of parameter SP.

The AnalyticalSchema function

Element	Description
Availability	From 3.0903
Syntax	*analyticalschema(FSTCode)*
Parameters	*FSTCode* Schema or FST item code
Value returned	Schema or FST item shown in synthetic mode

***IMPORTANT**: prevent 'partialising' the result of this script with the select functions and similar functions. If the script only returns some of the elements, some formulas present in certain FST items may be targeting elements that are not returned and this could be generating an error in the run step.*

Example

```
AnalyticalSchema(@SP)
```

Generates the analytical schema specified as the value of parameter SP.

The ControlGroup function

Element	Description
Availability	From 3.0903
Syntax	*controlGroupcontrolgroupCode*
Parameters	*controlgroupCode* Control group code
Value returned	Control group detailed in the accounts

Example

```
ControlGroup(@CG)
```

Generates details of the control group specified as the value of parameter CG.

FromHierarchy

Element	Description
Availability	From 3.0903
Syntax	*fromHierarchy(hierarchy_code)*
Parameters	• *hierarchy_code* Hierarchy code
Value returned	The same element to which the function is applied but taking it from the hierarchy specified as the parameter

Example

With a "Geographical area" hierarchy with code "AG" on the entity dimension and with a form filtered on another hierarchy, the geographical area to which the entity belongs can be obtained even if the "Geographical hierarchy" has not been used in the form.

- `$Entity.fromHierarchy("AG")`

Returns the same element used a s a filter but read by the "AG" hierarchy.

***IMPORTANT**: if it is a node and there is no node with the same code in the "AG" hierarchy, the system will return a warning and the cell will not be calculated.*

- `$Entity.fromHierarchy("AG").parent.code`

Returns the code of the node of the "AG" hierarchy to which the entity specified in the filter is related.

Excel functions

Description

These are Excel functions that can be used in the script's TGKML syntax. They are usually used to manipulate the content of a variable.

Example

```
var := LEFT($Entity.code, 1);
```

Saves, in the "var" variable, the first character of the entity code specified in the filter

Logical functions

Element	Description
AND(condition1, condition2...)	AND logic
OR(condition1, condition2...)	OR logic
NOT(condition)	Negation
IF(condition, Truevalue, Falsevalue)	Conditionlogic

Aggregate functions

Element	Description
SUM(argument1, argument2, ...)	Sum
AVERAGE(argument1, argument2, ...)	Average value
MAX(argument1, argument2, ...)	Maximum value
MIN(argument1, argument2, ...)	Minimum value
COUNT(argument1, argument2, ...)	Number of elements contained
PRODUCT(argument1, argument2, ...)	Value produced by multiplying the arguments
SUBTOTAL (function, argument1, argument2, ...)	Only supported in row/column/sheet formulas. Supports the following functions: • 1 - arithmetic mean • 2 - numbers count • 4 - max • 5 - min • 6 - product • 9 - sum Sum of specified arguments

Other arithmetic functions

Element	Description
SIGN(value)	Returns -1 for positive values, 1 for negative values
ABS(value)	Absolute value
MOD(dividend, divisor)	Rest of the division
INT(value)	Rounding down
ROUND(value, figure)	Rounding

String manipulation functions

Element	Description
CONCATENATE (argument1, argument2, ...)	Concatenation of strings. Equivalent to "String 1" + "String 2" + "String 3" ...
FIND(text, string, [start])	Excel's "Find" function
LEFT(text, numberCharacters)	Returns the number of characters indicated starting from the start of the string.
LEN(text)	Returns the length of the string.
LOWER(text)	Changes the text to lowercase.
UPPER(text)	Changes the text to uppercase
MID(text, start, numberCharacters)	Excel's "Extract String" function
SUBSTITUTE(text, occurrence, substitution)	Excel's "Substitute" function
REPLACE(text, start, numberCharacters, substitution)	Excel's "Replace" function
RIGHT(text, numberCharacters)	Returns the number of characters indicated starting from the end of the string.
REPT(text, times)	Excel's Repeat function
TRIM(text)	Excel's "Delete spaces" function
SEARCH(text, string, [start])	Excel's "Find" function (without distinction between uppercase and lowercase)
VALUE(text)	Changes the specified text into numeric text. Excel's "Value" function

Error management functions

Element	Description
ERR()	Error expression
IFERROR(expression, value)	Returns the processed value if the expression is an error expression, otherwise it returns the expression itself.
ISERROR(expression)	Returns 1 if the expression is an error expression, otherwise it returns 0.

Functions on sets

Description

Some functions, usually those used to navigate trees of aggregation structures, return sets of elements on which the user can operate with specific functions and operators.

The And function

Element	Description
Availability	From 3.0903
Syntax	* or &
Value returned	Intersections between sets

> ### Example
>
> ```
> $Category.getNode("01").lowest * $Category.getNode("02").lowest
> ```
>
> Returns the set made up of the lowest level elements simultaneously related to nodes "01" and "02" of the categories group.

The Or function

Element	Description
Availability	From 3.0903
Syntax	+ or /
Value returned	Union between sets. Duplicates are deleted.

> ### Example
>
> ```
> $Entity.allAncestors(2) + $Entity.children
> ```
>
> Returns the set made up of the parent, grandparent and children of the current node.

The Complement function

Element	Description
Availability	From 3.0903
Syntax	-
Value returned	Difference between sets (complementary set)

> ### Example
>
> ```
> $Entity.allDescendants(5) - $Entity.children
> ```
>
> Returns all descendants up to the fifth level, excluding the children of the entity node to which it is applied.

The Contains function

Element	Description
Availability	From 3.0903
Syntax	*contains(element)*
Parameters	*element*: element to be searched for in the set, defined as a string between inverted commas or dimensional function
Value returned	1 if the *element* parameter belongs to the set, otherwise 0.

Example

`Entity.lowest.contains($Entity.getLeaf("A01"))`

Returns 1 if the descendants of the entity node include entity "A01", otherwise it returns 0.

The Item function

Element	Description
Availability	From 3.0903
Syntax	*item(index)*
Parameters	*index*: index identifying the element belonging to the set
Value returned	Element of the set with index specified as a parameter (0-based). Returns an error if the set has an index lower than the indicated index+1 children.

Example

`$Entity.children.item(0)`: returns the first child of the node of entities.

`$Entity.children.item(1)`: returns the second child of the node of entities.

The Err() function

Element	Description
Availability	From 4.3.1
Syntax	*err()*
Value returned	Always returns an error.

The Iserror function

Element	Description
Availability	From 4.3.1
Syntax	*iserror(argument)*
Parameters	*argument*: generic function
Value returned	TRUE if the processed argument is an error, otherwise FALSE.

The Set Function

Element	Description
Availability	From 3.0903
Syntax	*set(element1, element2, ...elementN)*
Parameters	*elemento1* *elemento2* *element<...>*: elements that will form part of the set, defined as a string between inverted commas or dimensional function
Value returned	Creates a set with the parameters processed as elements. ***Note**: if one of the arguments is an error, the system will return a set containing only the elements that do not return errors.*

Example

```
Set($Entity.getNode("C1"), $Entity.getNode("C2"))
```

Set containing nodes C1 and C2 of the entity hierarchy specified in the filter.

The Size function

Element	Description
Availability	From 3.0903
Syntax	*size*
Value returned	Number of elements in the set

Example

```
$Entity.children.size
```

Returns the number of sheets in the node of the entity hierarchy specified in the filter.

The Sum/Intersect function

Element	Description
Availability	From 3.0903
Syntax	*sum(set1, set2, ... set<...>), intersect(set1, set2, ... setN)*
Parameters	*set <...>*: set of objects to be united or intersected with the sets specified in the subsequent parameters.
Value returned	Union and intersection between the sets indicated as parameters

Example

Let us consider two variables, a and b, defined as follows:

```
a := Set($Entity.getNode("C1"), $Entity.getNode("C2"));
b := Set($Entity.getNode("C3"), $Entity.getNode("C4"));
sum(a, b)
```

Returns a set containing nodes C1, C2, C3 and C4 of the entity hierarchy specified in the filter.

The TrimSet function

Element	Description
Availability	From 3.0903
Syntax	*trimSet(numElements)*
Parameters	*numElements*: number of elements, starting with the first, that you want to consider.
Value returned	The first "numElements" of the set. If the set contains fewer elements, they are all returned.

Example

```
$Entity.lowest.trimSet(3)
```

Returns the first three entities belonging to the sub-tree of the entity hierarchy node to which the specified entity belongs.

Hyperlinks

Purpose of the function

Hyperlinks allow you to link several forms belonging to the working application database. They are used for navigation and data entry purposes. For example, they can be inserted in a cockpit to guide access to forms or in an item of a form to allow the user to automatically see the source data of that item. A link can also activate a series of advanced actions, such as saving and printing files, and running macros or data processing.

Characteristics

Hyperlinks appear as hypertextual Excel links and can be positioned on matrix rows/columns or in any of the form's cells which does not contain a data structure (i.e. matrices, queries and cell fields).


They are created from the **Action List Wizard** window by defining the hyperlink and the actions that must be run when the hyperlink is opened, together with the run order. It is possible to define sequential actions or nest one action within another. Nested actions are indicated with the identification number of the action in which they are nested and a decimal number corresponding to the run order.

If a node is selected rather than a single form, all the forms in that node will open when the hyperlink is selected.


***Note**: several actions cannot be run sequentially via hyperlinks from web forms.*

Example

This example shows the **Action List Wizard** window in which the following sequence of actions, to be run once the hyperlink has been selected, was defined: open two reports, run a macro and close the source report.




In this example, in contrast, two **Save** actions have been inserted. Action **1.1 - Save values** is nested in **Open report**. The values contained in form B110_102 are automatically saved when the report is opened. Action **2 - Save values** is not nested. This action saves the values of the source report after actions 1 and 1.1 have been run.




Filters cycle example

This example illustrates how to open the same report for all entities. To do this, first of all a **Filters cycle** action that has those entities as filters must be defined.



Next, the **Open report** action to be nested in **Filters cycle**, the action with which to save the values and the action for closing the report are defined. Thus, each of these actions is repeated four times, once for every entity of the filters set in the **Filters cycle** window.

This cycle works by running the report in data entry mode, as it involves the saving of values.



Hyperlinks in matrices

In matrices, hyperlinks can be positioned in header cells and cells containing values. The definition of the actions that must be run when that hyperlink is opened is the same as the definition described for the links inserted directly in the report. The only differences are as follows:

- If the **Inherit from the source report** option is activated for the **Open report** action, the parameters are inherited from the filters present on the cell in the report in use, from which the hyperlink is opened.

  For example, for a matrix that has several entities on its rows, the report opened from the hyperlink is filtered on the entity present in the row from which the hyperlink was opened. Specifically, if the entity of the first row were A00, the corresponding report would be opened with the filter on entity A00.

- The query of a **Reporting.NET Navigation - Drill-through** action is run according to the filters present in the cell in use, from which the hyperlink is opened.

For more details on the hyperlink settings, see Table of row/column filter properties.

Managing hyperlinks

Open the Action List Wizard window

Excel > CCH® Tagetik > Design > select form >

See Come accedere alle finestre for alternative paths.

There are several ways in which the Action List Wizard window can be opened to create hyperlinks:

- Select a cell and click .
- Right click the desired cell and select **Tagetik** > **New Hyperlink**.
- In the **Open items** tab, right click on the template in which to insert the hyperlink and select **Hyperlink** > **New Hyperlink**.

Create a hyperlink in a cell of the form using Open form

Excel > CCH® Tagetik > Design > select form >

See Come accedere alle finestre for alternative paths.

1. Click the empty cell in which to insert the hyperlink.
2. Open the **Action List Wizard** window. See "Open the Action List Wizard window" on the previous page.
3. In the list of runnable actions, select **Open form** and click : the **Properties: Open form** window will appear showing the forms present in the working application database.
4. Select the desired forms and click **Next**.
5. Set the way in which to value the parameters defined for all the forms selected on opening.
6. If several forms are opened to ad system or ad hoc parameters, select **+ System parameter** or **+ adHoc parameter** as required and repeat step 5.
7. Click **Next**.
8. Indicate the way in which to open the target form and click **OK**: the **Open form** action will be added to the list of actions to be run.

Create a hyperlink to open a form defined in the next row/column

Excel > CCH® Tagetik > Design > select form >

See Come accedere alle finestre for alternative paths.

***IMPORTANT**: in the Excel add-in, the opening of a form in a subsequent row/column can only be configured via hyperlinks. They can only be used in web forms.*

1. Click on an empty matrix cell in which to insert the hyperlink.
2. Open the **Action List Wizard** window. See "Open the Action List Wizard window" on the previous page.
3. In the list of runnable actions, select **Open form specified in the next row/column** and click .
4. Indicate the way in which to identify the target form and click **OK**: the **Open form specified in the next row/column** action will be added to the list of actions to be run.

At runtime, when the hyperlink is clicked, the system will open the form indicated in the cell of the next row/column.

***Note**: the parameters of the target form can only be inherited from the context.*

Using the Filters cycle action

Excel > CCH® Tagetik > Design > (left-hand panel) click form > > Hyperlink (in Design bar)

See Come accedere alle finestre for alternative paths.

1. In the list of runnable actions, select **Filters cycle** and click : the **Properties: Filters cycle** window will appear.
2. Select the desired dimensions on which to filter and click .
3. Click **OK**.
4. Select the actions to be repeated and click .
5. Click **OK**.

Create a hyperlink in a matrix

Excel > CCH® Tagetik > Design > select form > Matrix

1. In the **Choose the dataset** window, click on the desired dataset and on **OK**.
2. Open an existing matrix, or create the matrix structure by inserting the desired filters on the rows and columns.
3. Select the (static or dynamic) row/column on which to insert the hyperlink.
4. In the properties table, click **Hyperlink** and define its properties.

   ***Note**: all the actions listed above can be inserted from the Action List Wizard.*

5. Click **OK**.

Action List Wizard window


Excel > CCH® Tagetik > Design > (left-hand panel) click form > > Hyperlink (in Design bar)

See Come accedere alle finestre for alternative paths.

Purpose of window

This window allows you to create the hyperlink and actions to be run once it has been opened.

What it looks like



Element	Description
A	List of actions that can be run when the hyperlink is clicked
B	List of sorted actions to be run when the hyperlink is clicked

Runnable actions

Element	Description
Open form	Allows you to set the opening rules for one or more target forms via a hyperlink on the source form. See "The Open form window (Action List Wizard)" on the next page.
Open form specified in the next row/column	(Only for web forms 2.0). Allows you to select one or more forms to be run, both in data entry and navigation modes, starting with the next row/column. Thus, a formula that returns the code of the form to be run can be inserted in the next row/column. In this mode, the parameters of the target form can only be inherited from the context.

Element	Description
Save	Automatically saves the values of the target or source form when the user clicks the hyperlink. The form that is saved will depend on the position of the **Save** action in the list of actions to be run. Any data processing to be run on saving, as defined in the form, are run automatically immediately afterwards.
Print	Not supported in web forms. Prints the target or source form on the predefined printer. The position of the **Print** action in the list of actions to be run determines the form to be printed Possible values for setting the print area to be printed by selecting the hyperlink: • **All**: all form content • **Areas**: only the content of the print areas, as defined in the form and indicated by the user • **Print area**: current print area defined for the form
Run macro	Running Visual Basic macros defined in the form. Macros can be run in both the target form and the original form only if the **Run macro** action is nested in a form opening action. Macros are called up in the form by calling up their names. If the **Run macro** action is followed by other actions in the list of actions to be run, then **Run macro** will need to return **True** for those subsequent actions to be run.
Close form	Closes a form when the hyperlink is selected. Depending on its position in the list of actions to be run, it closes the source or target form. It also locks the refresh form request set for other data processing inserted in the same hyperlink. If the form has been edited before the hyperlink is clicked, the form can be saved before closing.
Filters cycle	Not supported in web forms. Allows you to repeat actions for every element of a certain filter. The filter must belong to the same dimension/hierarchy as the parameters defined in the forms recalled by the hyperlink.
Reporting .NET - Navigation - Drill-through	Allows you to runs a drill-through query when the hyperlink is selected. See Query drill-through.
Data processing	Allow you to run data processing defined in the form. The data processing is added to the actions to be run when it is selected with the name that was attributed to it when created. See Elaborazioni lanciate da reporting.

Buttons

Element	Description
	Adds the selected action to the list of actions to be run.
	Removes the selected action from the list of actions to be run.
	Moves the selected action up or down in the run order.
	Allows you to rename the link or change its settings for the selected action
	Nests the action selected from the list of actions to be run within the previous action.

The Open form window (Action List Wizard)

Excel > CCH® Tagetik > Design > (left-hand panel) click form > > Hyperlink > select Open form >

Purpose of window

This window allows you to select one or more forms to be opened via the hyperlink and to set their parameters and the modes in which they are run via the hyperlink.

Window structure

Based on the characteristics of the target form, the window can may show the following:

- Definition of run parameters (only if the selected forms contain run parameters)
- Definition of the mode in which the target form is opened

Options in the definition of run parameters

Option	Description
Inherit from context	The system retrieves the value of the parameter from the filters of the cell from which the hyperlink is opened or from the form/tab filters. *For example, if there are several sheets in a form and a different entity has been defined for each sheet, to open the target form the system uses the entity defined in the sheet from which the hyperlink is opened.* If the hyperlink is contained in a transactional form matrix, the dimensional parameters of the form being run can inherit their value from the row containing the hyperlink and the parameter dimension from the column containing the hyperlink. Values on dimensions with display mode set to **description only** are not inherited.
Inherit parameters	The system retrieves the value of the parameter from the value of the corresponding parameter in the source form. This is only possible if the source form parameters belong to the same dimension and hierarchy as the target form parameters.
Excel Cell	The system retrieves the value of the parameter from an Excel cell. This cell must be specified using the syntax **${*cell coordinates*}**. For example, **${A5}** corresponds to cell A5.
Select	Allows the user to select the value of the parameter from a list of possible values.
Cell field	The system retrieves the value of the parameter from a cell field. For a transactional Analytical Workspace form, the cell field is also calculated considering the dimensional field of the row that has the same dimension as the parameter to be defined. In this case, the dimensional field has priority over form or matrix filters. The only dimension fields considered are the ones that have **code** or **code and description** display mode.
+System parameter	(Only if the hyperlink opens several forms) Allows you to set system parameters that are valid for running all forms.
+AdHoc parameter	(Only if the hyperlink opens several forms) Allows you to set ad hoc parameters that are valid for running all forms.

Options when defining the mode in which the form opens

Option	Description
Data entry	The target form opens in Data Entry mode.
Inherit from the source form	The target form will open in the same mode in which the source form was opened. *For example, if the source form was run in Data Entry mode, the target form will also open in Data Entry mode.*
Navigation	The target form opens in Navigation mode.

Buttons in the window

Element	Description
Next	(Only with forms containing run parameters) Saves the defined run parameters and shows the options for defining the mode in which the target form is run.
Previous	(Only with forms containing run parameters) Saves the settings on the mode in which the target form is opened and shows the options for defining the run parameters.
OK	Saves the settings and closes the window.
Cancel	Closes the window without saving.

Properties Window: Filters cycle


Excel > CCH® Tagetik > Design > (Left-hand panel) click form > > Hyperlink > Filters cycle

Purpose of window

This window allows you to set the actions to be repeated as many times as there are elements of a certain filter.

Options that can be inserted on tab filters can be inserted on option filters. See "Tab filter properties" on page 222 for a list of options.

What it looks like



Element	Description
A	List of available dimensions
B	List of sorted filters to be run
C	Details of selected filter

Buttons

Element	Description
	Changes the display mode.
	Allows you to search for the desired dimension.
	Adds one or several elements or nodes selected in the dimensions tree under the selected node in the filters tree.
	Only with filters already defined, adds one or several elements or nodes selected in the dimensions tree to all filters already defined. ***Note**: if there are no pre-defined filters in the column, it functions like the button.*
	Adds one or several filters selected in the dimensions tree to a selected filter, creating a OR type logical relationship. OR type logical relationships can only be created with elements or nodes belonging to the same dimension as the filters already defined. The added filter is labelled with the concatenation of the individual element codes separated by ",". The value displayed is equal to the sum of the elements entered.

Element	Description
	Adds one or several elements selected in the dimensions tree belonging to the same filter dimension to a node of filters linked by an OR logical relationship. The added filter is labelled with the concatenation of the individual element codes separated by ",". The value displayed is equal to the sum of the elements entered.
	Only with filters already defined. Deletes the selected element or node.
	Only with filters already defined. Deletes the entire level of the selected filter.
	Only with filters already defined. Moves the selected element up one position.
	Only with filters already defined. Moves the selected element down one position.
	Only with filters already defined on several levels. Moves the selected level up one level.
	Only with filters already defined. Replaces en bloc the selected elements of a filter with elements selected in the dimensions tree. Useful for reusing a filter by replacing its elements, but not its properties.
	Shows one or more elements of the filter containing the OR logical relationship, allowing you to see them and move or delete one or more of them.
	(Only for control groups) Adds the control group selected in the dimensions tree to the filter. See I gruppi di controllo: concetti di base.
	(Only for control groups) Adds the control group selected in the dimensions tree to all filters already defined. See I gruppi di controllo: concetti di base.
	(Only for FST items) Analytically adds, under the selected filter, the FST selected in the dimensions tree. See "Financial statement templates" on page 161.
	(Only for FST items) Analytically adds, under all filters, the FST selected in the dimensions tree. See "Financial statement templates" on page 161.
	(Only for FST items) Synthetically enters the FST under the currently selected filter. See "Financial statement templates" on page 161.
	(Only for FST items) Synthetically adds, under all filters, the FST selected in the dimensions tree. See "Financial statement templates" on page 161.
	Allows you to use predefined filters.
	Updates the predefined filters.
	Copies the selected filter or dimension.
	Pastes the copied filter or dimension in all filters.
	Pastes the copied filter or dimension in the selected filter.

Data Entry: introduction

Contents

This section covers the following topics:

Data entry forms 308
Data entry in cells 310
Data entry 311
Particular features of forms 312
Spreading 313
Spreading methods in data entry mode 313
Data entry tracking log 315

Data entry forms

Introduction

Data entry, i.e. entering and editing data in the application database, can be performed via *data entry forms*. These forms can be used both from the web interface and within the Excel add-in, and can also be opened in navigation mode to consult data.

***IMPORTANT**: unless specified otherwise, this section describes how to use the functionalities of data entry forms both within the Excel add-in and from the web interface.*

A data entry form must contain at least one of the following elements:

- cells editable by user (see "Create a data entry matrix for the user" on page 214)
- other formulas (see "Formula filters" on page 237)
- query on cells (see Query)

Data entry in the Excel add-in

Via the Excel add-in, the user has quick access, in Data Entry mode, to the forms for which they are authorised. The following jobs can be performed in the add-in:

Activity	Functionality
Data entry on gross and intercompany amounts, and comments	"Data entry in the Excel add-in" on page 316
Run data entry and submission tasks	"Workflow panel" on page 321

Data entry from web interface

From the web interface, the user can access and work on the data entry forms for which they are authorised from the process cockpit.

Opened...	Description
Directly	In the contributor cockpit: 1. Select the detailed overview tab or one of the step tabs 2. From the **Actions** column, click Forms: forms related to the process/step can be chosen from the list. The form can be run as a web form, if enabled, or as an Excel form.
From workflow	In the contributor cockpit, the user can see the data entry form as content of a task in the process's task workflow. See Sezione Workflow della scheda <fase>. • If the data entry form is enabled for opening on the web, the form will open in the web interface. • If the data entry form is not enabled for opening on the web, it will open in Excel. ***Note**: whether the form is opened from the web or in Excel, the data are synchronised in the application database when the form is saved.*

Conditions for using forms during data entry

Data entry forms have the following particular features:

- The can only be opened in data entry mode using the same filters by one user at a time. A form that has already been opened by a user is locked for other users, who cannot open it until it has been closed by the first user.

  ***Note**: when the form manages Analytical Workspace data only, and the 'Show user data only' option is active in the reference dataset, the form is never locked and it can be opened by several users. Multidimensional matrices do not support the 'Show user data only' dataset property.*

- When a form is open in Data Entry mode, the system automatically applies the filters of the process from which it is launched (e.g., Scenario, Period, Entity). As a result, filter options may be limited or unavailable for selection if they are not linked to the process.
- In editable cells containing numbers or formulas, and with spreading enabled, a maximum of 15 significant figures can be saved and displayed.

  ***Note**: when the fifteenth figure is changed, the system automatically calculates the value and shows a message in the Cell Properties window. If a sixteenth figure is entered, it will be replaced by a zero and will not be saved.*

- Forms built on datasources that use DTP parameters cannot be opened in data entry mode.
- Forms that use a period filter that allows several periods to be selected simultaneously cannot be opened in data entry mode, since data entry cannot manage more than one period at a time.

Data entry forms: cell editability

When designing the data entry form, it is necessary to define which cells are to be made editable, i.e. which cells contain values that can be modified by the user. Every time data is saved in the form, the system performs the following checks:

- The dimension filters set when opening the form for the current cell are single elements of one dimension and not nodes. This condition applies only if break back is enabled on the selected process, which allows data entry at node level (see the Break Back function)
- The user has the rights to edit and save data on the filters selected when opening the form.
- All dimensions indicated as filters, in particular the account, are associated with the application process.
- There are no restrictions among the dimensions defined as form filters.

Cells are editable for users with edit rights only when all conditions are met.

***Note**: to distinguish editable cells from non-editable cells, it is useful to assign a specific colour to editable cells (see "Layout options details" on page 134).*

Data entry data processing

Running data processing from data entry forms allows the user to enter data in the system and run complex calculation algorithms for purposes such as financial planning or consolidation. Data processing is launched using the filters managed in the form as run parameters. For example, in a form in which, for a product, the quantities sold and prices are entered, it is possible to define data processing to calculate revenue based

on these two values (*revenue = quantity * price*). This can be defined in the web interface to then be included in a form and run automatically at the user's request or when the form is saved.

For more details on how to configure data processing to be included in forms, see Elaborazioni lanciate da reporting.

Data entry in cells

Introduction

Data can be entered in editable cells either directly, by typing the data in the desired cell, or using the **Edit cell** function to enter the data in dedicated windows.

Cell edit function

The **Cell edit** function allows you to enter information quicker, through the following windows or pages.

Element	Description
Excel Add-in	• "Cell edit - Amounts window" on page 323 • "Cell edit - comments window" on page 325 • "Cell edit - intercompany window" on page 327
Web interface	"Edit comments page" on page 342

It therefore allows you to enter the following data:

- amounts
- text-based comments and attachments
- intercompany declarations

The specifics for the three types of data are provided below.

Amounts

When the user enters the amounts in a data entry cell on an account, the system considers them to be *amounts*. Those amounts can be of several different types:

Element	Description
Original FS amounts	• Balance sheet • Profit & Loss
Original variation amounts	• Variations that allow you to keep track of account transactions (whether equity, to order or other stock) during the period of time taken into consideration.
Statistical values	For example: quantity, headcount, square metres, et cetera. ***Note**: values typically used as drivers in allocation processes, the creation of indices, (e.g. revenue per passenger on a vessel), and management reporting.*
Gross amount	"Gross" amounts from intercompany declarations, or amounts which also include the intercompany quota.

When a new amount is entered in an editable cell on an account, the system automatically registers an original amount-type figure for which the transaction currency is the same as with the entity currency. The transaction currency of the amount entered can be edited manually from the **Edit Amounts** window (see "Cell edit - Amounts window" on page 323). Amounts edited in this way can be identified in the audit by the note *Inserted by form <form code>*.

Comments

In the data entry phase, editable cells can contain text-based comments. It is also possible to add an attachment to every comment (e.g. justification for an outbound amount).

The conditions for inserting comments and adding attachments to cells of the form are as follows:

- The form must be opened in data entry mode.
- The desired cell must be editable and contained in a matrix.
- The user must have editability rights on the filters set for the desired editable cell.
- If the cell is no longer editable because it contains data that has already been submitted, to insert a comment the user must have function 0004073 active in their own role.

For matrices created on the Financial Workspace and for multidimensional matrices, it is possible to attach one document for each comment. For the Analytical Workspace's transactional matrices, it is possible to attach several documents, which can be given one single shared description.

***Note**: in transactional matrices, the comment is saved in JSON on the partitions table and the attachment is saved in the OWS_LBL_DOCUMENTO table. In multidimensional matrices, the document is saved in the table containing all the documents related to multidimensional matrices.*

Edit comments

Users are only permitted to edit/delete a comments that they inserted themselves, with the exception of users who have a role for which the "Reporting-Data Entry-Comments-Administrator" function, code 0003862, is enabled in the repository. By default, this function is disabled for all users who have the $DEREPORT role.

When a comment is inserted on submitted data, the following conditions must be met:

- A comment inserted on a cell before the data are submitted cannot be edited or deleted after submission.
- When data are rejected, a comment inserted on a cell during the submission phase takes on the pre-submission status and thus becomes editable. When data are resubmitted, the comment become non-editable again.
- A comment inserted on data that have already been submitted can only be edited or deleted if function 0004073 is enabled on the Repository' user roles (see Roles). This function allows comments to be inserted on data submitted on both Line by Line and Multidimensional matrices.

Comments on matrices with conditional editability

For multidimensional matrices on Analytical Workspace and Financial Workspace, it is not possible to insert comments or add attachments on non-editable cells due to unsatisfied editability conditions.

If the user makes the cell editable while satisfying the conditional editability expression, then it becomes possible to edit comments and attachments. However, if, after editing comments or attachments, the user acts on factors of the conditional editability expression, making the cell non-editable again, then the additions, changes or removals made on the comments will be ignored on saving.

***Note**: for datasets created on the version prior to sp16 with transactional matrices containing comments and/or attachments on measure-type fields, these are now contained in the new field "OWS_LBL_COMMENTI". This field is created automatically within the dataset during transition to new versions, starting with sp16. Comments present on measures have all been moved to the single field that has been created. This field must be added to the matrix manually. By adding the new column, comments previously saved on the measures can continue to be viewed and edited.*

Hidden comments

In forms based on nodes or aggregation structures, it is possible to view any comments inserted on individual elements belonging to the node or aggregation structure.

The functionality that allows the user to view hidden comments is not available to all users by default, but only to those who have function "0002963 - Reporting.NET - Navigation - Hidden comments" enabled in the respective role.

Intercompany declarations

If permitted by the account, it is possible to enter intercompany declaration data in the editable cells of forms. A user can only enter or remove intercompany values if they possess editability rights over the entities involved in the declaration. When cell editability is locked, the *Info* button reveals details of the lock.

Data entry

Excel > CCH® Tagetik > Data Entry > open form

Data entry in the work desktop

To enter data, select the desired editable cell and enter the desired data.

Data entry by cell edits

1. Select the editable cell.
2. Click and select the type of data to be entered.
3. Enter the desired data.

For more details, see "Data entry in cells" on page 310.

Data entry in a detail window

***IMPORTANT**: only for transactional matrices in which the details editor is enabled and configured (see "Transactional form editor tab" on page 209).*

1. Select the desired cell: three action buttons appear.
2. Click : a window will open containing details of the column data included in the template.
3. Enter date in the desired cells and click **OK**.

Particular features of forms

Cell editability

When designing the data entry form, it is necessary to define which cells are to be made editable, i.e. which cells contain values that can be modified by the user. Every time data is saved in the form, the system performs the following checks:

- The dimension filters set when opening the form for the current cell are single elements of one dimension and not nodes. This condition applies only if break back is enabled on the selected process, which allows data entry at node level (see the Break Back function)
- The user has the rights to edit and save data on the filters selected when opening the form.
- All dimensions indicated as filters, in particular the account, are associated with the application process.
- There are no restrictions among the dimensions defined as form filters.

Cells are editable for users with edit rights only when all conditions are met.

***Note**: to distinguish editable cells from non-editable cells, it is useful to assign a specific colour to editable cells (see "Layout options details" on page 134).*

See "Cell editability" on page 156.

Paste set of values function

In Excel, this function allows you to copy, using the 'Copy' command, and then paste a set of values. Only areas of adjacent cells can be selected and pasted and any non-editable cells present in those areas will not be considered.

In data entry web forms, the combinations CTRL+C and CTRL+V can be used to copy a block of cells and paste it onto a block of editable cells.
If the copied block contains one or more non-editable cells, these will not be coped. This function can also be used to copy/paste from sources external to the form. However, if a paste a set of values operation has previously been performed in the web form, this will overwrite any subsequent copies from external forms.

Quick search cells

For web form cells containing value selection lists, it is possible to perform quick searches of the list's values directly in the cell. To do this, simply initiate and enter the text to search for.

The text search is performed on the codes or descriptions of the elements in the list, or on both if the selection list contains both codes and descriptions.

The search function does not take differences between uppercase and lowercase or special search characters such as '*' and '?' into account.

Spreading

Purpose of the function

The *spreading* functionality makes it possible to calculate monthly values based on existing annual values processed based on conditions determined by the user. Amounts may be calculated using spreading for forecasting and/or statistical purposes.

Objective	Description
Forecasting	Spreading makes it possible to calculate, based on values collected since the start of the year up until the current month, forecast values for both the remaining months and the entire year. *For example, in a annual forecast data collection form in which data on real sales from January to May is collected, spreading makes it possible to calculate the forecast data on the partial amounts of the remaining months, and therefore the total annual amount.*
Statistical	Spreading makes it possible to manually enter an annual amount and, based on the trends in the data collected over a specific period (e.g. from the start of the year to the current month, or during the previous year, etc.), to calculate amounts to be realised in the remaining months to achieve the desired total annual amount. *For example, in an annual sales planning form, to plan to double sales, the user can enter the desired annual amount and calculate, based on the real monthly amounts from the previous year, the monthly amounts that need to be realised to achieve the desired total in the current year.* In the calculation conditions, spreading also allows you to enter values expressed with a deviation calculation or fraction based on a reference value.

For more details on the spreading calculation functionality, see "Spreading methods in data entry mode" below.

Spreading methods in data entry mode

Introduction

The methods used in the application of the spreading calculation are provided below, with examples.

Examples of the application of spreading on the annual sales volumes forecast

In these examples, the following annual sales volumes for the Antivirus product are present in the database.

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Antivirus	92	90	116	92	92	116	92	92	116	92	92	116	1.200
Total	**92**	**90**	**116**	**92**	**92**	**116**	**92**	**92**	**116**	**92**	**92**	**116**	**1.200**

The sales forecasts for the subsequent year double in value, from 1200 to 2400 units. Details of the provisional data depending on the forecasting method are provided below.

Proportional spreading

Calculates how to subdivide the total value based on the monthly values existing on the application database, namely according to the values with which the form was generated.

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Antivirus	185	180	231	185	185	231	185	185	231	185	185	231	2.400
Total	**185**	**180**	**231**	**185**	**185**	**231**	**185**	**185**	**231**	**185**	**185**	**231**	**2.400**

Uniform spreading

Distributes the total value equally over the number of periods to which the total value refers.

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Antivirus	200	200	200	200	200	200	200	200	200	200	200	200	2.400
Total	**200**	**200**	**200**	**200**	**200**	**200**	**200**	**200**	**200**	**200**	**200**	**200**	**2.400**

4-4-5 / 4-5-4 / 5-4-4 spreading

Distributes the total value over the number of weeks in a month, for quarterly groups. For example, 4-4-5 applied over the quarter from January to March indicates that January and March have 4 weeks, while March has 5 weeks.

The number of weeks in each month depends on the calendar used, for which the system takes account of any months made up of more than 4 weeks, forecasting higher sales in those months. In the example, the volumes of sales in the third month of every quarter (therefore March, June, September and December) are higher than the other months.

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Antivirus	185	185	231	185	185	231	185	185	231	185	185	231	2.400
Total	**185**	**185**	**231**	**185**	**185**	**231**	**185**	**185**	**231**	**185**	**185**	**231**	**2.400**

On the contrary, using the 4-5-4 method, the volumes of sales are higher in the second month than the other months.

Customised spreading

Allows you to specify a customised distribution rule for the total value over the periods. The user freely adds the rule to be used. For example, the following data will be obtained if a 5-4-4-5-4 rule is defined:

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Antivirus	226	181	181	226	181	226	181	181	226	181	226	181	2.400
Total	**226**	**181**	**181**	**226**	**181**	**226**	**181**	**181**	**226**	**181**	**226**	**181**	**2.400**

In the definition window, every weight must be entered after the separator ";".

Spreading based on scenario

Allows you to distribute the new value based on the values present on another scenario, from among those linked to the current scenario, so that the possible seasonal variation of real data can be monitored.

The scenario 2011ACT values are provided below.

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Antivirus	69	69	87	69	69	87	69	69	87	69	69	87	900
Total	**69**	**69**	**87**	**69**	**69**	**87**	**69**	**69**	**87**	**69**	**69**	**87**	**900**

The value distribution of 2400 on scenario 2012BDG, based on the previous scenario 2011ACT values, is as follows:

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Antivirus	185	185	231	185	185	231	185	185	231	185	185	231	2.400
Total	**185**	**185**	**231**	**185**	**185**	**231**	**185**	**185**	**231**	**185**	**185**	**231**	**2.400**

Example of spreading on totals

Spreading can also be calculated in complex forecast forms, the totals of which are calculated on the basis of the subtotals. In this example, the form has the following structure:

- it has the subtotals by product on the rows
- it has the subtotals of the volumes of sales for the various months on the columns
- a total with the sum of the two subtotals

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Antivirus	92	90	116	92	92	116	92	92	116	92	92	116	1.200
Operating System	144	172	201	300	258	144	172	70	230	201	229	250	2.371
Multimedia Player	193	57	82	28	27	28	28	10	27	138	139	166	923
Spyware Removal													0
Utilities													0
Games	97	122	130	137	146	154	162	50	179	186	195	202	1.760
Home SW	**526**	**441**	**529**	**557**	**523**	**442**	**454**	**222**	**552**	**617**	**655**	**734**	**6.254**
Financial Software	70	69	70	69	70	70	69	70	86	85	94	104	926
Office Automation	160	239	240	239	240	120	239	240	239	600	240	303	3.099
Database	5	3	3	3	4	3	3	3	7	9	8	14	65
Graphics	8	8	3	2	3	5	1	4	4	10	14	13	75
Design Tools	48	56	56	56	3	8	3	5	11	8	9	8	271
Communication	26	23	16	16	16	16	32	16	16	40	16	16	249
Motherboards	241	295	344	354	331	100	340	134	375	600	402	416	3.932
PDA	16	16	16	16	16	16	16	16	16	16	16	16	192
Web applications	3	3	4	3	3	3	11	13	3	3	15	16	80
Software													0
Business SW	**577**	**712**	**752**	**758**	**686**	**341**	**714**	**501**	**757**	**1.371**	**814**	**906**	**8.889**
Software	**1.103**	**1.153**	**1.281**	**1.315**	**1.209**	**783**	**1.168**	**723**	**1.309**	**1.988**	**1.469**	**1.640**	**15.143**
Total	**1.103**	**1.153**	**1.281**	**1.315**	**1.209**	**783**	**1.168**	**723**	**1.309**	**1.988**	**1.469**	**1.640**	**15.143**

In a form with this structure, editing subtotals or the total brings about the following behaviours:

- editing the total sales value means that the new value will be distributed over all products and months based on the spreading method set on the form, and recalculates the subtotals.

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Antivirus	102	99	127	102	102	127	102	102	127	102	102	127	1.320
Operating System	158	189	221	330	284	158	189	77	253	221	252	275	2.608
Multimedia Player	212	63	90	31	30	31	31	11	30	152	153	183	1.015
Spyware Removal	0	0	0	0	0	0	0	0	0	0	0	0	0
Utilities	0	0	0	0	0	0	0	0	0	0	0	0	0
Games	107	134	143	151	161	169	178	55	197	205	214	222	1.936
Home SW	**579**	**485**	**581**	**613**	**576**	**486**	**500**	**245**	**607**	**679**	**721**	**807**	**6.879**
Financial Software	77	76	77	76	77	77	76	77	95	93	103	114	1.019
Office Automation	176	263	264	263	264	132	263	264	263	660	264	333	3.409
Database	5	3	3	3	4	3	3	3	8	10	9	15	71
Graphics	9	9	3	2	3	5	1	4	4	11	15	14	82
Design Tools	53	62	62	62	3	9	3	5	12	9	10	9	298
Communication	29	25	18	18	18	18	35	18	18	44	18	18	274
Motherboards	265	324	378	389	364	110	374	147	412	660	442	458	4.325
PDA	18	18	18	18	18	18	18	18	18	18	18	18	211
Web applications	3	3	4	3	3	3	12	14	3	3	16	18	88
Software	0	0	0	0	0	0	0	0	0	0	0	0	0
Business SW	**635**	**783**	**827**	**834**	**755**	**375**	**785**	**551**	**833**	**1.508**	**895**	**997**	**9.778**
Software	**1.214**	**1.268**	**1.409**	**1.447**	**1.330**	**861**	**1.285**	**796**	**1.439**	**2.187**	**1.616**	**1.804**	**16.657**
Total	**1.214**	**1.268**	**1.409**	**1.447**	**1.330**	**861**	**1.285**	**796**	**1.439**	**2.187**	**1.616**	**1.804**	**16.657**

Data entry tracking log

Log structure

If, on a form, the **Enable tracking of edits in data entry mode** item is enabled in **Form options**, the system will apply the changes on saving. See "Form options window" on page 133.

In data entry mode, the edit tracking log on the *LOG_PROSPETTO_DATA* database table has the following fields.

- *OID_DATA*: the edit's unique identifier.
- *AFFECTED_OID*: unique identifier of the row edited/added to the table of events.
- *TABLE_ID*: identifier of the table involved.
- *COD_PROSPETTO*: form code.
- *USERUPD*: code of the user who performed the save.
- *DATEUPD*: date and time saved.

The *TABLE_ID* field can have the following values:

- 0 for the *DATI_SALDI_LORDI* table
- 1 for the *DATI_SALDI_IC* table
- 2 for the *DATI_COMMENTI* table
- 3 for the *DATI_NOTE* table
- 5 for the *DATI_PROSPETTO_FORMULA* table

Data Entry from Excel

Contents

This section covers the following topics:

Data entry in the Excel add-in ... 316
Data entry toolbar ... 316
Working with data entry forms in Excel ... 318
Data Entry panel ... 319
Setup and Administration Panel - Data Processing ... 321
Workflow panel ... 321
Cell edit - Amounts window ... 323
Cell edit - comments window ... 325
Working with Cell edit - Comments ... 327
Cell edit - intercompany window ... 327
Intercompany report window ... 329
Edit intercompany: use case ... 330
Working with spreading ... 332
Data entry in work off-line mode ... 333
Work off-line toolbar ... 333
Working in Work off-line mode ... 333
Locked data entry forms page ... 335

Data entry in the Excel add-in

Enter data in forms

The Excel Add-in allows you to work through forms, perform data entry on gross and intercompany amounts, insert journals and enrich data by inserting comments and adding attachments. For more details, see "Data entry in cells" on page 310.

Running tasks from forms

It is possible to run and mark as finished tasks from the processes' task workflow via the Excel add-in. In particular, when the task includes the entry of data in a form, it is possible to run and complete it in the add-in. See "Workflow panel" on page 321.

Data entry toolbar

Excel > CCH Tagetik > Data Entry > select form > set filter parameters

Introduction

The **Data Entry** tab is shown when a data entry form is opened in the work desktop.

Buttons on the Data Entry toolbar

Element	Description
Tools	
	**Refresh**: runs the report again, potentially updating the data extracted from the database. ***Note**: this refresh operation could delete any edits to the run report made locally, especially if the report contains a dynamic matrix. To create areas that will not be updated, assign a name starting with "TGKNOTREFRESH" with the Excel AREAS function. The edits remain in place locally and are not visible to other users who are not in possession of that particular file.*
	**Refresh comments**: updates the comments linked to the report cells. See "Cell edit - comments window" on page 325.
	**Export Excel document (protected)**: allows you to export the form as an Export file, maintaining security over the spreadsheets.
	**Export Excel document (unprotected)**: allows you to export the form as an Excel file, removing the spreadsheet protection.
	**Work Off-line**: exports the form as an Excel file so it can be edited off-line and then reimported. See "Data entry in work off-line mode" on page 333.
	**Show**: shows cells containing hidden comments, or comments associated with the lowest level elements if the selected filter is the node of an aggregation structure. In this case, only the row related to the node is displayed in the report.
	**Details**: displays the comment in a dedicated window.
	**Hide**: hides the displayed comments.
	**Warning**: shows any non-blocking warnings. Only visible if there are warnings to be shown.
	**Hide rows/columns if 0**: shows/hides any rows or columns given the property "Hide" in the design phase.
	**Statistics**: runs an Excel file containing data on the form's performance. See Statistiche di reporting.
Show	
	**Cell properties**: in the left-hand panel, opens the **Cell properties** tab, showing information on the cell and filters.
	**Predefined filters**: in the left-hand panel, opens the **Filters** tab which shows the filters applied to the form parameters and allows the user to edit them.
	**Cell**: runs the drill-down on the selected cell. See Drill-down.
	**Column**: runs the drill-down on the selected column. See Drill-down.
	**Row: runs the drill-down on the selected row. See Drill-down.**
	**Data Processing**: runs the data processing associated with the form. See Elaborazioni lanciate da reporting.
	**Pivot table**: shows the contents of the selected matrix as a pivot table. See Tabelle pivot.
Edit	
	**Cell edit**: allows you to enter the following additional data and information: • **Intercompany**, see "Cell edit - intercompany window" on page 327. • **Amounts**, see "Cell edit - Amounts window" on page 323. • **Comments/Attachments**, see "Cell edit - comments window" on page 325.
	**Intercompany Report**: generates a report in Excel format listing all the intercompany entries declared on the accounts present in the report. See "Cell edit - intercompany window" on page 327.
	**Run TGKSend**: runs the TGKSend formulas. See Funzioni custom.

Element	Description
	**Formulas**: allows you to use the following functions: • **Show formulas used**. Shows the formulas used as comments and hides any comments. • **Retrieve formulas**. Shows the formulas used in the relative cells. Only available on editable cells. • **Retrieve formulas from...**. Shows the formulas used in the relative cells but allows you to specify a different scenario or period. The scenario can be marked as "Previous", "Next", "Ref1" ... "Ref5", or a combination thereof. The period can be changed by applying a forward or backward shift to all period filters. This function allows you to use formulas saved during the data entry session in a previous year or previous month, for example. • **Save all formulas**. Saves the formulas present on all editable cells of the form. • **Save selected formulas**. Saves the formulas present on the editable cells in the current selection. • **Delete all formulas in the DB**. Deletes the saved formulas related to the current form from the database. • **Delete selected formulas from DB.** Deletes all saved formulas related to the current selection. ***Note**: the formulas are not deleted but replaced with empty spaces.* These functions allow you to use Excel formulas to enter values in editable cells instead of typing the amounts directly, and so it is useful to save formulas and restore them to be used later. Every user can only see the formulas that they have created.
	**Paste set of values**: pastes a previously copied set of values. In the presence of validation checks on the target cells, the validation is also run on the copied values. ***Note**: only areas of adjacent cells can be selected and pasted. Non-editable cells will be ignored.*
	**Restore original values**: returns the form to how it was when opened.
	**Spreading Method**: activates/deactivates the spreading method. See "Spreading" on page 313.
	**Lock area**: locks the selected cells to spreading.
	**Unlock area**: unlocks the selected cells to spreading.
	**Go back online**: deactivates work off-line mode for a saved form to work on it locally. See "Data entry in work off-line mode" on page 333.

Working with data entry forms in Excel

Excel > CCH® Tagetik > Data Entry

Open a data entry form

1. In the left-hand panel, select the desired application database.
2. Select the process and the step. When the phase is selected, only the forms and/or groups related to the selected step are shown in the tree. If you want to select all steps, use the specific "All steps" option. In such cases, the **Group by step** option can be activated to show tree with the forms grouped by step.
3. To run the form, select the desired form in the tree and click . If requested, the **Parameters** window opens (see "Parameters" on page 136).
4. Select the desired parametric filters and click **OK**.

***Note**: the selected data entry form will open and the Data Entry toolbar will be displayed.*

Entering data in forms

This procedure describes how to enter data in a standard form.

1. Open the desired form (see "Open a data entry form" on the previous page).
2. To enter data, enter the desired cells in editable cells in the work desktop.

Show workflow tasks

Excel > CCH® Tagetik > Workflow - Grid

1. In the left-hand panel, select the desired application database.
2. Select the process and the step. On selecting the step, only the tasks of the selected step are shown in the task list. If **All the steps** is selected, the system shows all steps of the process in sequence, with the relative tasks.
3. Only if the **Enable submission by scenario/period** option is active on the process, select a scenario/period.
4. Select the desired entity or node of entities.
5. Click to refresh the task list.

Run a task

Excel > CCH® Tagetik > Workflow - Grid

In the left-hand panel, click the desired task, then click **Run**.
To mark a task as complete, click . To unmark as complete, click .

Run data processing

Excel > CCH® Tagetik > Workflow - Grid

Excel > CCH® Tagetik > Data Entry >

In the left-hand panel, click the desired data processing: a window will appear showing the data processing's progress.

Alternatively, click on the Data Entry bar and select the desired data processing: a window will appear showing the data processing's progress.

Define a colour for editable cells

Excel > CCH® Tagetik > Design > open form > Form options > Layout options tab

In the **Editable cells colour** field, click ..., then choose the desired colour to identify editable cells.


Data Entry panel

Excel > CCH® Tagetik > Data Entry

Purpose of the panel

This panel allows you to select and run a data entry form.

What it looks like



Element	Description
A	Action buttons
B	Fields for selecting parameters
C	Forms tree

Sections of the panel

Element	Description
Run form selections	Allows you to set the following for running the desired form: • the application database on which the form is saved • the process in which the form has been included • the step of the process with which the form is associated ***Note**: the **Group by step** option allows you to group forms by step.*
Forms tree	Show list of available forms based on selections.

Buttons on the panel

Element	Description
	Refreshes the forms tree.
	Opens the form in data entry mode.
	Only enabled if a report list saved in the forms tree is selected. Only opens selected forms that are included in the report list (see Report list).
	Lock/unlock form for editing. When the data entry form is locked, it can only be run in navigation mode.
	Allows you to search the forms tree.
	Allows the user to select the display mode for forms on the panel: with description only, with code only or with both description and code.

Setup and Administration Panel - Data Processing

Excel > CCH® Tagetik > Data Entry > open data entry form > (Data entry in Excel tab) Data Processing

Purpose of the panel

This panel allows you to run data processing associated with the data entry form.

Links on the panel

Element	Description
<data processing name>	Allows you to run the relative data processing associated with the form.

Workflow panel


Excel > CCH® Tagetik > Workflow - Grid

***Note**: the button is only available to users who have function "0003029 - Reporting.NET - Data Entry - Workflow table" enabled in their own role, or for whom the Sharepoint module is enabled.*

Purpose of the panel

This panel allows you to run and/or submit tasks from the step of the process with which the form is associated, for which the panel was launched.

What it looks like



Element	Description
A	Action buttons
B	Select run parameters
C	List of workflow tasks

Sections of the panel

Element	Description
Select run parameters	Allows you to set the following search criteria for the desired tasks: • the application database to which the process belongs • the process • the step or steps of the process • (only if the **Enable submission by scenario/period** option is active in the process) the desired scenario/period • the chosen entity or node of entities
Task list	Shows the list of tasks in sequential order for the selected step.

Buttons on the panel

Element	Description
	Updates the list of workflow tasks according to the selected parameters
	Runs the task.
	Task is Complete.
	Removes Task is Complete status.
	Opens a window to search and select elements in the hierarchy of entities.

Details of columns in List of steps

Element	Description
Type	Task type. • : data edit task. When run, it opens a form in data entry mode. • : submission task. Only run when all other tasks have been completed and the relative data have been locked for the process/step. • : data processing task. When run, it starts CCH Tagetik data processing. • : opens a window in the web interface.
Code	Entity/node of entities code
Phase	Phase
Description	Description of the task
Status	Task status. • : task not yet started • : task in progress • : task complete • : optional task • : task locked because the user does not have the rights to run it
User	Identifier of the last user to work on the task.
	Opens a window to search the content of the columns and allows the user to filter them according to defined operators.

Cell edit - Amounts window

Excel > CCH® Tagetik > Data Entry > open form > select editable cell with amount > Cell edit > Amounts


Purpose of window

This window allows you to enter gross balance data in an editable cell of a form and specify certain additional information.

***Note**: when the cell on which the user wants to enter gross amounts is not editable due to conditional editability rules, or a filter has been set on the currency, then this window will open in read only mode.*

***Note**: (enabled by default) this window can be enabled/disabled via the **Forms: use details window to input gross and IC data with transaction currency** parameter in the data entry rules. When the window is enabled, the data can be entered in the cell.*

What it looks like



Element	Description
A	Amount management buttons
B	Current cell amounts
C	**Edit Amounts** section

Window sections

Element	Description
Cell amounts	Amounts present in the selected cell.
Transaction currency	Currency in which the gross amount row is expressed. (If the data entry rule specifies that the transaction currency is managed on amounts and if the **Manage transaction currency** option is active for the account) Indicates the currency in which the transaction is carried out. ***Note**: for more details on data entry rules, see "Data entry modes" on page 2.*

Element	Description
Transaction currency amount	(If the data entry rule for the current process specifies that the transaction currency is managed on gross amounts if the **Manage transaction currency** option is active for the account) Indicates the amount in the transaction currency. **Note**: for more details on data entry rules, see "Data entry modes" on page 2.
Entity currency amount	Obtained from the automatic conversion of the transaction amount into the declaring entity currency at the FX rate of the account on which the value being edited is declared. It can be edited manually.
Notes	Allows you to insert text-based notes on gross amounts

Buttons in the window

Element	Description
	Creates a new amount.
	Changes an amount.
	Deletes an amount.
	Saves an amount.

Cell edit - comments window


Excel > CCH® Tagetik > Data Entry > open form > select editable cell > Cell edit > Comments/Attachments

Purpose of window

This window allows you to manage comments and documents in an editable cell of a form.

***Note**: when working on Analytical Workspace line-by-line matrices, several documents can be attached to the same comment. If there are several attachments, the system displays the same description. For matrices created on the Financial Workspace and for Multidimensional matrices, however, only one document can be attached to each comment.*

What it looks like



Element	Description
A	Comment management buttons
B	List of comments in the current cell
C	Insert comment section

Page sections

Element	Description
Cell comments	List of comments present in the cell
Insert comment area	Editable cell content

Comment management buttons

Element	Description
	Creates a new comment.
	Edits a comment. Only available for the user who added the comment, or users for whom Reporting-Data Entry-Comments-Administrator, code 0003862, is enabled. Disabled for users with $DEREPORT role.
	Deletes a comment. Only available for the user who added the comment, or users for whom Reporting-Data Entry-Comments-Administrator, code 0003862, is enabled. Disabled for users with $DEREPORT role

Element	Description
	Saves a comment.
	Attaches a document and defines a description visible when the cursor is hovered over the cell containing the comment.

Working with Cell edit - Comments

Inserting comments

Excel > CCH® Tagetik > Data Entry > open form > select editable cell > Cell edit > Comments/Attachments

The cells to which a comment is associated can be recognised in the form thanks to a red triangle positioned in the top-right corner of the cell. To view the comment, hover the cursor over the cell.

***IMPORTANT:** the comment is associated to the cell on which it is set and the cell is visible when the form is run with a specific combination of parameters. To save the comment on the database and make it visible to other users, the form must be saved. After saving the form, the comment is visible in all forms with the same filters as those used on the cell on which the comment was created.*

Attaching documents to comments

Excel > CCH® Tagetik > Data Entry > open form > select editable cell > Cell edit > Comments/Attachments

1. Select the desired comment and click **Attach Document**.
2. In the window, click ... next to **File** and select the desired attachment.
3. In **Description** enter the description of the attachment that the system will show when the cursor is hovered over the cell containing the comment.
4. Click **OK**.
5. Click **Save**.

Open an attachment

In the work desktop, click to the right of the desired cell.

Show comments on individual elements of a node

Excel > CCH® Tagetik > Data Entry > open form > select cell with comment > Hidden comments > Details

Hide comments on individual elements of a node

Excel > CCH® Tagetik > Data Entry > open form > select cell with comment > Hidden comments > Hide

Cell edit - intercompany window

Excel > CCH® Tagetik > Data Entry > open form > select editable cell with amount > Cell edit > Edit intercompany


Purpose of window

This window allows you to enter intercompany declarations in an editable cell of the form on an account that allows intercompany data.

***Note**: when the cell on which the user wants to enter intercompany data is not editable due to conditional editability rules, or a filter has been set on the currency, then this window will open in read only mode.*

***Note**: (enabled by default) this window can be enabled/disabled via the **Forms: use detail window to input gross and IC data with transaction currency** parameter in the data entry rules.*

What it looks like



Element	Description
A	Intercompany declaration management buttons
B	The intercompany declarations in the current cell
C	Intercompany declarations management section
D	Diagnostic checks on intercompany data section

Page sections

Element	Description
Intercompany declarations in the cell	List of the intercompany declarations present in the selected cell. In particular, this shows the following for every declaration: • **Gross amount** • **Intercompany amount**
Manage intercompany declarations	Contains the following tabs: • **IC Fields**: allows you to define the details of an intercompany declaration. • **Additional fields**: allows you to add optional data on the intercompany declaration.
Checks on intercompany data	Allows you to run balancing checks on the data entered, to verify consistency between the amounts entered by the declaring entity and those entered by the counterparty entity.

Fields in IC Fields

Please find below the most important fields.

Element	Description
Counterparty entity	Allows you to select, from within the same group, an entity to which to make a declaration that generates the current transaction.
Custom dimension 2 counterparty	Allows you to select a custom dimension 2 item (if active) that details the intercompany declaration.
Transaction currency	(If the data entry rule for the current process specifies that the transaction currency is managed on intercompany amounts and if the **Manage transaction currency** option is active for the account) Indicates the currency in which the transaction is carried out. ***Note**: for more details on data entry rules, see "Data entry rules" on page 3.*
Transaction currency amount	(If the data entry rule for the current process specifies that the transaction currency is managed on intercompany amounts if the **Manage transaction currency** option is active for the account). ***Note**: for more details on data entry rules, see "Data entry rules" on page 3.*
Entity currency amount	Obtained from the automatic conversion of the transaction amount into the declaring entity currency at the FX rate of the account on which the value is declared. It can be edited manually.
Notes	Allows you to enter text-based notes on the intercompany declaration.

Fields in Checks on data

Element	Description
Relationship check	Shows all entries towards the counterparty entity declared by the declaring entity and vice versa.
Check all	Shows all entries in which the declaring entity is present, as either the declaring entity or the counterparty.
Print	Prints the result of the checks on a pre-defined printer.

Key combinations

Element	Description
CTRL+A	Adds a new row.
TAB	Allows you to shift from one field to another when adding a new row.
CTRL+S	Saves changes.
CANC	Deletes the selected row.
ESC	Closes the window. If there are any unsaved changes, a confirmation message will appear.

Intercompany report window

Excel > CCH® Tagetik > Data Entry > open form > Intercompany report

Purpose of window

This window allows you to extract an XLSX report on the intercompany entries declared on the accounts present in the form. By default, the report contains the following information:

- account
- counterparty entity
- counterparty custom dimension 2 (if the custom dimension 2 is active in the environment)
- amount in the transaction currency (if active)
- transaction currency (if active)
- amount in entity currency
- any notes
- origin of the intercompany amount, i.e. whether the data was entered via a data entry form (INPUT_DEFORM), a dedicated management window (INPUT_WEB) or an ETL.

Fields in window

Element	Description
Print empty cells	The report will include cells of the form that do not contain intercompany values but which are potentially suitable for the entry of intercompany data.
Cells	Defines the types of cell to be included in the report. • **Only editable**: cells defined as editable in the matrix and on which intercompany data has been entered • **Editable + actual**: cells defined as editable in the matrix on which intercompany data has been entered and cells on which neither a scenario shift nor a period shift has been defined. • **All**: all cells on which intercompany data has been entered

Edit intercompany: use case

Introduction

An example showing how to enter an intercompany entry directly from the Tagetik Reporting Excel client is provided below.

The intercompany context

Suppose you have a transaction between European company A00, which sells services, and American company C00, which buys them. Both companies belong to the same Group. Then we need to enter the following values for the January 2012 Budget:

- Other Revenues of EUR 250 (taking account of the fact that the document amount is USD 300) **for company A00**
- Other Commercial costs of USD 300 **for company C00**

Enter Other revenues figures

The first step is to enter the Other revenues figures.

1. Open the form on which to enter those amounts.
2. Select the cell in which to enter the amount. In this case, select the cell that corresponds to "Other revenues" for scenario "2012BDG" and period 01.
3. From the cell, click **Cell edit > Intercompany**: the add intercompany declaration window will open.

Enter an intercompany value

In this example, an intercompany value towards company A02 - Berlin Distribution has already been entered in the cell.

1. To enter the new value towards C00, click **New**.
2. Add the counterparty entity:

To add the entity...	Then...
manually	enter the value in the field.
from a list	click ... and choose the desired entity from the available counterparties.

***Note**: the intercompany data defined in the "Frequently used Ctps" table are shown. When the "Show all Ctp Entities" flag is selected, the system shows the full list of counterparty entities that could be selected by the user.*

3. Optional. To search for an entity among the counterparties, click **Search**, select the desired entity and click **OK**, the entity will be added to the intercompany declarations window.
4. Enter the transaction amount, then define the Currency amount as USD 300 and select USD as the currency: the system will automatically calculate the amount in the currency of the declaring entity (in this case, EUR).

***Note**: this amount can be overridden and overwritten.*

5. Insert a note to allow this declaration to be tracked at a later date.
6. Click **Save** to save the new report in the database.

Enter the amount of the cost for the beneficiary entity


When the declaring entity (A00) has finished entering its revenues, the corresponding cost incurred by the beneficiary entity (C00) must be entered.

1. Open the Excel form dedicated to cost data entry.
2. To enter the value, select **Edit cell > Intercompany** on the cell corresponding to "Commercial expenses".
3. Define the counterparty entity as "entity A00 - Rome Distribution".
4. Enter USD 300 as the amount.
5. If useful, insert a note to comment on or describe the entered value.

Run data coherence diagnostics

Once both values have been entered, it is useful to run diagnostics to check that the intercompany relationship is balanced. Diagnostics can be run directly from the Intercompany window. The first check that can be performed is the "**Relationship check**", which allows you to see all entries declared by the current entity towards the selected counterparty entity (and vice versa).

To check the intercompany relationships between entities A00 and C00, select entity C00 and then click **Check relationship**.



The system will show all the relationships entered between the two entities, A00 and C00. An example of the results generated by the diagnostics is provided below:

```
A00 - Distribution Rome <--> C00 - Corporate USA (EUR)

  A00 - Distribution Rome
    50010 - Product Revenues
      G01 - Generic
      G01 - Generic Product
      G01 - GEN                                    -150.00 EUR              -150.00
    50020 - Other Revenues
      G01 - Generic
      G01 - Generic Product
      G01 - GEN                                    -300 USD                 -250.00
                                                                ------------------
                                                 Exchange rate diff.          20.96
                                                          Total              -379.04

  C00 - Corporate USA
    50110 - Cost of Good Sold
      G01 - Generic
      G01 - Generic Product
      G01 - GEN                                     150.00 EUR               137.43
    50350 - Other Gen/Comm Expenses
      G01 - Generic
      G01 - Generic Product
      G01 - GEN                                     300 USD                  229.04
                                                                ------------------
                                                 Exchange rate diff.          12.57
                                                          Total              379.04

                                                       Difference              0.00
```

The diagnostics shows all the intercompany values entered in the system between the current entity and the selected entity. The system shows the sum total of the revenues in the first section, and the sum total of the costs in the second. The difference between the two values is calculated in the last row.

In the example, the difference between the two section is zero, so the entered values are correct and the result is balanced.

Also note that, in cases in which a value expressed in a currency other than the entity currency is entered, the system calculates the FX rate difference between the value calculated by the system at the current FX rate and the value entered manually.

It is also possible to "**Check all**" via diagnostics. This shows all entries in which the declaring entity is present, as either the declaring entity or the counterparty. In the example, it checks all IC declarations from A00 to C00, but also from A00 to A02.

To print the result generated by the diagnostics, click **Print**: the file will be printed on the pre-defined printer.

Working with spreading

Excel > CCH® Tagetik > Data Entry > open form

Enable spreading

1. Click .
2. Select the desired spreading method from the drop-down menu.

With spreading enabled, all other options accessible from the data entry toolbar are disabled.

Edit totals with numerical values

To edit a total, enter the new value in the desired total cell and press ENTER.

Based on the structure of the form, the system distributes the new value over the rows or columns according to the spreading method set on the form.

Edit totals with deviation values or fractions

To enter total values expressed with a deviation calculation or fraction based on the original value, enter the desired numerical or percentage value in the cell, preceded by the sequences \+, \-, *, \/. The final value will correspond to the cell's original value, plus, minus, multiplied by or divided by the value following the expression.

For example, by entering \-400 or \-40% in a cell with value 1000, the system will calculate a final value of 600.

Lock/unlock cells for spreading

This procedure shows how to lock specific ranges of cells for spreading. This can be useful when performing forecasting jobs. In this case, it is necessary to lock data collected in the months from the start of the year up until the analysis, so it cannot be edited.

- To lock a range of cells, select the cells and click on the toolbar: the locked cells will be shown in grey.
- To unlock cells, select them and click .

Data entry in work off-line mode

Introduction

It is also possible to work on data entry forms in Excel without being linked to a CCH Tagetik or without Excel installed, but with a compatible application capable of opening and saving XLSX files available (e.g. Open Office Google Apps, Office 365). To do this *work off-line* mode must be activated. This allows you to download a copy of the form locally and use it as a normal Excel spreadsheet, to then re-upload it to CCH Tagetik at the end of the data entry session. The data are first saved on the form, then transferred to the operational database.

When a form is downloaded in off-line mode, it can no longer be opened in data entry mode with the same filters by any user, until it has been uploaded to CCH Tagetik again. This lock is not subject to any timeouts set in configuration, but is removed by the current user when they return to online mode.

> ***Note**: when the form contains Analytical Workspace data only, if the Show user data only option is active in all the reference datasets, then the form will not be locked (see "Forms page" on page 336).*

Forced return to online mode

If the contributor user does not return to online mode, the form used off-line will be locked. If necessary, the administrator user can override the lock via a specific unlock window, which also allows the administrator to monitor the status of a form. See "Locked data entry forms page" on page 335.

Work off-line toolbar

Excel > CCH® Tagetik

***IMPORTANT**: this bar is only shown when a data entry form that has previously been saved in Work off-line mode is opened.*

Buttons on the Work off-line toolbar

Element	Description
	Turns off off-line data entry mode and reimports the form into the system.
	Activates the spreading method (proportional method only). See "Spreading methods in data entry mode" on page 313.

Working in Work off-line mode

Excel > CCH® Tagetik

Downloading a data entry file in off-line mode

1. Open the form in data entry mode (see "Open a data entry form" on page 318).
2. On the toolbar, click the button.
3. Select the folder in which to save the file. The file will be saved as a normal Excel spreadsheet.

Opening a data entry form off-line

Open the desired data entry form file.

If...	Then...
the CCH Tagetik Excel add-in is not installed on the device	the file will open in Excel.
the Excel add-in is installed on the device	If the user is not logged in, the file will open in Excel with the addition of the "Work off-line" toolbar. If the user is logged in, the system asks if they want to end the work off-line session. **If...** / **Then...** the user confirms → the system asks if they want to save the data edited in the off-line report and open the form in on-line mode. the user does not confirm → the file will open in Excel with the addition of the "Work off-line" toolbar.

Loading a data entry form that has been edited off-line into CCH Tagetik.

This procedure shows how to save data entered in the form off-line.

If...	Then...
the Excel add-in is not installed on the device	the edited data will be saved in the local file.
the Excel add-in is installed on the device	the system asks the user if they want to leave work off-line mode. **If...** / **Then...** the user confirms → the system asks for log-in credentials, goes back online and asks the user if they want to save the data entered/edited on the form off-line. If the user confirms, the data will be saved on the database. the user does not confirm → the data will be saved locally.

Locked data entry forms page

Admin | <application database>

Forms management tile > Elements > select form > > Locked data entry forms

Purpose of the page

This page shows a list of the forms for which data entry is locked because they are being used by other users.

This can also be used for forms in off-line mode and allows you to override the lock on them so they can be used for data entry in on-line mode.

Page fields

Element	Description
<Form description>	• **User**: identifier code of the user locking the form • **Form**: code and description of the form • **Access Date**: date and time at which the user opened the form in data entry mode • **Status**: details of the status of the lock on the form

Buttons on the page

Element	Description
	Unlocks the selected form and makes it available for data entry.

Data Entry from Web

Contents

This section covers the following topics:

Forms page ... 336
The web forms page (data entry) ... 339
Working with comments and attachments ... 341
Edit comments page ... 342
Edit IC page ... 344
Run data entry in web forms ... 345
Data processing via hyperlinks in web forms ... 346
The grouping function ... 346
Rich Text Editor ... 349
Working with spreading in web forms ... 350
Journals Hub ... 350
Dashboard View ... 352
Management view ... 353
Bulkloader view ... 355

Forms page

Admin | <application database>

Forms management tile > Elements

Purpose of the page

On this page you can:

- view the list of existing forms in CCH Tagetik
- edit certain parameters and relationships of standard forms
- create and edit transactional forms

***Note**: new standard forms can only be created from the Excel interface.*

Buttons on the page

Element	Description
	(Available for transactional forms only) • **Stored Procedures**: opens a page to select stored procedures to be run automatically when the form is saved, or run manually. • **Usable accounts**: opens a page to select the accounts to consider for data entry ("Data only" or "Data and Dimension" forms).
	**Recode**: opens a page to edit the codes associated with the forms. **Transactional form dictionaries**: opens a page to manage the dictionaries for transactional forms. **Form dictionary items**: opens a page to manage dictionary items. **Data entry locking forms**: opens a page to unlock forms for which data entry is locked (see "Locked data entry forms page" on the previous page).

Tabs on the page

Element	Description
Attributes tab	Defines the characteristics of the forms.
Relationships tab	Allows you to associate the form with groupings of forms.

Attributes tab

Element	Description
Form identification section	Allows you to enter the form's code and description and the data that it manages.
Input properties	(Transactional forms only) Allows you to manage options related to data entry in the form.
ETL	(Transactional forms only) Allows you to link an ETL job to the form.
Manage use as web form	(Only when editing a standard form) Manage the use of the form on the web interface.
Validity	(Only when editing a standard form) Allows you to set start and end dates for the form's validity.

Details of the form identification section

Element	Description
Code	Form code
Description	Form description
Form type	Indicates the form type: • (Only when creating a transactional form): **Transactional** (not editable). • (Only when editing a standard form): **Standard** (not editable).
Definition	(Only when editing a transactional form) Opens a page to define the form's data structure (see Pagina Colonne).
Input type	(Only when creating a transactional form) Defines the purpose of the data entry performed within the form. • **Data only**: the form enters or edits data in the CCH Tagetik application database. • **Dimension only**: the form enters or removes data in the elements table of a dimension of the CCH Tagetik application database. • **Data and Dimension**: the form enters or edits data in the application database, or enters or removes data in the elements table of a dimension.

Details of input properties

Visible for transactional forms only.

Element	Description
Show user data only	Shows only data entered or edited by the user.
Disable editability checks	Disables any editability checks during the data entry step.
Disable insertion of records	Disables the insertion of new rows under the last existing row in the data entry step. When selected, the **Add** button is disabled when the form is run.
Disable deletion	Disables the deletion of form rows in the data entry step. When selected, the **Delete** button is disabled when the form is run.
Ignore scenario filter	Allows you to ignore the initial filter on the scenario with which the form was launched in the data entry step. This option is useful when the form is used to insert elements in the elements table, or when data entry is performed on several scenarios simultaneously. When this option is enabled, the **Scenarios** column must be defined manually in the data entry step.

Element	Description
Ignore period filter	Allows you to ignore the initial filter on the period. This option is useful when the form is used to insert elements in the elements table, or when data entry is performed on several periods simultaneously. When this option is enabled, the **Period** column must be defined manually in the data entry step.
Ignore entity filter	Allows you to ignore the initial filter on the entity. This option is useful when the form is used to insert elements in the elements table, or when data entry is performed on several entities simultaneously. In forms used to enter data, when this option is enabled, the **Entity** column must be defined manually in the data entry step.

ETL details

This field is only valid for forms created with the utility that exists in the old Flex interface. If enabled on a new form from the current interface, it will not allow you to manually relate an ETL job to the form the this field.

Element	Description
Enable loading	Manages the automatic transfer of information entered on the form, and saved on the specific FORM_DATI database, on the data tables (DATI_SALDI_LORDI, DATI_SALDI_IC) or the dimension tables (DEST1, DEST2, etc.) of the application database. • Selected: the system will transfer the data on saving the form. • Not selected: the system will not transfer the data. The data can be transferred manually from the ETL module, or via the "run data processing from form" function
Jobs	(With **Enable loading** selected) Allows you to select the ETL job to be used to transfer the data from the form to the application database tables. ***Note**: currently, this can only be used to edit the job on forms which already have one related to them, by choosing another one from the list.*
Period length	Defines how amounts are saved when transferred to the data tables or dimension tables. • **Cumulated** • **Monthly** • **Annual** • **Bimonthly** • **Quarterly** • **Four-monthly** • **Semiannual**
ETL domain	Encompasses the entire setup that allows the user to define a number of rules for extraction, transformation and loading.
Routine	Specific task from among those contained in the ETL environment selected above. A routine can contain one or several Jobs.

Details of management as web form

Only when editing a standard form

Element	Description
Enable as web form	• **From configuration**: behaviour will depend on the value of the parameter specified in advanced form configuration (see Finestra Impostazioni). • **Yes** • **No**
Lock structure	Locks the form structure so it cannot be edited by the current user or other users.
Do not display in data entry & navigation	Removes the form from the lists for data entry and navigation.

Relationships tab

Element	Description
Grouping selection menu	Select a grouping to which to associate the form.

The web forms page (data entry)

Processes tile > select process > select scenario and period (if present) > select step tab > select entity > (Workflow) if present, click task form > Open Form in Web


Introduction

This page is similar in both navigation and data entry modes. The page in data entry mode is described below.

If a web form is run in data entry mode, the editable cells of the form can be changed. On saving, the changes are applied to the CCH Tagetik application database.

***Note**: in data entry mode, a web form can only be run directly from the web interface from the processes cockpit.*

What it looks like



	CY	PY	Variance
ASSETS			0
Cash in Bank Accounts	1.319.611	350.433	969.178
Petty Cash	323.500	25.000	298.500
Bank Credit Lines			0
Accounts Receivable	1.995.782	1.591.257	404.525
Inventory	1.428.373	828.638	599.735
Other current Assets	1.354.269	1.470.519	-116.250
Current Assets	6.421.535	4.265.847	2.155.688
Accruals and Prepaid Expenses	673.649	592.584	81.065
Land	2.053.242	1.753.242	300.000
Buildings	2.258.100	2.258.100	0
Property & Equipment	3.981.517	2.630.970	1.350.547
Other Tangible Assets	1.776.152	1.248.144	528.008
Financial Investments In Consolidated Affiliates	4.495.719	3.995.719	500.000
Financial Investments In Unconsolidated Affiliates	230.000	230.000	0
Tangible Assets	15.468.379	12.708.759	2.759.620
Goodwill	875.300	875.300	0
Other Intangible Assets	1.627.238	1.504.699	122.539
Intangible Assets	2.502.538	2.379.999	122.539
Land - Acc. Depreciation			0
Buildings - Acc. Depreciation	-905.910	-900.540	-5.370
Property & Equipment - Acc. Depreciation	-1.398.108	-1.392.475	-5.633
Other Tangible Assets - Acc. Depreciation	-507.754	-499.258	-8.496
Accumulated Depreciation (DEPRECATED)			0
Accumulated Amortization	-573.666	-573.666	0
Depreciation & Amortization	-3.385.438	-3.365.939	-19.499
TOTAL ASSETS	21.007.014	15.988.666	5.018.348
LIABILITIES			0

Element	Description
A	Form title bar
B	Functions tab
C	Action buttons, which vary according to the selected function
D	Form content

Page tabs

Element	Description
Home	Allows you to manage the filters panel settings and data within the form (e.g. save, update, delete data, etc.), run the Quick Data Loader, open a page to manage intercompany data entry for the selected cell, and open the Cash Flow Planning page.
Analysis	Allows you to run drill down, open various types of detailed analysis pages, and enable/disable the running of all drill-through queries.
Utility	Allows you to run additional functionalities not included in the main tabs (e.g. show a cell's properties).
Spreading	Allows you to activate and manage the spreading calculation functionality.

Action buttons

The buttons shown in the various tabs are detailed below.

Element	Description
Home tab	
	Saves edited data.
	Launches the Quick Data Loader.
	Runs ETLs present in the form.
	Undoes the changes made after the last save.
	Refreshes the data shown in the form.
	Refreshes the comments associated with the form cells.
	If cells which accept intercompany entries are present in the form, this opens a page to manage the intercompany entries for the selected cell. See "Cell edit - intercompany window" on page 327.
	Allows you to edit the comments associated with the selected cell or add new ones. See "Cell edit - comments window" on page 325.
	Opens the Cash Flow Planning page. Cash Flow Planning is fed from the dimensional filters of the current cell. Function available for Financial Planning processes only.
	Hides/shows the panel of filters applied to the form. It is possible to edit the filters and regenerate the report.
Analysis tab	
	(Navigation only). Runs the drill down below the selected row. • If the selected cell is a dimension header, it shows as many rows as there are child elements of the dimension in the row. • If the selected cell is a matrix value, it shows the values present on all dimensions nested in that row. See Esecuzione del drill-down.
	Opens the detailed analysis page for the cell's dimensional perimeter, changing aggregations or splits.
	Opens the detailed analysis page for the dimensional perimeter of the entire matrix, changing aggregations or splits.
	Opens the detailed analysis page for any of the system's dimensional perimeters, proposing the cell's perimeter as the preset one.
	Active if at least one drill-through query is present on the form. Runs a drill-through query using the filters of the current cell.

Element	Description
Live-mode	Active if at least one drill-through query is present on the form. Enables all drill-through queries to be run when the cursor is moved from one cell to another.
Utility tab	
	Shows the cell properties, see Pannello Proprietà cella.
XLS	Exports the web form to Excel.
	Downloads a detailed report on the form's run times.
	Creates a Magazine in which to insert the open form The magazine can only be created from a form opened in navigation mode; the create magazine icon is disabled for forms in data entry mode.
Show rows and columns	Hides/shows rows and columns.
Spreading tab	
Proportional	Activates the proportional spreading method.
Flat	Activates the uniform spreading method.
Seasonality	Allows you to select the spreading mode by seasonality (4-4-5, 4-5-4, 5-4-4 or a customised value).
Based on scenario	Allows you to select the base scenario for the spreading calculation.
	Restores the values from prior to the activation of the spreading method.
	Locks a selected area to be excluded from spreading.
	Unlocks the selected area.

Working with comments and attachments

User | <application database>

Processes tile > select process > select step tab > select entity > (Workflow) right click task form > Run on web > select editable cell > Edit comments

Inserting comments

1. Click ⊕. A new row will appear in the list of comments.
2. Enter the desired comment text in **Comment**.
3. Enter the comment's author in **User**.
4. Enter the date on which the comment was inserted in **Date**.
5. (Optional) Insert a document (see "Attaching documents to comments" below).
6. Click **Save**.

For more details on inserting comments, see "Data entry in cells" on page 310.

Attaching documents to comments

1. In the list of comments, select the comment to which a document is to be attached.
2. Click **Insert Attachment** and, in the window, click **Choose file** to select the desired document from the file system, then insert a description of the attachment to be shown in navigation.
3. Click **OK**. The **File** and **Description** fields automatically show the file name and description.
4. Click **Save**.

Download and open an attachment

This procedure allows you to download all comments and attachments to a matrix from the web interface. The function is only accessible to users for whom function 0004152 is enabled.

1. In the work desktop, click to the right of the desired cell: a window will open showing a list of attachments present on the cell.
2. Click the desired attachment to download it and then open it.

View comments and attachments

This procedure is only possible if the **Display data entry comments in reports navigation** option is enabled in the **Comments** section of the **Settings** window (see Finestra Impostazioni).

1. Open the web form in Navigation mode.
2. To view comments and attachments, position the cursor over the cell that contains them.

Edit comments page

User | <application database>

Processes tile > select process > select step tab > select entity > (Workflow) right click task form > Run on web > select editable cell > Edit comments

Purpose of the page

This page allows you to manage comments and attach documents in an editable cell of a web form.

***Note**: when working on Analytical Workspace line-by-line matrices, several documents can be attached to the same comment. If there are several attachments, the system displays the same description. For matrices created on the Financial Workspace and for Multidimensional matrices, however, only one document can be attached to each comment.*

To be able to use comments on transactional matrices, the user must have inserted a **Comments and Attachments** type field in the dataset and in the reference matrix on which they intend to work with comments.


***IMPORTANT**: the web form must be saved for an insertion or change to be saved, and therefore visible to other users.*

It is also possible to download all comments and attachments to the matrix in a single zipped file from this page. The file has the following characteristics:

- Comments belong to the dataset on which a matrix is built and are filtered via the dimensions used in the form filters.
- If the form contains just one matrix, the file name is the concatenation of the template identifier and the name of the matrix.
- If the form contains more than one matrix, the name of the downloaded file contains the report code. It therefore contains as many zipped files as there are AIH-type matrices present in the form itself.

***Note**: this function is only available for Line by Line matrices and multidimensional matrices of the Analytical Workspace. If a form also contains Financial Workspace matrices, the relative comments and attachments will not be downloaded.*

What it looks like



Element	Description
A	Comment management buttons
B	Insert comment section
C	List of comments in the current cell

Comment management buttons

Element	Description
	Creates a new comment.
	Edits a comment. Only available for the user who added the comment, or authorised users (Reporting-Data Entry-Comments-Administrator, code 0003862). Disabled for users with $DEREPORT role.
	Allows you to download all comments and attachments to the matrix. Only available for users for whom function 0004152 is enabled.
	Deletes a comment. Only available for the user who added the comment, or authorised users (Reporting-Data Entry-Comments-Administrator, code 0003862). Disabled for users with $DEREPORT role.
	Saves a comment.

Insert comment section

Element	Description
General	
Comment	Area in which to type the comment.
User	Area identifying the author of the comment.
Date	Date on which comment was inserted.
Attachment	
File	Allows you to select any files to be attached from the file system.
Description	Allows you to insert a description for the attachment, which will later be available when you move the cursor over the cell.
Attachment	Enables the insertion of an attachment.
Insert attachment	Loads the attachment.

Edit IC page

User | <application database>

Processes tile > select process > select step tab > select entity > (Workflow) right click task form > Run on web > select editable cell > > Edit IC


Purpose of the page

This window allows you to enter intercompany declarations in an editable cell of the web form on an account that allows intercompany data.

***Note**: edit IC is only enabled on web forms if the Cumulative method was used as the Period Length in the form design step (see Il Periodo: concetti di base).*

***Note**: a user can only enter or remove intercompany values if they possess editability rights over the entities on which they are going to work.*

What it looks like



Element	Description
A	Intercompany declaration management buttons
B	Insert intercompany declarations section
C	The intercompany declarations in the current cell

Intercompany declaration management buttons

Element	Description
	Creates an intercompany declaration.
	Edits an intercompany declaration.
	Deletes an intercompany declaration.
	Saves the current intercompany declaration.
	Allows you to search for an intercompany declaration.
	Duplicates the current intercompany declaration.
	Refreshes the list of the current cell's intercompany declarations.

Insert intercompany declarations section

Element	Description
General	
Counterparty entity	Allows you to select the counterparty entity of the transaction on which the declaration is being made.
Entity currency amount	Calculates/allows you to insert the transaction amount in the declaring entity currency, obtained by converting the document amount into the declaring entity currency at the FX rate of the account on which the value is entered. If entered manually, it overwrites the value calculated by the system.
Company currency	Shows the declaring entity currency.
Transaction currency amount	Allows you to insert the intercompany amount in the transaction currency.
Transaction currency	Shows the transaction currency.
Notes	Notes on the transaction
Notes	
Invoice number	Allows you to insert the invoice number.
Invoice date	Allows you to insert the invoice's issue date.
Accounting date	Allows you to insert the invoice's accounting date.
Document type	Allows you to specify the invoice type.
Sent/received	Allows you to specify whether the invoice was sent/received by the declaring entity.
Invoice matching number	Allows you to insert the number of the reference invoice for the document.

***Note**: the options in the Notes section are only shown if the "Enable additional fields on IC" is enabled in the data entry rules.*

Run data entry in web forms

User | <application database>

Open data entry forms from the cockpit

Application database > Processes tile > select process > Contributor > select step tab

Navigation panel > Contribute > Processes > select process > Contributor > select step tab

1. Select an entity from the hierarchy: the workflow of the entity's tasks on the step will appear in **Workflow**.
2. Click on the icon relating to the desired data entry form, then choose **Open Form in Web** or **Open Form in Excel**.
3. If the form is not associated with any task workflow, in **Actions**, click Form and then or next to the desired form to open it in web interface or the Excel add-in.

Open the data entry form from the Forms tile

Forms tile > click grouping of forms > (next to form)

Forms tile > Reporting > Forms grouping (next to form)

Forms tile > click grouping of forms > (next to form) : the form will open in Excel

Data entry forms opened as web forms in this way will appear in navigation.

Entering data in forms

The form's editable cells appear in yellow, or a different colour chosen by the user. To run data entry, enter data in editable cells (see " Data entry forms: cell editability" on page 309).

Delete records from the form

To delete records from transactional forms with a Line by Line matrix, click  in the **Status** column.

Data processing via hyperlinks in web forms

Specific behaviours when running data processing

In the data entry step, data processing (DTP, Stored Procedures, Submission Processes, etc.) can be run on web forms via a hyperlink created in the design step (see "Hyperlinks" on page 298).

If several data processes are associated with a hyperlink, the following rules will apply:

- The data processes will be run in the order in which they were associated with the hyperlink.
- If the one data process fails while a data processing sequence is being run, the system will show the details of the error extracted from the audit and locks the current and remaining data processes.
- When the **Force refresh** option is active on a data process, the form will be updated automatically upon completion. If the option is active on several data processes associated with the hyperlink, the form will be updated upon completion of the last data process.

Specific behaviours when running Datasource Mapping

In the data entry step, the *Datasource mapping* process can be run from web forms via hyperlinks, even when this requires a source file containing the data to be loaded (see Quick Data Loader - Pagina Datasource mapping). In this case, when the user clicks the hyperlink, the system shows the source file selection window and enables the run data processing button when a file is selected.

> ***Note**: in the presence of a Datasource Mapping process, it is not possible to associate other data processing with the hyperlink.*

The grouping function

Description

Grouping is one of the functionalities included in web forms. It supports the following formulas:

- SUBTOTAL
- Algebraic sum of cells (does not support the native SUM function)

Grouping is performed when:

- The items involved in a formula are adjacent and belong to the same level.
    - a. Items that end up adjacent after the lower-level grouping has been run should also considered adjacent.



Adjacency between items involved in a formula: "Product Sales" and "Service Sales" are adjacent and both involved in the formula that determines "Revenue 1"




Adjacency between items after the "Revenue 1" and "Revenue 2" lower-level groupings have been run

- The items involved in a formula and the formula itself are adjacent



Adjacency between items and formulas. Sum 1 is the sum of "Revenue 4" and "Revenue 5"

- The formula contains a single item and this is adjacent to the formula




Grouping of a single element adjacent to the formula

The grouping's orientation is determined by the "subtotal before the detail" flag".

- If the flag is not selected, the grouping's orientation is standard and only formulas which have adjacent items (and items that end up adjacent after lower-level groupings have been completed) above the formula will be grouped.
- If the flag is selected, the grouping's orientation is the opposite of standard and only formulas which have adjacent items (and items that end up adjacent after lower-level groupings have been completed) below the formula will be grouped.


EXAMPLE 1 - "subtotal before the detail" not selected



	D	E
6		2019 Budget
7		February
8	Product Sales	
9	Service Sales	
10	Revenue 1	0
11	Sales Discounts	
12	Revenue 2	0
13	Sum 0	0
14	Packaging	
15	Other Cost of Sales	
16	Commission Fees	
17	Revenue 3	0
18	Other Tangible Assets - PL Depreciation	48,691
19	PL Depreciation - Intangible Assets	37,665
20	Revenue 4	86,356
21	PL Depreciation - Capitalized Expenses	
22	Revenue 5	0
23	Sum 1	86,356

View of an FST, in analytical mode, with standard grouping orientation involving all rows with formulas having adjacent items and items above the cell containing the formula

EXAMPLE 2 - "subtotal before the detail" selected



	D	E
6		2019 Budget
7		February
8	Revenue 1	0
9	Product Sales	
10	Service Sales	
11	Revenue 2	0
12	Sales Discounts	
13	Sum 0	0
14	Revenue 3	0
15	Packaging	
16	Other Cost of Sales	
17	Commission Fees	
18	Revenue 4	86,356
19	Other Tangible Assets - PL Depreciation	48,691
20	PL Depreciation - Intangible Assets	37,665
21	Revenue 5	0
22	PL Depreciation - Capitalized Expenses	
23	Sum 1	86,356

View of an FST, in analytical mode, with grouping orientation opposite to the standard, involving all rows with formulas having adjacent items and items below the cell containing the formula


EXCEPTION There is an exception to this behaviour for Synthetic-type FSTs. In this case, the grouping's orientation is determined by the first formula to be used

- If the formula refers to items positioned above, the grouping's orientation is standard and only formulas that use adjacent items above the formula will be grouped.
- If the formula refers to items positioned below, the grouping's orientation is opposite to the standard and only formulas that use adjacent items below the formula will be grouped.

Example 1 - synthetic FST with items above the formula

	001	Revenue 1	Abbinabile
	002	Revenue 2	Abbinabile
	030	Sum 0	Formula Standard
	040	Revenue 3	Abbinabile
	050	Revenue 4	Abbinabile
	060	Revenue 5	Abbinabile
	070	Sum 1	Formula Standard

Configuration of an FST with formulas adjacent to the items involved in the formula and positioned above. Code 030 is the sum of codes 001 and 002, which are adjacent and positioned above, while Code 070 is the sum of codes 050 and 060, adjacent and positioned above




View of the FST from Figure 5, in synthetic mode, with standard grouping orientation visible on row 10 (Sum 0 with FST Code 030) and row 14 (Sum 1 with FST Code 070)

Example 2: synthetic FST with item below the formula

	030	Sum 0	Formula Standard
	010	Revenue 1	Abbinabile
	020	Revenue 2	Abbinabile
	007	Sum 1	Formula Standard
	040	Revenue 3	Abbinabile
	050	Revenue 4	Abbinabile
	060	Revenue 5	Abbinabile

Configuration of an FST with formulas adjacent to the items involved in the formula and positioned below. Code 030 is the sum of codes 010 and 020, which are adjacent and positioned below, while Code 070 is the sum of codes 040 and 050, adjacent and positioned below



View of the FST from Figure 7, in synthetic mode, with grouping opposite to the standard orientation visible on row 9 (Sum 0 with FST Code 030) and row 12 (Sum 1 with FST Code 070)

Rich Text Editor

User | <application database>.

Application database > Processes tile > select process > select Detail summary tab > select entity > Actions column > form > select form > select Rich Text cell type> ABC

Application Database > Navbar > Processes & Workflows > Process > select Process > select Detail Summary tab > select Entity > Actions column > form > select form > select Rich Text cell type> ABC

Application Database > Processes tile > select process > select Step tab > select entity > (workflow) right-click on task form > Run on web > select Rich Text cell type> ABC

Application Database > Navbar > Processes & Workflows > Process > select process > select Step tab > select entity > (workflow) right-click on task form > Run on web > select Rich Text cell type>

ABC

Purpose of the page

This panel allows you to insert Rich text referring to a cell of '*Rich text*' type Formatting is only displayed within the editor, while an unformatted preview of the text is shown on the matrix cells.

IMPORTANT: If the user selects a different cell when displaying the panel, the system automatically updates the panel with the text of the selected cell.

Panel sections

Element	Description
Button section	Shows a set of button groups to edit formatting, styling text, and inserting/editing tables (only visible on DE forms)
Rich text box	Section where the user can enter and view rich text

Working with spreading in web forms

Processes tile > select process > select step tab > select entity > (Workflow) right click task form > Run on web > Spreading tab

Using the spreading functionality

1. In the toolbar, click the desired spreading method.
2. In the work desktop, select the cell containing the total on which to run spreading and enter the new value to be distributed in the cells. Based on the structure of the form, the system distributes the new value over the rows or columns according to the spreading method set on the form.
3. To disable the spreading method, click the relevant button on the toolbar.

Edit totals with deviation values or fractions

To enter total values expressed with a deviation calculation or fraction based on the original value, enter the desired numerical or percentage value in the cell, preceded by the sequences \+, \-, *, \/. The final value will correspond to the cell's original value, plus, minus, multiplied by or divided by the value following the expression.

For example, by entering \-400 or \-40% in a cell with value 1000, the system will calculate a final value of 600.

Journals Hub

Page purpose

The Journals Hub is a tool designed to enhance the experience and efficiency of analysing and managing journals by providing access to multiple data views.

The Journals Hub is available for both entity and consolidation journals, accessible from the Process Cockpit with Entity dimension as well as from the Process Hub.


In the Process cockpit Entity dimension:

- the Journals Hub for Entity journals can be accessed from the Detail Summary tab and from the tabs by step, for both the Contributor Cockpit and the Consolidator Cockpit
- the Journals Hub for consolidation journals can be accessed from the Overview tab and from the tabs by step, but only for the Consolidator Cockpit

In the Process Hub:


- the Journals Hub for entity journals can be accessed from the Contributor's tabs by step and from the Consolidator's tabs by step
- the Journals Hub for consolidation journals can be accessed from the Consolidator's tabs by step

What it looks like



Element	Description
A	Title bar
B	Main Filter Panel
C	Journal management panel

Actions on this page

Element	Description
	**Show Dashboard**: allows you to view a dashboard for analyzing journals.
	**Show Journals Headers**: allows you to efficiently manage header attributes using the multiple selection option.
	**Show** Journals : Allows you to work on journal headers and rows within the same page, focusing on the relevant information. This is the default view.
	**Show Bulkloader**: allows you to work with journals using a spreadsheet, with the ability to enter headers and rows together.
Hide Context / Show Context	Allows you to hide/show the main filter panel.

Main Filters

Through the main filters you can filter the journals be analysed. These filters are retained even when switching between views.

Source filter	Description
Scenario /Period	Mandatory filter. A single scenario/period can be selected. By default, the scenario/period used to access the dashboard is filtered. In single-submission processes, the scenario/period linked to the process with the longest start/end date is filtered.
Entity	Only in the Entity Journals Hub Mandatory filter. A list of entities can be selected. By default, the entities selected in the cockpit are filtered. If nodes (contributor, consolidator or even non-significant) are selected in the cockpit, the child entities of these nodes are filtered.
Consolidator nodes	Only in the Consolidation Journals Hub. A list of consolidation nodes can be selected. By default, the nodes selected in the cockpit are filtered. The selected nodes are turned into a list of relationships between entities. You must select at least one of the Consolidator Nodes or Entity 1 filters.
Entity 1	Only in the Consolidation Journals Hub. A list of entity nodes can be selected. This filter is applied to the header field containing Entity 1 of the relationship. You must select at least one of the Consolidator Nodes or Entity 1 filters.
Category	Optional filter. In the Entity Journals Hub, you can select from a list of entity journal category types. In the Consolidation Journals Hub, you can select from a list of consolidation journal category types.

Clicking on the 'Apply' button applies the filters to the data in the selected view.

Once the filter has been applied, the 'Apply' button is disabled.

When the filter values in the panel are changed, the 'Apply' button is enabled again, giving the user an immediate view of a mismatch between the filter value and what is displayed in the selected view.

Dashboard View

Purpose of the page

The Dashboard view allows you to analyse the journals that match the filters in the main filter panel.

It consists of three panels.

The first panel allows the user to select the analysis driver. Three options are available:

- Balanced vs Unbalanced Always available. Selected by default.
- Posted vs Draft Only available if the journal posting functionality is enabled for the process.
- Submitted vs Unsubmitted Only available if the journal submission functionality is enabled for the process.

The second panel shows how the journals are distributed based on the selected driver.

The third panel shows how the journals are distributed based on the selected driver, broken down by entity:

- in the Journals Hub for Entity journals, by entity
- in the Journals Hub for consolidation journals, by relationship

Management view

Purpose of the page

The Management view allows the user to work on journal headers and rows on the same page.

It consists of 2 panels:

- a panel showing the list of journal headers matching the filters in the main filter panel
- a panel displaying the rows of the journal selected in the header list panel

If you prefer to use the “old” data entry mode for journals, where headers and rows are managed in separate windows, you can use the “Bulk Management” button located below the list of headers.

Journal headers

The journal headers panel allows advanced search and header management.

To insert a new journal header, use the 'Create' button; to copy, edit or delete a journal, use the appropriate icons in the header menu.

It is possible to filter the content of the header list in three different ways:

- using the 'search' field, where any filter applied acts on the journal number
- using the 'Filter' button, which allows you to filter by the various fields of the journal headers
- using the quick filters, which allow you to filter headers according to specific information

The following quick filters are available:

Symbol	Description
	Journals not balanced.
	Draft Journals.
	Journals with manual rows.
	Periodic journals
	Journals with attached documents.
	Journals with depreciation plan.
	Journals with override of standard data processing parameters.
	Journals with consolidation scenario filter
	Many-to-many-relationship journals (only for consolidation journals)

Journal rows

The rows panel of a journal allows you to work on the rows of the journal selected in the journal header list panel.

It consists of one section containing information about the selected journal, with menus that allow you to perform tasks related to the journal, and another section containing the grid for managing the rows.

The journal number and the most relevant information about the selected journal are displayed at the top.

If the journal submission feature is enabled for the process, a summary indicator of the submission status is displayed to the left of the journal number. By clicking this indicator, a window opens showing the detailed submission status by step, along with the user and the date of the last submission activity performed on that step.

To the right of the journal number, the user and the date of the last activity are displayed.

Further to the right, menus are available that open the journal details and allow you to perform tasks related to the journal.

The following menus are available:

Symbol	Description
	Utility: • Generate balance sheet amount (only for entity journals y and if the journal is not in 'draft' status) • Generate rows from template (only if the journal is not in 'draft' status) • Generate rows from another journal (only if the journal is not in 'draft' status) • Open Journal header in the following periods (only if the scenario/period is not locked and if the journal is not in 'draft' status) • Consolidate Journals (only for consolidation journals, if the scenario/period is not locked and if the journal is not in 'draft' status) • Copy Journal • Edit category • Delete journal
	Details: • Documents • Consolidation scenario (only for journals with 'Filter consolidation scenarios' option enabled) • Original and consolidated rows • Control group balancing (only if the diagnostic is enabled for the process) • Depreciation proposal (only if the event scenario has been defined for the process and if the journal is not in 'draft' status) • Periodic management (only for single-submission processes and for journals with 'Periodic journal' option enabled and not in 'draft' status)
	Overrides: • Proportional Rows • Converted and Consolidable rows • Carry forward rows on Original Scenario The menu is displayed only for journals that are not in 'draft' status

	Submission and posting: • Submit • Post • Submit and post • Submit by workflow • Reject • Unpost • Reject and unpost • Switch journal to draft mode • Show Journal log The menu is displayed only if at least one of the journal posting or journal submission features is enabled for the process.
	Diagnostic: • Diagnose • Diagnose and update log (only if the scenario/period is not locked and if diagnostic log management has been enabled for the process) The menu is displayed only if the diagnostic is enabled for the process.

Bulkloader view

Purpose of the page

The Bulkloader view is a spreadsheet listing the rows of all journals that match the filters set in the main filter panel. It also displays the most relevant header information.

Once the user has applied the main filters, the contents of the spreadsheet are loaded.

The Bulkloader allows you to:

- delete rows of different journal headers
- edit rows of different journal headers
- insert new rows on existing journal headers
- insert new rows for journal headers yet to be created; this also involves the automatic opening of journal headers



***IMPORTANT**: The bulkloader is not to be considered a data integration tool. This means it is necessary to pay attention to the volume of data being handled. More precisely:*

- If the spreadsheet contains more than 25,000 cells, a message warns the user that the loading operation may require significant system resources and asks for confirmation to proceed with the upload.
- If the spreadsheet contains more than 50,000 cells, a message warns the user that the loading operation is excessively demanding and the operation is not performed.